


I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF ENERGY.

P.S. 806 *Robert A. Andriotto*



(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS.

DATE JANUARY 16, 19 97

OPERATOR'S WELL NO. 4188

API WELL NO. 47-061-01265P

STATE COUNTY PERMIT

MINIMUM DEGREE OF ACCURACY 1 / 200 FILE NO. _____ SCALE 1"=500'

PROVEN SOURCE OF ELEVATION COMPANY NETWORK TIED INTO U.S.G.S.

STATE OF WEST VIRGINIA DEPARTMENT OF ENERGY OIL AND GAS DIVISION

WELL TYPE: OIL GAS LIQUID INJECTION WASTE DISPOSAL "GAS" PRODUCTION STORAGE DEEP SHALLOW

LOCATION: ELEVATION 1362.30' WATERSHED RANGE RUN

DISTRICT BATTELLE COUNTY MONONGALIA QUADRANGLE WADESTOWN 7.5'

SURFACE OWNER FREDA L. PHILLIPS ACREAGE 67.28

ROYALTY OWNER _____ LEASE ACREAGE _____

PROPOSED WORK: _____ LEASE NO. _____

DRILL CONVERT DRILL DEEPER REDRILL FRACTURE OR STIMULATE PLUG OFF OLD

FORMATION _____ PERFORATE NEW FORMATION _____ PLUG AND ABANDON CLEAN OUT AND REPLUG _____ OTHER _____

PHYSICAL CHANGE IN WELL (SPECIFY) _____ TARGET FORMATION NONE

ESTIMATED DEPTH Plugging the 1929 well.

WELL OPERATOR CONSOLIDATION COAL CO. DESIGNATED AGENT ROGER E. DUCKWORTH FEB 07 1997

ADDRESS P.O. BOX 100 OSAGE, WV 26543 ADDRESS P.O. BOX 100 OSAGE, WV 26543

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
P. O. BOX 100, OSAGE, WV 26543
Address

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1800 WASHINGTON ROAD, PITTSBURGH, PA. 15241
Address

FREDA L. PHILLIPS
Lease or Property Owner
R. D. #1, BOX 21 WADESTOWN, WV 26589
Address

CONSOLIDATION COAL COMPANY
Name of Well Operator
P. O. BOX 100, OSAGE, WV 26543
Complete Address

6-16-97 19
WELL LOCATION

BATTELLE
District

MONONGALIA
County

4188
WELL NO.

FREDA L. PHILLIPS
FARM

Handwritten signature

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of HARRISON

ss:

G. ANDREW LANG

and

KEVIN WRIGHT

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by CONSOLIDATION COAL CO. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28TH day of May and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
CLEANED HOLE WITH 9 7/8" BIT FROM SURFACE TO 1,313'. REDUCED HOLE TO 7 7/8" AND CLEANED 7 7/8" HOLE FROM 1313' TO 1384', TOP OF 7" CASING. REDUCED HOLE TO 6 1/4" AND CLEANED 6 1/4" HOLE FROM 1384' TO 1586'. CLEANED 9 7/8" HOLE THRU PITTSBURGH COAL LEAVING 7" CASING IN HOLE 1384' TO 1586'. RAN COAL PROTECTION STRING AS FOLLOWS: 1558.89' OF 4 1/2" CASING. CEMENT HOLE FROM 1558.89' BACK TO SURFACE USING 580 SACKS OF POZ MIX AND 165 SACKS OF THIXATROPIC CEMENT. LATCH DOWN PLUG AT 1357.26'. FLOAT VALVE AT 1390.87. CEMENT DID CIRCULATE. USED 1000 GALLONS OF MUD FLUSH. DISPLACED CEMENT WITH WATER LET SET AND BAILED DRY.				
TOTAL DEPTH: 1,586 FEET				
Coal Seams		Description of Monument		
(Name) PITTSBURGH		8' OF 4 1/2" CASING WITH PLAQUE STATING CONSOLIDATION COAL CO.		
(Name) 1,185' TO 1,191'		WELL #4188		
		PERMIT #47-61-1265-P		


and that the work of plugging and filling said well was completed on the 5TH day of JUNE 1997

And further deponents saith not.

Handwritten signatures of G. Andrew Lang and Kevin Wright

Sworn to and subscribed before me this 16TH June 1997

My commission expires: 6-29-99



Charlotte West
Notary Public

Permit No. #47-61-1265-P