

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Isaac Lemley (current Richard Francis) Operator Well No.: F2-291


LOCATION: Elevation: 1,244 (surveyed) Quadrangle: Blacksville  
District: Clay County: Monongalia  
Latitude: 14,100 Feet South of 39 Deg. 42 Min. 30 Sec.  
Longitude: 10,725 Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal Corp Coal Operator: Eastern Associated Coal Corp  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Mark A. Gouzd Coal Operator: \_\_\_\_\_  
or Owner \_\_\_\_\_

Permit Issued Date: 11/07/01



AFFIDAVIT

State of West Virginia,  
County of Monongalia ss:

Michael Hughes I and Gary C Thomas being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Randall Mick Oil and Gas Inspector representing the Director, say that said work was commenced on the 13<sup>th</sup> day of November, 2001, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 6 1/4" bit to 1,627'.			
	Ran logs with Timco and Sperry-Sun.			
	Pumped bottom plug through drill pipe using 181 sacks cement.			
	Made internal cuts in 7" casing at 913', 918', 922' and 924'.			
	Ran 1,017' of 4 1/2" vent pipe with latch down at 996' - cemented in with 105 sacks E1K cement and 570 sacks cement.			
	Added 80 sacks cement to top of hole.			
	Bailed water out of the inside of 4 1/2" pipe and checked plug @ 990' — OK.			
	Pittsburgh Coal: 912 - 919			

Description of monument: 4 1/2" Pipe with metal plate, API#, Date plugged and that the work of plugging and filling said well was completed on the 20<sup>th</sup> day of December, 2001.

And further deponents saith not. Michael Hughes I


Gary C Thomas

Sworn and subscribe before me this 8<sup>th</sup> day of January 20 02.

My commission expires: September 28, 2004.

Mark A. Gouzd  
Notary Public

Oil and Gas Inspector: Randall Mick



MONO 1422-P