



16 09 09:31a cristan.jenkins
 Rev (5-01)
 WR-98
 DATE: 11-13-09

3046220180 p.1

API # 47-6101599P

61-01599P

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Zyra Thomas Operator Well No.: F2-S-6

LOCATION: Elevation: 1491 Quadrangle: Blacksville
 District: Clay County: Monongalia
 Latitude: 11.521' Feet South of 38 Deg. 40 Min. 00 Sec.
 Longitude: 6.510' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview WV 26570 Fairview WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner

Permit Issued Date: April 9, 2009

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Monongalia ss:

Jeff Sine and Chris Thomas being first duty sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 29th day of May, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 12 1/4" bit to 763'. Cleaned out with 8 3/4" bit to 1,435'.			
	A Gamma Ray/ CCL log was performed on the hole by Timco Inc. The coal seam was from 1,084' to 1,092' based on log information. The 10" pipe was perforated between 1076' to 1100'. There was a deviation log performed by Century Wireline Services.			
	Ran 1-1/2" tubing and pumped the bottom plug with 80 sacks of ETK expanding cement. The top of the bottom plug is 1200' deep.			
	Ran 1,200' of 4-1/2" tubing and pumped the top plug with 620 sacks of ETK expanding cement. Swabbed water off hole. Latch down plug at 1,177'.			


Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 25th day of June, 2009.

And further deponents saith not.

Sworn and subscribe before me this 13th day of November, 2009
 My commission expires: 2017

Oil and Gas Inspector: [Signature]

[Signature]
[Signature]
 Notary Public
[Signature]



RECEIVED
 Office of Oil & Gas

JUN 12 2012

WV Department of
 Environmental Protection

06/22/2012