

Rev (5-01)
WR-38
DATE: 05-15-12

API # 47-6101634P

61-01634P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Quicke, Penny Operator Well No.: F2- S54

LOCATION: Elevation: 1,258' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 14.664' Feet South of 39 Deg. 37 Min. 30 Sec.
Longitude: 8.563' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner

Permit Issued Date: September 22, 2011

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Kevin H. Gump and Garrett H. Hickman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 3rd day of January, 2012, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Pulled 3124.5' of tubing. Pulled 3173.7 feet of 3" pipe. Ran 4" hole opener to 3133', then pumped in bottom plug of 40 sacks of expanding cement. Ran 4" hole opener to 2203', then pulled 1931' of 5" pipe. Then they pumped 172 sacks of expanding cement. Logged the hole down to 1220'. Cut and pulled 1179' of 7" pipe. Cleaned out with 8" bit back down to 1,100'				
Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 752'. The hole deviated 7.6 feet at the coal seam. There was 10" pipe from 542' to 1116'. The pipe was shot every 50 feet from 1,100' to 550'.				
There they pumped an expanding cement plug of 615 sacks from 1220 to 86 feet deep.				
Then the hole was topped off with 80 more sacks of expanding cement.				

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 14th day of March, 2012.

And further deponents saith not. Kevin H. Gump


Garrett H. Hickman

Sworn and subscribe before me this 15th day of May, 2012

My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: Sam Ward



RECEIVED
Office of Oil & Gas

JUN 19 2012