

Rev (5-01)
WR-38
DATE: 02-20-12

API # 47-6101638P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Latocha, Michael Operator Well No.: F2-S20

LOCATION: Elevation: 1,658' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 14.349' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 7.794' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS _____

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner: 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner _____

Permit Issued Date: December 15, 2011

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Jeff Sime and Chris Thomas being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 27th day of December, 2011, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
				Cleaned out with a 6 1/2" bit to 600 feet deep. Cleaned out with a 12 1/2" bit to 298'. Ran 330' of 8" pipe. Put on 6" bit and cleaned to 1500' deep.
				Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 1,231'. The hole deviated 19.9' at the coal seam. There was 7" pipe from 318' to 1,500' deep.
				Used 7" spears to fish out 12 pieces of 7" pipe. Ran 10" watermelon hole opener to 565' deep. Ran 10" pipe over 7 inch pipe to 600'. Used 7" spear and pulled 29 joints of 7" pipe. Pulled 10" pipe. Ran 13" bit to 1196'. Ran 12 1/4" flat bottom milled to 1241 (which milled the pipe through the coal seam). There was an expanding cement plug from 1,500 feet deep to 1,100 feet deep. Then from 780' to the surface, the rest was pumped with regular cement.
				The plug was pumped by BJ Hughes.

RECEIVED

Office of Oil & Gas

JUN 12 2012

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 6th day of February, 2012.


And further deponents saith not.

Chris Thomas

Notary Public

Edward Y. Hoy

Notary Public



Sam Ward 2/21/2012

06/22/2012