

Rev (5-01)  
WR-38  
DATE: 04-25-12

API # 47-6101639P

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Albert, Kenneth Operator Well No.: F2- 928

LOCATION: Elevation: 1,392' Quadrangle: Blacksville  
District: Cley County: Monongalia  
Latitude: 1,108' Feet South of 39 Deg. 37 Min. 30 Sec.  
Longitude: 8,140' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC  
1044 Miracle Run Road or Owner: 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner \_\_\_\_\_

RECEIVED  
Office of Oil and Gas

Permit Issued Date: February 08, 2012

NOV 1 9 2014

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

WV Department of  
Environmental Protection

Jeff Sinc and Ken Hughes being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 1<sup>st</sup> day of March, 2012, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cleaned out with a 28" bit to 77'. Ran a 12" mill down to 90'. Ran 90' of 13" pipe. Fished out a 7' and 9' long piece of 7" pipe. Ran 180' of 10" pipe. Ran 6 1/2" bit to 1170'. Pulled the 10" and 13" pipes.				
Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 955'. The hole deviated 2.2 feet at the coal seam. There is 6 5/8" pipe through the coal seam. It was shoot by Timco at 1155, 1105, 1055, 1005, 955, 905, 855.				
There is a 357' thick bottom plug made of expanding cement from 1,167' to 810' feet.				
The rest of the hole was filled with regular cement from 810' to the surface.				

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 25<sup>th</sup> day of April, 2012.


And further deponents saith not.

Jeff Sinc  
Ken Hughes

Sworn and subscribe before me this 25<sup>th</sup> day of April, 2012  
My commission expires: July 7, 2017

Notary Public  
S. D. W...

Oil and Gas Inspector: \_\_\_\_\_



11/21/2014