

Rev (5-01)  
WR-38  
DATE: 10-01-12

API # 47-6101648P

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Kathy Ice Operator Well No.: F2- S38

LOCATION: Elevation: 1,350' Quadrangle: Grant Town  
District: Clay County: Monongalia  
Latitude: 2,001' Feet South of 39 Deg. 37 Min. 30 Sec.  
Longitude: 9,631' Feet West of 80 Deg. 12 Min. 30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC  
1044 Miracle Run Road or Owner 1044 Miracle Run Road  
Fairview, WV 26570 Fairview, WV 26570

Agent: Edward Y. Hoy Coal Operator or Owner \_\_\_\_\_

Permit Issued Date: July 11, 2012

RECEIVED  
Division of Oil and Gas  
NOV 18 2014

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

WV Department of  
Environmental Protection

Kenneth M. Guinn and Jeff Sime being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Sam Ward, Oil and Gas Inspector representing the Director, say that said work was commenced on the 2<sup>nd</sup> day of July, 2012, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Pulled 3,336.10' of 2" tubing. Cleaned out with 4" tools down to 3050'. Pulled 2,006' of 5" casing. Pulled 856.20' of 7" casing.				
Logged the hole with Century Wireline Service. The bottom of the Pittsburgh coal seam is 899'. The hole deviated 7.5 feet at the coal seam. Based on logs, there is 7" casing in the Pittsburgh coal seam.				
There is 7" pipe from 855' to 1116'. This pipe was shot by Timco every 30 feet.				
There is a bottom hole plug of cement from 3050 to 1,140'. Then an expanding cement plug from 1,116' to 772'. Then from 772' to surface it was filled with cement.				

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 14<sup>th</sup> day of September, 2012.

And further deponents saith not. Kenneth M. Guinn


Jeff Sime

Sworn and subscribe before me this 1<sup>st</sup> day of October, 2012

My commission expires: July 7, 2017

Notary Public

Oil and Gas Inspector: S. P. D. Bennett



11/21/2014