

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Mason S. Henderson Operator Well No.: 8163
LOCATION: Elevation: 1,193.58' Quadrangle: Hundred, WV
District: Battelle County: Monongalia
Latitude: 39.668313 Feet South of 39 Deg. 40 Min. 5.93 Sec.
Longitude: -80.390101 Feet West of 80 Deg. 23 Min. 24.36 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Coal Operator West Virginia Land Resources
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent Gayne Knitowski
Permit Issued Date 2-19-25

Coal Operator
or Owner

RECEIVED
Office Of Oil and Gas

OCT 20 2025

WV Department of
Environmental Protection

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew Yearsley and John Campbell being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 20th day of July, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thompson's Green Dye & Gas Blocker	1,218'	732'	8 5/8" Casing - None	Unknown
Expandable Cement	732'	Surface	16" Conductor - None	20'

Description of monument: 77" of 7" casing with company name, well #, and date completed. and that the work of plugging and filling said well was completed on the 1st day of August, 2025.


And further deponents saith not.

Matthew A. Yearsley

John Campbell

Sworn and subscribe before me this 22nd day of September, 2025

My commission expires: August 13, 2029



Kerri McCormick
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Gayne Knitowski
Digitally signed by Gayne Knitowski Date: 2025.10.10 16:04:32 -0400

Title: Inspector

10/24/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
KANDY L. & RANDY L. EARL
Lease or Property Owner
249 Blacks Run Rd. Core, WV 26529
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Hundred, WV 7.5'
Well Location
Battelle
District
Monongalia
County
8163
Well No.
MASON S. HENDERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____ Gayne Knitowski

Gayne Knitowski
Digitally signed by
Gayne Knitowski
Date: 2025.10.10
10:05:16 -0400


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and **JOHN CAMPBELL**, being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of July, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from surface to 240'. Reduced to 9 7/8" bit. Cleaned 9 7/8" hole from 240' to 878'. Tagged pre-existing 8 5/8" casing. Reduced to 7 7/8" bit. Cleaned 7 7/8" hole through 8 5/8" casing to a DEP approved depth of 1,218'. Cleaned 7 7/8" hole through Pittsburgh Coal Seam from 932' to 940'. Made a diligent effort to remove 8 5/8" casing by pulling 150% string weight. All attempts were unsuccessful. Left unknown amount of 8 5/8" casing in well from 878' to unknown depth. Cut remaining 8 5/8" casing at, 1,140', 1,090', 1,040', 990', 950', 945', 940', 938', 936', 934', 932', 927', 922', 882'.	8 5/8"	None	Unknown	
		16"	None	20'
Cemented hole from 1,218' to surface as follows: From 1,218' to 732' w/ 185 sack of Thixotropic Cement w/ Green Dye and Gas Blocker. From 732' to surface with 425 sacks of Expandable Cement. Cement did circulate at surface. Left 20' of 16" conductor pipe from surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	932' – 940'	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1st day of August, 2025



Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Sworn to and subscribed before me this 22nd day of September 2025

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-061-01979
Well No. 8163
Latitude: 39° 40' 5.93" N
Longitude: 80° 23' 24.36" W

RECEIVED
Office of Oil and Gas

OCT 20 2025

WV Department of
Environmental Protection

10/24/2025