LATITUDE 39° 40' 00"

80° 12' 30" LONGITUDE

7.5'

7'5 OGIS topo location

7.5' loc 1.99S / 1.24W

15' loc (calc.) 1.99S / 3.46W

Company _____

Farm _____

Quad Blacksville

County Monongahela

District Clay

WELL LOCATION MAP

File No. 061-65A

File No. [illegible]

Plat showing the location of Well No. 2. of the Pure Oil Co. of Newark, Ohio. to be abandoned on the Catherine & Noah Ammons farm containing 102.5 Acres, located in Clay District, Monongalia County, West Virginia.



Engineers Certificate.

I the undersigned hereby certify that this map is correct and shows all the information to the best of my knowledge and belief, required by the oil and gas section of the Mining Laws of West Virginia.

[illegible]
Engineer.

Acknowledged before me a Notary public in and for Monongalia County, West Virginia this 27th day of June 1922.
My Commission expires April 16, 1927.

[illegible]
Notary Public.

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

Development File No. [illegible] Well No. 8

The Pure Oil Company, of [illegible], Ohio

on the G. & E. [illegible] Farm

containing 1180 acres. Location

Clay District, in Monongalia County, West Virginia

The surface of this above tract is owned in fee by G. & E. [illegible]

of [illegible], W. Va. address, and the mineral rights are owned by

R. W. [illegible] of [illegible], Pa.

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit

No. issued by the West Virginia Department of Mines, Oil and Gas Division

Oct. 7, 1909 19[illegible]

Elevation of surface at top of well. Spirit Barometric.

The number of feet of the different sized casings used in the well.

[illegible] feet 10" casing size. Wood-conductor.

[illegible] feet [illegible]" size, cog. [illegible] feet 6 5/8" sized cog.

[illegible] feet 5 3/16" size, cog. feet sized cog.

feet size, cog. feet sized cog.

packer of size, set at

packer of size, set at

, in casing perforated at feet to feet.

, in casing perforated at feet to feet.

Coal was encountered at 705 feet; thickness 4 ft. inches, and at 1000 feet; thickness 5 ft. inches; and at 1118 feet; thickness 6 ft. inches.

Liners were used as follows: (Give details) Liner set at [illegible]?

June 30, 1[illegible]

Date.

The [illegible] Oil Co.

Approved By Ford Willis, Owner.

Division Superintendent

By (Title)

FIE No. [illegible]

The Pure Oil Company

Box 551, Newark, Ohio Address

Well No. 2 on S. & H. Ammons

File - Abandonment No. 22

COMPLETION DATA SHEET
No. 2
FORMATION RECORD

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Bluff Sand				680	725			
Fairview Coal				755	759			
Mapletown Coal				1020	1025			
Pgh. Coal				1115	1118			
Little Dunkard				1452	1455			

Well was not shot at _____ feet; well was shot at _____ feet.

Fresh water at _____ feet; fresh water at _____ feet.

Well was producing bbls. day

June 30, 1955 Date

The Pure Oil Company

Approved By [signature]

Division Superintendent

NOTE: All bottom formations must be noted as indicated above and all hard rocks and oil and gas sands must be recorded under their proper geological names in the column as well as any fresh water encountered with in the column for such items.

The Pure Oil Company

Box 551, Newark, Ohio Address

Well No. 2 S. S. A. H. Amos

File Abandonment No. 22

COMPLETION DATA SHEET
No. 2
FORMATION RECORD

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Bluff Sand				680	705			
Fairview Coal				705	709			
Hopletown Coal				1020	1025			
Pgh. Coal				1112	1116			
Little Dunkard				1428	1428			
Big Dunkard				1638	1658			
Gas Sand				1880	1885			
Salt Sand				1900	2150			5 Bailers water at 1900
Break in Salt Sand				1980	1985			Hole full water at 2000
Maxon Sand				2260	2275			
Little Lime				2320	2340			Water & show oil 2319 to 2325'
Pencil Cave				2340	2355			
Big Lime				2355	2416			
Big Injun Sand				2416	2506			Oil Pay - 2506'
Gantz Sand				2900	2920			
50' Sand				2940	2955			
30' Sand				3110	3130			
Gaspell Run Sand				3265	3275			5th Sand - 3271 3266
Golden Stray				3315	3340			
Golden Sand				3320	3337			
TOTAL DEPTH				3334				

Well was not shot at 2325-2340 Date; well was shot at _____ Qts.

Fresh water at 1900 Date; fresh water at 2325 Qts.

Well was producing oil bbls. daily

June 20, 1928 Date

Approved: Thomas W. Willey
Division Superintendent

NOTE: All bottom formations must be noted as indicated above and all formations and oil and gas sands must be recorded under their proper geological names to the extent as well as any fresh water encountered and be shown in the table.

FORM W-8

AFFIDAVIT IN TRIPLICATE TO TIME AND MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION FILE NO. 28

R. W. Brown,
COAL OPERATOR OR OWNER

Uniontown, Pa.
ADDRESS

COAL OPERATOR OR OWNER

ADDRESS

G. & N. Amons (Owner)
COAL OPERATOR OR OWNER

Fairview, W. Va.
ADDRESS

The Pure Oil Company,
NAME OF WELL OPERATOR

Box 561,
Newark, Ohio
COMPLETE ADDRESS

Sept. 27, 19 33

WELL AND LOCATION

Clay District

Monongalia County

Well No. 2

G. & N. Amons Farm

AFFIDAVIT TO BE MADE IN TRIPLICATE, ONE COPY TO BE MAILED BY REGISTERED MAIL TO THE DEPARTMENT, ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ABOVE NAMED AT THEIR RESPECTIVE ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia } ss:

Hardie Conway and Howard Darrah
being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by The Pure Oil Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11th day of July, 19 33, and that the well was plugged and filled in the following manner:

Manner in which sand was plugged:
Pulled 4" liner. Filled hole from bottom 3054' with non-porous material to 3511' - 50' above fifth sand. Set wood plug 3511' - 3508'. Cement 3508' - 3408' sealing Fifth sand. Filled with non-porous material 3408' - 2000' - 50' above Gantz Sand. Set wood plug 2000' - 1977'. Cement 1977' - 1907' sealing Gordon, Gordon Stray, Campbell Run, Thirty Foot, Fifty Foot and Gantz Sands. Filled with non-porous material 1907' - 1500'. Removed 8 5/16" casing. Filled with non-porous material to 1500' - 50' above Big Injun Sand. Set wood plug 1500' - 1498'. Cement 1498' - 1398' - sealing Big Injun Sand. Filled with non-porous material 1398' - 1340'. Set

Manner in which sand was plugged:
wood plug 1340' - 1337'. Cement 1337' - 1235' - sealing Keener Sand. Filled with non-porous material to 1180'. Removed 6 5/8" casing. Filled with non-porous material to 1000' - 50' above Salt Sand. Set wood plug 1000' - 1977'. Cement 1977' - 1907' sealing Salt Sand. Filled with non-porous material to 1016'. Removed 8" casing. Filled with non-porous material 1016'-1400'. Set plug 1400' - 1390'. Cement 1390' - 1290' sealing Big and Little Dunkard Sands. Filled with non-porous material 1290' - 1140'. Cemented 1140' - 1000' - 50' above Pgh. Coal. Filled with non-porous material 1000' - 1000', 50' below Waynesburg Coal. Cemented 1000' - 1000', 50' above Waynesburg Coal. Filled with non-porous material 1000'-700', 50' below Fairview Coal. Cemented 700'-700' - 50' above Fairview Coal. Filled with non-porous material 700' to Surface. Erected marker as described in Rule 18, Regulations.
All work done in workmanlike manner

THE ABOVE DESCRIPTION HAS BEEN MADE AND IS IN ACCORDANCE WITH THE PROVISIONS OF SECTION 10, ARTICLE 4, CHAPTER 22 OF THE CODE

and that the work of plugging and filling said well was completed on the 8th day of September, 19 33.

And further deponents saith not.

Hardie Conway
Howard Darrah

Sworn to and subscribed before me this 16th day of Sept., 1933

P. J. Christler

My Commission expires

Notary Public

Rec. Sept. 19, 1933
File W-10-67-Cl.

Form G-6

AFFIDAVIT IN TRIPLICATE TO TIME AND MANNER OF PLUGGING AND FILLING WELL

(Required by Section 9, Article 4, Chapter 22 of the Code)

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION FILE NO. [illegible]

E. V. [illegible]
COAL OPERATOR OR OWNER

Uniontown, Pa.
ADDRESS

COAL OPERATOR OR OWNER

ADDRESS

G. & E. [illegible] (owner)
COAL OPERATOR OR OWNER

Fairview, W. Va.
ADDRESS

The Pure Oil Company
NAME OF WELL OPERATOR

[illegible]

[illegible], Ohio
COMPLETE ADDRESS

Sept. [illegible], 19[illegible]

WELL AND LOCATION

Clay District

Monongalia County

Well No. 8

G. & E. [illegible] Farm

AFFIDAVIT TO BE MADE IN TRIPLICATE. ONE COPY TO BE MAILED BY REGISTERED MAIL TO THE INSPECTOR, ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ABOVE NAMED AT THEIR REPORTED ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA,
COUNTY OF Monongalia } ss:

Hardie Conaway and Howard Darrah
being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by The Pure Oil Company, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22th day of July, 19[illegible], and that the well was plugged and filled in the following manner:

[illegible]: Pulled 6" line. Filled hole from bottom [illegible]' with non-gaseous material to [illegible]' - [illegible]' above [illegible] sand. Set wood plug [illegible]' - [illegible]'. Cement [illegible]' - [illegible]', sealing [illegible] sand. Filled with non-gaseous material [illegible]' - [illegible]' - [illegible]' above Gantz Sand. Set wood plug [illegible]' - [illegible]'. Cement [illegible]' - [illegible]', sealing Gantz, Gordon Stray, Gordon Big, Thirty Foot, Forty Foot and Gordon Sands. Filled with non-gaseous material [illegible]' - [illegible]'. Inserted 8 5/8" casing. Filled with non-gaseous material to [illegible]' - [illegible]' above Big Injun Sand. Set wood plug [illegible]' - [illegible]'. Cement [illegible]', sealing Big Injun Sand. Filled with non-gaseous material [illegible]' - [illegible]'. Set wood plug [illegible]' - [illegible]'. [illegible] - [illegible] - sealing Berea Sand. Filled with non-gaseous material to [illegible]'. Inserted 6 5/8" casing. Filled with non-gaseous material to [illegible]' - [illegible]' above Salt Sand. Set wood plug [illegible]' - [illegible]'. Cement [illegible]' - [illegible]', sealing Salt Sand. Filled with non-gaseous material to [illegible]'. Inserted [illegible]" casing. Filled with non-gaseous material [illegible]' - [illegible]'. Set plug [illegible]'-[illegible]'. Cement [illegible] - [illegible]', sealing Big and Little Dunkard Sands. Filled with non-gaseous material [illegible] - [illegible]'. Cemented [illegible] - [illegible] - [illegible]' above Pgh. Coal. Filled with non-gaseous material [illegible]' - [illegible]' - [illegible]' below Sewickley Coal. Cemented [illegible]'-[illegible]', [illegible]' above Sewickley Coal. Filled with non-gaseous material [illegible]' - [illegible], [illegible]' below Waynesburg Coal. Cemented [illegible]'-[illegible]', [illegible]' above Waynesburg Coal. Filled with non-gaseous material [illegible]' to surface. Inserted marker as described in Rule 10, 1935 Regulations. All work done in workmanlike manner

(THE ABOVE DESCRIPTION MUST BE IN DETAIL AND IN ACCORDANCE WITH THE PROVISIONS OF SECTION 10, ARTICLE 4, CHAPTER 22 OF THE CODE)

and that the work of plugging and filling said well was completed on the [illegible] day of September, 19[illegible].

And further deponents saith not.

Hardie Conaway
Howard Darrah

Sworn to and subscribed before me this 30th day of Sept., 19[illegible].