

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES,
OIL AND GAS DIVISION

334

WELL RECORD

Permit No. **282-A**


Oil or Gas Well **Gas**
(KIND)

Company **Hope Natural Gas Company.**
Address **445 West Main St. Clarksburg, W. Va.**
Farm **I.B. Wright** Acres **44**
Location **5079** (circled) **1405'**
Well No. **clay** Elevation **Monongalia**
District _____ County _____
The surface of tract is owned in fee by _____
Address _____
Mineral rights are owned by _____
Address _____
Drilling commenced **May 1, 1918**
Sept. 14, 1918
Drilling completed **8-21-18** **3344** **3351**
Date Shot _____ From _____ To _____
With _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil **Reported in coal seam** _____ bbls., 1st 24 hrs.
Fresh water **1850** feet _____ feet
Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13	979'	Pulled	
10	1690	1690	Size of
8 1/4	2148'	2148'	
6 1/2	3171'	3171'	Depth set
5 3/16			
3	3356	Pulled	Perf. top
2			Perf. bottom
Liners Used			Perf. top
	Not cemented		Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
COAL WAS ENCOUNTERED AT **365'** **72"** FEET INCHES
_____ FEET INCHES FEET INCHES
_____ FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapletown Coal			965	971			
Pittsburgh Coal			1428	1480			
Little Dunkard sand			1520	1560			
Big Dunkard sand							
Gas Sand			1635	1668			
First Salt sand			1685	1746			
Second Salt sand			1860	1960	water	1850	
Maxon sand			1975	2000			
Little Lime			2111	2141			
Bencil cave			2141	2146			
Big Lime			2146	2204			
Big Injun sand			2204	2395	gas	2315	
Essea sand			2460	2506			
Gantz sand			2780	2816			
Fifty Foot sand			2837	2900			
Thirty Foot sand			2930	2980			
Gordon sand			3167	3170			
Fourth sand			3235	3247			
Fifth sand			3310	3333			
Bayard sand			3342	3352	gas	3348-3350	
		Total Depth		3356			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date August 27, 1942, 194

APPROVED Hope Natural Gas Company., Owner

By [Signature] Gen. Sup't.
(Title)