


Latitude

Longitude



Topo Location

7.5' Loc. \_\_\_\_\_ 15' Loc. \_\_\_\_\_  
 \_\_\_\_\_ (calc.) \_\_\_\_\_

Company Duron Moe.  
 Farm Wm Starks #2  
 15' Quad \_\_\_\_\_  
 (sec.)  
 7.5' Quad Osage  
 District Chy

WELL LOCATION PLAT

County 061 Permit 30556

Clay District, Monongalia County, W. Va.  
 By Dunn-Mar Oil & Gas Co., Waynesburg, Pa.  
 Abandoned under permit Mon-.....-A?  
 On.....acres.

Elevation, .....<sup>+</sup> ft.

Drilling completed August 1927.

10" casing, 454'; 8", 1132'; 6", 1645'; all left in.

Coal was encountered at 100-105, 230-235, and 438-447'.

Oil well. Record to Dept. of Mines stamped Sept. 27, 1952.

Record to RCT from Mrs. Griffith June 10, 1952. Old File No. 603.

	Top.	Bottom.
Waynesburg Coal	100	- 105
Harpistown (Sewickley) Coal	230	- 235
Pittsburgh Coal	438	- 447
Murphy Sand	670	- 725
Gas Sand	1130	- 1180
Salt Sands	1240	- 1420
Big Lime	1640	- 1680
Big Injun Sand (oil, 1780')	1690	- 1790
Total depth		1905



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

603

MON-556-A

WELL RECORD

Permit No.

Oil or Gas Well

(KIND)


Company Dunn-Mar Oil & Gas co.  
 Address Waynesburg, Pa.  
 Farm Wm Shanks Acres \_\_\_\_\_  
 Location (waters) \_\_\_\_\_  
 Well No. Two Elev. \_\_\_\_\_  
 District Clay County Monongalia  
 The surface of tract is owned in fee by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced \_\_\_\_\_  
 Drilling completed Aug. 1927  
 Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_  
 Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10		454	Size of
8 1/2		1132	
6 5/8		1645	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT 100 FEET 60 INCHES  
230 FEET 60 INCHES 438 FEET 108 INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Waynesburg Coal			100	105			
Mapletown Coal			230	235			
Pgh. Coal			438	447			
Murphy Sand			670	725			
Gas Sand			1130	1180			
Salt Sands			1240	1420			
Big Lime			1640	1680			
Big Injun			1690	1790	oil 1780		
Total Depth				1905			



PROPOSED MANNER OF PLUGGING AND FILLING WELL

(Pursuant to Order and Regulations)

WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS DIVISION  
WORK ORDER

Well to be plugged and filled as follows:

- Clay 1905 to ~~1875~~ <sup>1875</sup> - 30' below 4-1/2" casing  
 Cement 1875 to 1800 ~~1875~~ <sup>1875</sup> - 1800' - 5' crushed stone at 1875'  
 Bridge 1450 Stone & Cement ~~1875~~ <sup>1875</sup> to 1800' casing
- Clay 1440 to ~~1380~~ <sup>1380</sup> ~~1380~~ <sup>1380</sup> - 30' below 4-1/2" casing  
 Cement 1380 to 1320 ~~1380~~ <sup>1380</sup> - 1320' - 5' crushed stone at 1380'  
 Bridge at 800 "stone & cement" ~~1380~~ <sup>1380</sup> to 795'
- Clay 795 to 487, Start 10" casing. Test for gas. If found  
 put in 2" vent. If not found plug as follows  
 Cement 487 to 418
- Clay 418 to 360 ~~418~~ <sup>360</sup> - 30' below Naphtholene Coal  
 Cement 360 to 310 ~~360~~ <sup>360</sup> - 310'
- Clay 310 to 125  
 Cement 125 to 80
- Clay 80 to Surface, sect Marker. OK. by Mr. Flagel

IF 2" VENT IS SET - CHECK THE COAL SHOW FROM  
 30' BELOW TO 80' ABOVE EACH SHOW - SHOWS THIS.

To the Department of Mines  
 Coal Owner or Operator,  
 Lessee or Property Owner.

Comments:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner as the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

\_\_\_\_\_  
 Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owner or interested by the Department of Mines in the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this

7th day of ~~November~~ <sup>November</sup> 1952 . . . 11

DEPARTMENT OF MINES  
 Oil and Gas Division

By C. Hall

