

Latitude 39° 40'

#2 4.15 W

#4 4.71 W

Surf: Wash Devine, Rt #2 Fairview, W.Va.
 Coal: Little Kanawha Syndicate
 S/o Dunlap, Brady P.O. Box 488
 Summersville, W.Va.

- New Location
- Drill Deeper
- Abandonment

Map N71E N15 E21

Company South Penn Natural Gas Co.
 Address Parkersburg, W.Va.
 Farm David Haught
 Tract _____ Acres 130[±] Lease No. 28017
 Well (Farm) No. 2 & 4 Serial No. _____
 Elevation (Spirit Level) (2) 1326.63 ft. (4) 1428.84 gr.
 Quadrangle Blacksville
 County Monongalia District Clay
 Engineer A. C. Hillbert
 Engineer's Registration No. 2534
 File No. 1294 Drawing No. _____
 Date May 27, 1959 Scale 1"=800'

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP

FILE NO. 7704-628-A #2
7704-629-A #4

- + Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.
- Denotes one inch spaces on border line of original tracing.

JD

Latitude

39°42'30"

Longitude

2.825
1.98w

Topo Location

7.5' Loc. _____ 15' Loc. _____
_____ (calc.) _____

Company South Perrin Nat Gas

Farm David Haught #4

15' Quad _____
(sec.)

7.5' Quad Blacksville

District Clay

WELL LOCATION PLAT

County 061 Permit 30629



664

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle Bladenville

Permit No. 679A

WELL RECORD

Oil or Gas Well _____ (KIND)

Company SOUTH PENN NATURAL GAS COMPANY
Address P. O. Box 1280, Parkersburg, W. Va.
Farm David Haught Acres 130
Location (waters) Branch of Days Run
Well No. 4 Elev. 1428.84
District Clay County Monongalia
The surface of tract is owned in fee by Wash Devine
Rt. #2, Address Fairview, W. Va.
Mineral rights are owned by John W. Devine, et al.
R. F. D. No. 2 Address Fairview, W. Va.
Drilling commenced Sept. 25, 1905
Drilling completed Nov. 25, 1905
Date Shot 3 Times From _____ To _____
With 10 Qts; 16 Qts. & 20 Qts.
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil 65 bbls., 1st 24 hrs.
WELL ACIDIZED _____
WELL FRACTURED _____

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			<u>Larkin Bottom Hole</u>
<u>13 1/4"</u>	<u>178'</u>	<u>86'-8"</u>	Size of
10	<u>1435'</u>	<u>168'-2"</u>	<u>5 3/16" x 6 5/8"</u>
8 1/4	<u>2024'</u>	<u>None</u>	Depth set
6 3/8	<u>2218'</u>	<u>2218'</u>	
5 3/16	<u>2415'</u>	<u>2415'</u>	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom


CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 1020 FEET ? INCHES
1116' FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

RESULT AFTER TREATMENT _____
ROCK PRESSURE AFTER TREATMENT _____
Fresh Water _____ Feet _____ Salt Water _____ Feet _____

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Conductor				<u>16</u>			
Maplewood Coal			<u>1020</u>				
Pittsburgh Coal			<u>1116</u>				
Little Dunkard			<u>1510</u>	<u>1535</u>			
Big Dunkard			<u>1600</u>	<u>1640</u>			
Gas Sand			<u>1875</u>	<u>1910</u>			
Salt Sand			<u>2000</u>	<u>2120</u>			
Big Lime			<u>2316</u>	<u>2375</u>			
Big Injun			<u>2375</u>				
TOTAL DEPTH				<u>2487</u>	<u>Gas</u> <u>Oil</u>	<u>2380</u> <u>2480</u>	

APR 6 1962 (over)



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date June 3, 1959, 19

APPROVED SOUTH PENN NATURAL GAS COMPANY, Owner

By George W. Wilman
George W. Wilman, District Agent