STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Ralph Westfall			_Operator Well		
LOCATION:	Elevation: 1221.5		Quadrangle:	Valley Grove Ohio	
	District: Tridelphia Latitude: Longitude:	Feet South o	County: f <u>40</u> Deg. <u>4</u> f <u>-80</u> Deg	Min. 43.68	Sec. 016 _ _{Sec.}
Well Type: O	IL GAS _X	<u> </u>			
· ·	184 Schoolhouse Lane Valley Grove, WV 26060		ner 184 Sc	Tunnel Ridge LLC 184 Schoolhouse Lane Valley Grove, WV 26060	
1180111			Operator		
well operator,	rsley ss: and ey are experienced in the	Kevin S. Wright e work of plugging work of plugging	and filling the abo	gas wells and were e	worn according to law depose employed by the above named aid work was commenced on ollowing manner:
TYPE	FROM	ТО	PIPE RE		LEFT
Expandable Cemer	nt 886'	633' Surface			
10 3/4" Casing 16" Conductor	407' Surface	653' 40'	0		246'
	f monument: 77" of 7" cas completed on the 15th	ing with company name _ day of _November	, well #, API#, and dat	e cemented and that t	he work of plugging and filling
	deponents saith not.	Kevin S	A. Yearsley S. Wright		OFFICIAL SEAL NOTARY PUBLIC STATE OF WEST VIRGINIA Christopher Andrew Willis 76 Starling Estates Morgantown, West Virginia 26508 My Commission Expires June 8, 2027
	expires: Sune 8		Muy	20 <u>22</u> & Alloholic lotary Public	
Affidavit review	ed by the Office of Oil a	nd Gas: <u>Strade</u>	r Gower 11/2	2/2022 Title	: Oil and Gas Inspector

FORM WR-38 (Affidavit of Plugging)

WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION **OIL AND GAS WELLS DIVISION**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

TUNNEL RIDGE LLC

TUNNEL RIDGE LLC Name of Well Operator

Coal Operator or Owner

184 SCHOOLHOUSE LANE, VALLEY GROVE WV 26060 184 SCHOOLHOUSE LANE, VALLEY GROVE WV 26060

Address

Complete Address

TUNNEL RIDGE LLC

VALLY GROVE

Coal Operator or Owner 184 SCHOOLHOUSE LANE, VALLEY GROVE WV 26060 Well Location

Address

TRIDELPHIA

SCOTT BLACK

District **OHIO**

Lease or Property Owner

County

1775 STOOLFIRE ROAD VALLEY GROVE WV 26060

WESTFALL #1

Address

Well No. PH WESTFALL Farm

Strader Gower

11/22/2022

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of MONONGALIA ss: MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Tunnel Ridge LLC well operator, and participated in the work of plugging and filling the above well, that said work was

commenced on the 24th day of October, 2022 and that the well was plugged in the following manner:

Casing Casing Sand or Zone Casing/Tubing Size **Pulled** Left In Filling Material Record **Formation** 10 3/4" Casing O' 246' Cleaned 12 1/4" hole from surface to 407'. Tagged top of 10 3/4" casing at 407'. Reduced the hole to 9 7/8" at 407'. Cleaned 9 7/8" hole through 10 3/4" casing from 407' to total depth of 885'. Tagged 40' O' cement plug at 885'. Cleaned a 9 7/8" hole through the Pittsburgh 16" Conductor Coal Seam (603.7'-609.5'). Attempted to remove 10 3/4" casing by pulling 150% string weight. All attempts were unsuccessful. Left 246' of 10 3/4" casing in hole from 407' to 653'. Cut the remaining 10 3/4" casing at the following depths: 621', 611.5', 609', 608', 606.5', 605', 603.5', 600', 595', 555', 504.5'. Perforated 10 3/4" casing with 6 shots at 616'. Left 40' of 16" conductor pipe in the hole from the surface to 40'. Cemented the hole from 885' to surface as follows: From 885' to 633' with 170 sacks of Expandable Cement, tagged top of Expandable Cement plug at 633'. Cemented the hole from 633' to surface with 370 sacks of Expandable Cement. Cement did circulate at the surface. A total of 500 sacks of cement were used to fill the hole from 855' to surface. **Coal Seams Description of Monument** 603.7' - 609.5' 77" of 7" casing w/ company name, well number, Pittsburgh permit number and date cemented stated on 7' casing. Well marker will be attached to cement plug at ground level.

... and that the work of plugging and filling said well was completed on the 15h day of November, 2022

And further deponents saith not.

OFFICIAL SEAL NOTARY PUBLIC STATE OF WEST VIRGINIA Christopher Andrew Willis 76 Starling Estates organtown, West Virginia 26508 My Commission Expires June 8, 2027 Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright Kevin S. Wright

Notary Public

Sworn to and subscribed before me this 18 day of November, 2022

12/16/2022

My commission expires: Tune 8, 2027

Permit No. 47-069-00018

Well No. Westfall #1 Latitude: 40° 4' 43.68"N

Longitude: -80° 32' 7016"W