

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
www.dep.wv.gov

PERMIT MODIFICATION APPROVAL

January 09, 2014

CHESAPEAKE APPALACHIA, L.L.C. POST OFFICE BOX 6070 CHARLESTON, WV 25362

Re: Permit Modification Approval for API Number 6900114 , Well #: ROY FERRELL OHI 10H Modified Casing

Oil and Gas Operator:

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

Please call James Martin at 304-926-0499, extension 1654 if you have any questions.

Sincerely,

Gene Smith

Regulatory/Compliance Manager

Office of Oil and Gas



Danielle Southall Regulatory Analyst II

August 23, 2013

VIA UPS

Ms. Laura Cooper Office of Oil & Gas 601 57th Street Charleston, WV 25304

Re: Modification to Roy Ferrell OHI 10H. API# 47-069-00114

Dear Ms. Cooper:

Attached please find a revised WW-6B for the above captioned well. We would like to modify the 13 3/8" and 20" casing in order to be consistent with the other Roy Ferrell well and the 5 ½" casing due to directional work. The BHL will remain the same. This well is situated on the Roy Ferrell property, in Triadelphia District, Wetzel County, West Virginia.

If you have any questions or require additional information, please contact me at 304-517-1416 ext 86024.

Sincerely

Chesapeake Appalachia, LLC

Dee Southall

Enclosure(s)

RECEIVED
Office of Oil and Gas

AUG 26 2013

WV Department of Environmental Protection

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Operator:	Chesapeake	Appalachia, LLC	49447757	69- Ohio	7- Triadelphia	648-Valley Grove	
•			Operator ID	County	District	Quadrangle	
2) Operator's Well 1	Number: Ro	y Ferrell OHI 10H	Well Pad Name: Roy Ferrell OHI Pad				
3 Elevation, current ground: 1196' Elevation, proposed post-construction: 1196'						196'	
4) Well Type: (a) C	4) Well Type: (a) Gas Oil Underground Storage						
Other							
(b) If Gas: Shallow Deep							
	Horiz	zontal			01/		
5) Existing Pad? Ye	s or No: Yes	3			Byle	3/22/2013	
6) Proposed Target	Formation(s),	Depth(s), Anticipate	ed Thicknesses and	d Associated	Pressure(s):	5/0-1	
Target formation- Marcellu	us, Target top TVD- 6	6630', Target base TVD- 66	90', Anticipated thickness-	60', Associated Pr	essure- 4177		
7) Proposed Total V	ertical Depth:	6,640'					
8) Formation at Total Vertical Depth: Marcellus RECEIVED							
9) Proposed Total M	9) Proposed Total Measured Depth: 14,400' Office of Oil and Gas						
10) Approximate Fresh Water Strata Depths: 326' AUG 2 6 2013							
11) Method to Determine Fresh Water Depth: Form a water well-4000' WNW of the pad WV Department of							
12) Approximate Saltwater Depths: 800' Environmental Protection							
13) Approximate Co	13) Approximate Coal Seam Depths: 646'						
14) Approximate Depth to Possible Void (coal mine, karst, other): 646' void abandoned mine							
15) Does proposed well location contain coal seams directly overlying or adjacent to an active mine? If so, indicate name and depth of mine:							
16) Describe proposed well work: Drill and stimulate any potential zones between and including the Benson to the Marcellus. "If we should encounter a void, place basket above and below							
void area - balance cement to bottom of void and grout from basket to surface. Run casing not less than 20' below void nor more than 50' below void.							
(*If freshwater is encountered deeper than anticipated it must be protected, set casing 50' below and cts)							
17) Describe fracturing/stimulating methods in detail:							
Well will be perforated within the target formation and stimulated with a slurry of water, sand, and chemical additives at a high rate. This will be performed in stages with the plug and perf method along							
the wellbore until the entire lateral has been stimulated within the target formation. All stage plugs are then drilled out and the well is flowed back to surface.							
The well is produced through surface facilities consisting of high pressure production units, vertical separation units, water and oil storage tanks.							
18) Total area to be disturbed, including roads, stockpile area, pits, etc, (acres):							
19) Area to be disturbed for well pad only, less access road (acres): 7							

20)

CASING AND TUBING PROGRAM

ТҮРЕ	Size	New or Used	Grade	Weight per ft.	FOOTAGE: For Drilling	INTERVALS: Left in Well	CEMENT: Fill -up (Cu. Ft.)
Conductor	20"	New	J-55	94#	∨ 100'	100'	CTS
Fresh Water	13 3/8"	New	J-55	54.5#	∨ 741'	741'	680'sx/CTS
Coal	9 5/8"	New	J-55	40#	√ 2200¹	2200'	820 sx/CTS
Intermediate	7"	New	P-110	20#	If Needed	If Needed	If needed/As Possible
Production	5 1/2"	New	P-110	20#	v 14,400'	14,400'	Lead 1050 sx Tail 1440 sx/100 inside intermediate
Tubing	2 3/8"	New	N-80	4.7#	Approx. 7,181'	Approx. 7,181'	
Liners							

MgK 8/22/2613

TYPE	Size	Wellbore Diameter	Wall Thickness	Burst Pressure	Cement Type	Cement Yield
Conductor	20"	30"	0.25	2120	15.6 ppg	1.19/50% Excess
Fresh Water	13 3/8"	17.5"	0.380	2740	15.6 ppg	1.19/50% Excess
Coal	9 5/8"	12 1/4"	0.395	3950	15.6 ppg	1.19/50% Excess
Intermediate	7"	8 3/4"	.0317	4360	15.6 ppg	1.20/15% Excess
Production	5 1/2"	8 3/4"	0.361	12360	15.6 ppg	1.20/15% Excess
Tubing	2 3/8"	4.778"	0.190			
Liners						

PACKERS

Kind:	10K Arrowset AS1-X	DECEIVED
Sizes:	5 1/2"	Office of Oil and Gas
Depths Set:	Approx. 6,197'	2.00.2012
		AUG 2 6 2013

WV Department of Environmental Protection



