

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

June 13, 2013

WELL WORK PERMIT

Horizontal 6A Well

This permit, API Well Number: 47-6900171, issued to CHESAPEAKE APPALACHIA, L.L.C., is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to all conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

In addition to the applicable requirements of this permit, and the statutes and rules governing oil and gas activity in WV, this permit may contain specific conditions which must be followed. Permit conditions are attached to this cover letter.

Per 35CSR-4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926-0499 ext. 1654.

James Martin

Chief

Operator's Well No: CARL ROTTER OHI 1H

Farm Name: ROTTER, CARL J. AND GRACE A

API Well Number: 47-6900171

Permit Type: Horizontal 6A Well

Date Issued: 06/13/2013



PERMIT CONDITIONS


West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

CONDITIONS

- 1. Valves on pad catch basin outlets shall remain closed during all drilling and completion activities on the pad so as to not allow any discharge from the pad during drilling and completion activities.
- 2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than fifty (50) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.
- 3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the fill material shall be within plus or minus 2% (unless soil test results show a greater range of moisture content is appropriate and 95% compaction can still be achieved) of the optimum moisture content as determined by the standard proctor density test, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort. Each lift must meet 95% compaction of the optimum density based on results from the standard proctor density test of the actual soils used in specific engineered fill sites. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.
- 4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.
- 5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations*, 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.
- 6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.

Map from a Flex Viewer application

Powered by ArcGIS



Drilling very close to permitted mine: U200805

UKC



Rick Neidermeyer Senior Landman - Coal Relations

March 20, 2013

Re: Carl Rotter OHI 1H Location

Dear Sir or Madam:

I am attaching an exhibit map as part of our permit review. I have indicated Chesapeake Appalachia LLC well location for the Carl Rotter OHI 1H in references to the active mine permits in the area. The location is approximately 380 feet outside of the permit boundaries of this mine. The owner/operator of this mine permit is Tunnel Ridge LLC. The permit number for this underground permit is U018183 and U200805. Please feel free to contact me if you have any further questions.

Sincerely,

Rick Neidermeyer

Office of Oil & Gas

APR - 5 2013

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS W.VA. CODE §22-6A - WELL WORK PERMIT APPLICATION

1) Well Operator: Chesapeake Appalachia, LLC	494477557	69-Ohio	3-Liberty	648-Valley Grove
	Operator II) County	District	Quadrangle
N Out and a 2 Wall Name have		Wall Pad No	ma: Carl Rotter Ol-	HI Pad
2) Operator's Well Number: Carl Rotter OHI 1	ıH.	- Well Pad Na	me: Carl Rotter OF	ii r au
B Elevation, current ground: 1340	Elevation, propos	ed post-constru	iction:	1334'
4) Well Type: (a) Gas Oi	il			
Other	•			
(b) If Gas: Shallow	Deep			-
Horizontal		-		
Tiorizontai			11 JL	
5) Existing Pad? Yes or No: No			2/77	12013
Daisting Fau: Tes of No.			3(21	
6) Proposed Target Formation(s), Depth(s),	Anticipated Thicknesses	and Associate	d Pressure(s):	
Target formation-Marcellus, Target top TVD- 6550', Target base	이번에 집 그렇게하면 하는 하셨다면서 이 지나에게 되었다면 되었다.			
7) Proposed Total Vertical Depth: 6,580				
	larcellus			
'n 1m 11/ 1n i -	6,000'			
0) Approximate Fresh Water Strata Depths	Acres		_	
1) Method to Determine Fresh Water Dept		e-logs drillers logs ar	nd from wells within a	2500' radius
2) Approximate Saltwater Depths: 830		c logs, dillicia loga di	d from wells within a	2000 Tadius
	700'			
4) Approximate Coar Scalin Depths.		None that we	are aware of.	
(5) Does land contain coal seams tributary (그렇게 하는 것이 되었다. 그렇게 그리고 말하다는 그 때에서 전혀가 하셨다. 하나 없이 되었다.			NED Had
(6) Describe proposed well work:	or adjacent to, active min	e? <u>No</u>	acjocent t	o DEP-permitted
Drill and stimulate any potential zones between and including the	ne Benson to the Marcellus. **If we sho	ould encounter a void, r	olace basket above and	1 below
void area - balance cement to bottom of void and grout from bas				
(*If freshwater is encountered deeper than anticipated it must be				
17) Describe fracturing/stimulating methods	s in detail:			
Well will be perforated within the target formation and stimulated with a slur		a high rate. This will be per	formed in stages with the p	plug and perf method along
the wellbore until the entire lateral has been stimulated within th	e target formation. All stage plugs are	then drilled out and the	well is flowed back to	surface.
The well is produced through surface facilities consisting of high	pressure production units, vertical seg	paration units, water an	d oil storage tanks.	
			Reserved	
100 m . 1 1 . 1 . 1 . 1 . 1 . 1	for a contract of the contract of	Offic	e of OUAS Gas	
18) Total area to be disturbed, including roa	ds, stockpile area, pits, e	tc, (acres):	14:0	
16) A 4 - 1 - 4t-4t - 1 C 11 1 - 1 - 1		29.41		
Area to be disturbed for well pad only, I	ess access road (acres):	9.0	2012	

20)

CASING AND TUBING PROGRAM

ТҮРЕ	Size	New or Used	Grade	Weight per ft.	FOOTAGE: For Drilling	INTERVALS: Left in Well	CEMENT: Fill -up (Cu. Ft.)
Conductor	20"	New	J-55	94#	100'	100'	CTS
Fresh Water	13 3/8"	New	J-55	54.5#	542'	542'	510 SX/CTS
Coal	9 5/8"	New	J-55	40#	2250'	2250'	850 SX/CTS
Intermediate	7"	New	P-110	20#	If Needed	√ If Needed	If Needed/As Needed
Production	5 1/2"	New	P-110	20#	16,000'	16,000'	Lead 1210 sx Tail 1570 sx/100' inside intermediate
Tubing	2 3/8"	New	N-80	4.7#	Approx. 7753'	Approx. 7753'	
Liners							

Mg/ 3/27/2017

TYPE	Size	Wellbore Diameter	Wall Thickness	Burst Pressure	Cement Type	Cement Yield
Conductor	20"	30"	0.25	2120	15.6 ppg	1.19/50% Excess
Fresh Water	13 3/8"	17.5"	0.380	2740	15.6 ppg	1.19/50% Excess
Coal	9 5/8"	12 1/4"	0.395	3950	15.6 ppg	1.19/50% Excess
Intermediate	7"	8 3/4"	.0317	4360	15.6 ppg	1.20/15% Excess
Production	5 1/2"	8 3/4"	0.361	12360	15.6 ppg	1.20/15% Excess
Tubing	2 3/8"	4.778"	0.190			
Liners						

PACKERS

Received Office of Oil & Gas

Kind:	10K Arrowset AS1-X	EPE _ = 2013
Sizes:	5 1/2"	
Depths Set:	Approx. 6,197'	

) Describe centralizer placement for each casing string.	
All casing strings will be ran with a centralizer at a minimum of 1 per every 3 joints of casing.	
) Describe all cement additives associated with each cement type.	
**Please see attached sheets for Chemical Listing of Cement & Additives for Chesapeake Energy wells.	
) Proposed borehole conditioning procedures.	
All boreholes will be conditioned with circulation and rotation for a minimum of one bottoms up and continuing until	
operator is satisfied with borehole conditions.	

*Note: Attach additional sheets as needed.


Received Office of Oil & Gas

APR - 5 2013

<u>Chemical Name</u>	CAS Number	
Fuller's earth (attapulgite)	8031-18-3	0.2% BWOC
Polypropylene glycol	25322-69-4	
polyethylene terephthalate	25038-59-9	0.125 lb/sk
calcium chloride	10043-52-4	2% BWOC
polyethylene terephthalate	25038-59-9	1 lb/bbl
bentonite	1302-78-9	20 lb/bbl
Fuller's earth (attapulgite)	8031-18-3	0.2% BWOC
Polypropylene glycol	25322-69-4	100-22-
polyethylene terephthalate	25038-59-9	0.125 lb/sk
sodium chloride	7647-14-5	10% BWOW
chrystalline silica	14808-60-7	0.15% BWOC
bentonite	1302-78-9	20 lb/bbl
polyethylene terephthalate	25038-59-9	1 lb/bbl
product classified as non-hazardous.		0.05 gal/sk
product classified as non-hazardous		0.01 gal/sk
polypropylene glycol	25322-69-4	0.02 gal/sk
Carbohydrate	proprietary	1 lb/bbl
Silica Organic Polymer	proprietary	0.1 gal/bbl
barium sulfate	7727-43-7	310 lb/bbl
fatty acid amine	proprietary	
ethoxylated alcohol	proprietary	
glycerol	56-81-5	
2.2'-Iminodiethanol	111-42-2	1 gal/bbl
aliphatic amide polymer	proprietary	0.35% BWOC
non-crystalline silica	7631-86-9	6% BWOC
boric acid	10043-35-3	0.8% BWOC
Fuller's earth (attapulgite)	8031-18-3	
Polypropylene glycol	25322-69-4	0.2% BWOC
chrystalline silica	14808-60-7	0.00/ 514/0.5
metal oxide	proprietary	0.2% BWOC
sulphonated synthetic polymer	proprietary	0.00/ 0.000
formaldehyde (impurity)	50-00-0	0.3% BWOC
Fuller's earth (attapulgite)	8031-18-3	
Polypropylene glycol	25322-69-4	0.2% BWOC
aliphatic amide polymer	proprietary	0.35% BWOC
Sodium Polynaphthalene Sulfonate	9008-63-3	0.050/ 511/00
Sodium Sulfate	7757-82-6	0.25% BWOC

Received e of Oil & Gas

2013



3302 Old Elkins Road Buckhannon, WV 26201 My commission expires November 27, 2022

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS

CONSTRUCTION AND RECLAMATION PLAN AND SITE REGISTRATION APPLICATION FORM GENERAL PERMIT FOR OIL AND GAS PIT WASTE DISCHARGE

Operator Name Chesapea	ake Appalachia, I	LC	OP Code	494477557	3 111
Watershed Upper Ohio Son	uth	Q	uadrangle 648-Valley Gro	ve	
Elevation 1340'		County_69-Ohio	Distric	3-Liberty	
Description of anticipated	d Pit Waste: _C	losed loop system in place at this	time - cuttings will be taker	n to a permitted landfill.	
Do you anticipate using t	nore than 5,00	bbls of water to complete th	e proposed well work?	Yes xx No	-
Will a synthetic liner be	used in the pit?	If so,	what mil.?		
Proposed Disposal Metho	od For Treated Land Applica				
	Underground	Injection (UIC Permit Num	ber_ 2D0072539/ 2D04131	75/ 2D0610306/ 2D0610317)
		PI Number at next anticipated well, A		DDMR &/or permit addendum)
-	Off Site Disp Other (Expla	osal (Supply form WW-9 for inFlow back fluids will be put in steel tai	disposal location) asks and reused or taken to a permitte	ed disposal facility.	
Drilling medium anticipa	ted for this we	1? Air, freshwater, oil based,	etc. Air and salt saturate r	mud	
-If oil based, wh	at type? Synth	etic, petroleum, etc. Synthetic	: Oil Base		
Additives to be used? _s		ts			
Will closed loop system		n pit, landfill, removed offsite	etc Landfill		
		y what medium will be used?			
-Landfill or offs	ite name/permi	t number? Meadowfill SWF-103	32, SS Grading SWF-4902,	Northwestern SWF-1025	
		00172, Carbon Limestone 28726/CID 2872			
on August 1, 2005, by th provisions of the permit a or regulation can lead to I certify under application form and all the information, I believ submitting false informat Company Official Signat	e Office of Oil are enforceable enforcement ac penalty of lav attachments the et that the info- tion, including	that I have personally exacted and that, based on my intrination is true, accurate, and the possibility of fine or impr	a Department of Enviro from or condition of the g mined and am familiar inquiry of those individu d complete. I am awa	nmental Protection. I under the seneral permit and/or other heceived with the information subals immediately responsible	rstand that the applicable law mutted on this e for obtaining
Company Official (Type	d Name) Danie	le Southall			
Company Official Title F	Regulatory Analy	st II			_
Subscribed and sworn be	fore me this_0	oth day of Mil	nch,	20 13	_
Buttony	R Wood	4	No	ary Public	
My commission expires_	11/37/37	J		OFF Notary Public,	ICIAL SEAL State of West Virginia

Property Bounda	ary A	Diversion -	111111
Road	======	== = Spring	○
Existing Fence	—_x—_x—_x	———— Wet Spot	mage
Planned Fence	///-	Drain Pipe	
Stream		w/ size in inches —	(12)
Open Ditch		Waterway —	\leftarrow
Rock	ర్శాల్గ్రాహ్హ	Cross Drain ZZZZZ	THITTH THE
1.0-2	-00	Artificial Filter Strip XXXXX	XXXXXXXXXXXXXXXXX
North	T	Pit: Cut Walls	enting.
Buildings		Pit: Compacted Fill Walls	Juniline E
Water Wells	w	Area for Land Application	mulum
Drill Sites	$\widecheck{\oplus}$	of Pit Waste	9-9-9-9
	reatment: Acres Disturbed 1		on pH
Fertilizer (10-20	-20 or equivalent) 500	lbs/acre (500 lbs minimum)	
Mulch_Hay/Straw		Tons/acre	
		Seed Mixtures	
			A
Seed Type	Area I lbs/acre	Seed Type	Area II lbs/acre
White Clover	15	White Clover	15
Red Top	15	Red Top	15
Orchard Grass	20	Orchard Grass	20
			Received Office of Oil & Gas
Attach:	·	land amplication	APR - 5 2013
Drawing(s) of road, locat	ion,pit and proposed area for	rand application.	- 601/1
Photocopied section of in	volved 7.5' topographic shee	t.	
Plan Approved by:	Jaim J Cut		
Comments:			
		8 3	
Title: Oil and Gas Inspector	r	Date: 3 27 2013	
	Victoria de la companya della companya della companya de la companya de la companya della compan		
Field Reviewed?	(Yes	() No	

Marcellus Well Drilling Procedures And Site Safety Plan

Chesapeake Appalachia, LLC

47 - 69 Well name Carl Rotter OHI 1H
Valley Grove, Quad
Liberty, District
Ohio County, West Virginia

3/2/200

Submitted by: Danielle Southall	3/19/2013 Date:
Title Regulatory Analyst II	Chesapeake Appalachia, LLC
Approved by:	
	Date:
Title:	
Approved by:	
	Date:
Title:	
Chesapeake Appalachia, L.L.C Con	ıfidential

Received Office of Oil & Gas

APR - 5 2013

Site Safety Plan

- 1. A formal pre-spud meeting will be held prior to this well being drilled. Discussions between the drilling rig toolpusher and CHK representatives will be held weekly regarding general safety and environmental issues.
- 2. The highest ranking drilling contractor representative present shall keep an accurate count of all drilling personnel on the drilling location at all times. All non-drilling (i.e., non-CHK and non-drilling contractor) personnel will be required to sign the attached ACCESS CONTROL REPORT. All non-essential persons will be kept off the drilling location at all times, and such access will be enforced by the highest ranking drilling contractor representative present.
- 3. In case of an emergency on the drilling site, all persons on location will exit via the access road and meet at the evacuation meeting area designated on the attached EVACUATION PLAN. The highest ranking drilling contractor representative will be responsible for comparing the persons that were present on location to those persons gathered at the designated evacuation meeting area. Any evacuation deemed necessary of residents in the surrounding area will be accomplished by telephone or door-to-door contact from a CHK representative.
- 4. For the prevailing wind direction please see Evacuation Route/Prevailing Winds sheet attached hereto.
- 5. General safety and environmental awareness meetings will be held with the rig toolpusher weekly or more often if needed.

The following is a list of emergency response agencies for well Carl Rotter OHI 1H:

Agency Type	Name	Phone Number	Cell
County Police	Ohio County	911 or 304-234-3811	
State Police	Ohio County	911 or 304-238-1100	
Ambulance Service	Ohio County	911 or 304-277-4357	
Hospital		304-234-0123	
Fire Department	Ohio County	911 or 304-234-3651	
Darrel Overgaard	Drilling Engineer Manager	405-935-4118	405-248-7920
Casey McDonough	Drilling Engineer	405-935-4778	405-606-1482
Chase Dwiggins	Drilling Engineer	405-935-4247	405-312-6284
Stacey Tubbs	Drilling Superintendent	575-391-1462	575-631-8271
John Melville	Drilling Superintendent	814-573-6692	304-380-7127
Rick Harless	Drilling Superintendent		304-807-3600
Rickey Beene	Drilling Superintendent	405-990-0394	970-250-4441
Clayton Lane	Drilling Superintendent		304-997-9466
Malcom Ashley	Drilling Superintendent		304-997-9258
Gary Gould	District Manager	405-935-4060	405-249-4514
Scott Nease	Production Superintendent	304-517-1416 x 86001	304-641-0085
Kevin Patterson	EHS Field Specialist	304-517-1416 x 860 Psc	
Zach Arnold	Operations Manager	304-517-1416 x 86028f	Dil & 304-203-8059
Nathan Smarr	Field Superintendent	304-517-1416 x 86023	304-997-0600
Tim Murray	Field Manager	405-935-2505	405-818-2467
Joe Kennedy	Drilling Safety Manager, Op.	405-935-8256	201 405-990-8126
Kris Osecky	Field Safety Representative	724-324-2205 x 83836	724-886-8161
Gayne Knitowski	WV Oil and Gas Inspector		304-546-8171
Dave Belcher	Inspector Supervisor	304-926-0499 x 1647	304-389-7590
James Martin	Chief	304-926-0499 x 1654	
WV DEP	Emergency Pollution and Spills	1-800-642-3074	
Chesapeake	24 Hour Hotline	1-800-566-9306	

Contractor's	Company	Phone	
Well Control Co.'s	Boots & Coots	1-800-256-9688	
	Halliburton	1-800-409-6479	
Earthwork/Equipment	Triple J Contractors	304-472-3962	
Remediation/Cleanup	Weaverton Environmental	724-746-4850	
Remediation/Cleanup	Ryan Environmental	304-842-5578	
Remediation/Cleanup	Central Environmental Services	304-863-8867	
Heavy Equipment	Kanawha Stone	304-755-8271	
Heavy Equipment/Rouster	Arvilla Pipeline	304-665-2652	
Heavy Equipment	Hoy Contracting	724-627-0272	
Cleanup Supplies	McJunkin Supply	304-472-3565	

Driving Directions: Take I-79N to I-70W. Go approx.. 16.7 miles and take the exit toward Old Brick Road. Turn right on Old Brick Road and continue onto Maple Ave. Turn left onto Church Street and then turn left onto Highland Ave. Continue onto Trestlework Rogers Road entering into WV. Follow for approx.. 1.6 to arrive at the Carl Rotter Pad.

Casing Requirements

1. The following is a list of all known freshwater, saltwater, oil and gas producing, hydrogen sulfide producing, thief, and high pressure and volume zones:

Name of Zone	Anticipated Depth	Type of Zone
Fresh water	442'	Fresh Water
Coal	700'	Coal
Salt Water	830'	Salt Water
Big Injun Base	2095'	Gas
Geneseo	6380'	Gas
Tully	6400'	Gas
Hamilton	6435'	Gas
Marcellus	6550'	Gas

^{**} All casing used in the well bore will be new.

2. The casing and cementing program is as follows:

Casing Type	Size	Grade	Weight	Footage	Cement Top
Conductor	20"	J-55	94#	100'	CTS
Fresh Water	13 3/8"	J-55	54.5#	542'	510 SX/CTS
Coal	9 5/8"	J-55	40#	2250'	850 SX/CTS
Intermediate	7"	P-110	20#	If Needed	If Needed/As Needed
Production	5 1/2"	P-110	20#	16,000°	Official (12 10 fx Tail, 1570 Sx/or at least as 100' up inside intermediate string
Tubing	2 3/8"	N-80	4.7	Approx. 7753'	7 2013
Packer 10K Arrowset AS1-X	5 1/2"				
Contingency Liner	7 5/8"	P-110	29.7		

^{**} All Cements used will meet the API Standards.

- 3. -Well Work Detail: Drill and stimulate the Marcellus formation. If we should encounter a void, place a basket above and below the void area balance cement to bottom of void and grout from basket to surface. Run casing not less than 20' below void nor more than 50' below void. If freshwater is encountered deeper than anticipated it must be protected, set casing at least 50' below but not more than 100' below freshwater and cts.
- 4. -All casing cemented will not be disturbed for at least 8 hours after cementing operations.
- 5. -Surface, Coal, and Intermediate strings will be pressure tested at a pressure 20% greater than what is expected to be exerted on each string throughout the remainder of the well operations.
- 6. -No oil or gas production or pressure should exist on the surface or coal protection strings.
- 7. -A Formation Integrity Test (FIT) will be performed immediately following the drill out of intermediate casing.
- 8. -Centralizers will be used in the well. However, the placement of the centralizers will be contingent on the final well log and directional data.
- 9. -Production casing will be pressure tested at a pressure 20% greater than what is expected to be exerted upon it during fracturing operations. Upon completion of fracturing operations the production casing will be pressure tested at a pressure 20% greater than expected shut in pressure.
- 10. -Well will be perforated within the target formation and stimulated with a slurry of water, sand, and chemical additives at a high rate. This will be performed in stages with the plug and perf method along the wellbore until the entire lateral has been stimulated within the target formation. All stage plugs are then drilled out and the well is flowed back to surface. The well is produced through surface facilities consisting of high pressure production units, vertical separation units, water and oil storage tanks.

Received
Office of Oil & Gas

2013


BOP Requirements

1. The following is a list of the blow-out prevention equipment that will be utilized at various times during the drilling of the well:

- Testing of the BOP stack intermediate drilling phase will be conducted upon initial set up and the
 annular tested to 70% of capacity. For the Bottom and horizontal wellbore drilling phase, the BOP
 equipment will be tested upon initial installation Annulars to 70% of capacity and rams to 80% of
 capacity.
- 3. The BOP equipment will be installed when nippling-up on the casing strings as shown above.
- 4. The following persons that will be involved in the drilling operations are BOP certified:

Rig Toolpusher
Rig Morning Tour Driller
Rig Daylight Tour Driller
Rig Evening Tour Driller
CHK Drilling Representatives

- 5. A drilling record book will be maintained during the drilling operation, which will denote all formations encountered, any water or hydrocarbon occurrences, any occurrences of hydrogen sulfide, any lost circulation zones and any abnormally pressured zones. The WVOOG inspector will be notified by phone upon any significant drilling events.
- 6. The following diagram illustrates the wellhead assembly that will be placed on the well upon completion of the well.



Well Flaring Operations

- 1. No flaring is anticipated on this well and therefore no flare lines will be utilized. Based on offset well information no significant gas flows should be encountered during drilling. If a significant show is encountered the gas would be flared through the 7" flanged flowline. This flowline will be anchored to the ground using chains and deadman stakes, and will be approximately 75 feet long.
- 2. In the unlikely event that gas needs to be flared. The well would be shut-in, and a smudge pot would be set up as a primary ignition with a marine flare pistol used as a backup igniter.
- 3. All flammable material within a minimum distance of 50' from the end of the flow line will be cleared, in case a flare would be needed.
- 4. The fire department will be notified immediately prior to flaring.
- 5. The duration of flaring typically will not last more than 7 days.

Well Killing Operations Method and Type

- 1. Barite and saturated brine will be available if necessary to weight up beyond the proposed compositions. Should a significant gas flow occur, historical data from the field shows that the brine is of sufficient weight to kill the well.
- 2. No mixing units will be required since only brine would be utilized in the unlikely event of a significant gas show.

Received
Office of Oil & Gas

2017

Chesapeake H2S Safety Packages

Hydrogen Sulfide Operations H2S (Low Level Concentration and Low Risk)

1. Training

- a. Basic awareness training (either video or booklet review) will occur on-site and may require two trips in order to train all rig crew members
- b. Each crew member will be given certification test to verify his competence to respond in an H2S situation.
- c. Physically show members how to properly don a mask and peform a qualitative fit test (bananna oil) if utilizing a tight fitting mask as an escape unit.
- d. Identify and discuss the location of escape units, SCBA's and location of H2S monitors and sensors.

2. Drills

- a. Evacuation of the rig (Discuss). Identify muster points and location of SCBA's.
- b. Man Down Drill (Discuss procedures for rescueing an employee who has gone down).

3. Safey Equipment

- a. (10) 5 minute escape packs will be installed on the rig floor for a quick escape.
- b. (1) 10 minute escape pack will be installed on the board.
- c. (4) 30 minutes SCBA's will be on-site. Two SCBA's will be placed at the entrance to the location (Muster Point #1) and the other two placed at Muster Point #2 on the other side of the location. This will allow either equipment to be in area that is upwind.
- d. (1) 4 multichannel H2S Monitor with sensors placed on the floor, shakers, bell nipple and other to be placed where needed.
- e. (2) hand held multi-gas monitor or a box of H2S tubes and a box of SO2 tubes to perform test in the event a monitor has been sounded.
- f. (2) Safety Area Signs
- g. (1) Condition Sign
- h. (2) Wind socks that are to be placed in areas that can can been seen at all times on the rig and at an height with good wind flow.

4. Record Keeping

- a. A copy of employee certications should be submitted to the Chesapeake Rig Consultant for files.
- for files.

 b. Weekly checks or calibration records must be provided to the Chesapeake Rigs

 Consultant.

2013

Step-Up Package (High Risk and High Concentration)

- I. Training (Same training as the Basic Packing with the following Additions):
 - a. Medical Eval Forms to be filled out
 - b. Perform Fit Test
 - c. Discuss how to properly hook up supplied air equipment to masks.
- II. Drills
 - a. Evacuation of the rig (Discuss). Identify muster points and location of SCBA's.
 - b. Man Down Drill (Discuss procedures for rescueing an employee who has gone down).
- III. Safey Equipment (Same as the Basic with the following Additions):
 - a. Install a supplied air cascading system with (2) manifolds that will supply air to the the floor and the rigs backyard.
 - i. (5) Quick connects on the floor and 20st 50st of hose.
 - ii. (1) Quick conenct at the shakers with 20st 50 st of hose.
 - iii. (1) Quick connect mid-way down the pits with 20st 50 st of hose.
 - iv. (1) Quick connect at the end of the pit with 20st 50st of hose.
 - v. (1) Quick connect installed to provide air to the choke manifold with 20ft 50ft of hose.
 - b. Install an explosion proof siren and lights
- IV. Record Keeping
 - a. A copy of employee certications should be submitted to the Chesapeake Rig Consultant for files.
 - b. Weekly checks or calibration records must be provided to the Chesapeake Rig Consultant.
 - c. If a H2S Safety Representative is required on location for 24-hours periods, then a daily report must be provided to Chesapeake's Rig Consultant.

In the unlikely event that hydrogen sulfide would be present, all affected residents and agencies would be notified by telephone or in person by a Chesapeake Appalachia, LLC representative, and access would be controlled by a sign, color coded flags and a sign-in sheet. Oil and Gas Inspector, Gayne Knitowski will be called at (304) 546-8171.

Office of Oil & Gas

- 2013


^{**}Chesapeake will authorize payment for initial training of all rig crew members. If a new rig crew member is hired, then the contractor is responsible for payment to train the new employee.

Notification

Emergency personnel and local residents will be given prior notification, if possible, of significant drilling events either by telephone or in person by a Chesapeake Appalachia, LLC representative. If prior notification is not possible, the CHK representative in charge of the drilling operation will contact all applicable persons in the case of any event that requires notification once circumstances allow. A copy of the Site Safety Plan will be provided to the local county emergency office at least 7 days before dirt work or well work commences. MSDS sheets will be available in the tool- pusher's office.

The nearest Schools and Public facilities with in a 1 Mile radius +/- are:


CR 40	Historical Society 304-234-3656
Valley Grove, WV	Thistorical Society 304-234-3030




ACCESS CONTROL REPORT Well Name: Carl Rotter OHI 1H

DATE	NAME		TIME IN	TIME OUT
		D	sealund	
		Office	ecelved of Oil & Gas	
		Omog	01 011 0 000	
		APR	- 5 2013	

	BL		EVENTER SO		
WELL FIELD RIG	:				
COUNTY OPERATION	: : 17 1⁄2" S	urface Hole		STATE : REVISION : :	-1 1
	onent Des			Proceedian	Reference
_		Description			
		Rotating Head			
В				Trip Tank Required: Yes	□ No□
C				Inp tank required: Yes	
D E					ļ
F					
G			 1		
н					
DSA			A		
C Sec					
B Sec				Flowline to close	ed loop pits
11000				with bypass vent	line to flare
1	Kili Line			Choke Li	l l
ID Pressu	re Descr	iption	-	ID Pressure D	escription
 					
L			1		
			1 1		
					7774 San C Ga
			i l		- 2013
Tes Item	ting Requi	rements Frequency			
Rotating Head	250 / 500 psl	Once prior to DO shoe]		
]		-
				Approved by	Date
		<u> </u>		4	
•				HaO-	1
			J		





west virginia department of environmental protection



Water Management Plan: Primary Water Sources



WMP-01180

API/ID Number:

047-069-00171

Operator:

Chesapeake Energy

Carl Rotter OHI 1H - 837750

Important:

For each proposed primary water source (including source intakes for purchased water sources) identified in your water management plan, and summarized herein, DEP has made an evaluation concerning water availability over the specified date range. DEP's assessment is based on the following considerations:

- •Statistical analysis of historical USGS stream gauge data (transferred to un-gauged locations as necessary);
- Identification of sensitive aquatic life (endangered species, mussels, etc.);
- •Quantification of known existing demands on the water supply (Large Quantity Users);
- · Minimum flows required by the Army Corps of Engineers; and
- Designated stream uses.

Based on these factors, DEP has provided, for each intake location (and origination point for purchased water), a reference gauge location and discharge flow reading which must be surpassed prior to withdrawals. Additionally, DEP has established a minimum passby flow at the withdrawal location which must also be surpassed prior to withdrawals. These thresholds are considered terms of the permit and are enforceable as such.

DEP is aware that some intake points will be used for mutiple wells and well sites. In these cases, the thresholds set by the Water Management Plan are to be interepreted as total withdrawal limits for each location over the specified date range regardless of how many wells are supported by that intake.

For all purchased water intakes, determinations of water availability are made at the original source intake location. It is the responsibility of the Oil and Gas Operator, not the seller, to cease withdrawal of water from the seller when flows are less than the minimum gauge reading at the stream gauge referenced by the Water Management Plan in order to protect stream uses.

Note that the determinations made herein are based on the best available data, but it is impossible to predict water availability in the future. While the DEP has carefully established these minimum withdrawal thresholds, it remains the operator's responsibility to protect aquatic life at all times. Approval to withdrawal is contingent upon permission from the land owner. It is the responsibility of the operator to secure and maintain permission prior to any withdrawals.

The operator is reminded that 24-48 hours prior to withdrawing (or purchasing) water, DEP must be notified by email at DEP.water.use@wv.gov.



Source Summary

WMP-01180

API Number:

047-069-00171

Operator:

Chesapeake Energy

Carl Rotter OHI 1H - 837750

Stream/River

Source

Ohio River WP 1 (Beech Bottom Staging Area)

Owner:

Brownlee Land Ventures

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude:

Intake Longitude:

7/1/2013

7/1/2014

4,032,000

40.226889

-80.658972

✓ Regulated Stream?

Ohio River Min. Flow

Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

6,000

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

Ohio River @ Essroc Withdrawal Site

Owner:

Essroc Ready Mix Corp.

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

39.9947

Intake Latitude: Intake Longitude: -80.736483

7/1/2013

✓ Regulated Stream?

7/1/2014

4,032,000

Ohio River Min. Flow Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

6,000

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

Big Wheeling Creek WP 1

Owner:

Fulton Storage, LLC

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

40.077019

Intake Latitude: Intake Longitude: -80.713866

7/1/2013

7/1/2014

4,032,000

3112000

WHEELING CREEK AT ELM GROVE. WV

☐ Regulated Stream? Max. Pump rate (gpm):

2,500

Min. Gauge Reading (cfs):

Ref. Gauge ID:

43.57

Min. Passby (cfs)

40.03

DEP Comments:

Source Little Wheeling Creek WP 1 (Rt. 40 Staging Area)

JDS Investments, LLC

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

ntake Longitude -80.591145

7/1/2013

7/1/2014

4,032,000

3112000

WHEELING CREEK AT ELM GROVE, WV

40.078324

Owner:

Max. Pump rate (gpm):

☐ Regulated Stream?

2,000

Min. Gauge Reading (cfs):

Ref. Gauge ID:

64.80

Min. Passby (cfs)

2.83

DEP Comments:

Source Summary

WMP-01180

API Number:

047-069-00171

Operator:

Chesapeake Energy

Carl Rotter OHI 1H - 837750

Purchased Water

Source

The Village of Valley Grove

Owner:

The Village of Valley Grove

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

7/1/2013

7/1/2014

4,032,000

720,000

✓ Regulated Stream?

Ohio River Min. Flow Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

6.468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

Ohio County PSD

Owner:

Ohio county PSD

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

7/1/2013

7/1/2014

4,032,000

720,000

9999999

Ohio River Station: Willow Island Lock & Dam

✓ Regulated Stream? Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

Ohio River Min. Flow Ref. Gauge ID:

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

Wheeling Water Department

Owner:

Wheeling Water Department

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

7/1/2013

7/1/2014

4,032,000

720,000

Regulated Stream?

Ohio River Min. Flow

Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DFP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Elite Gasfield Services Source

Owner:

Elite Gasfield Services

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

7/1/2013

7/1/2014

4,032,000

2,000,000

✓ Regulated Stream?

Ohio River Min. Flow Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

WMP-01180 API/ID Number: 047-069-00 Carl Rotter OHI 1H - 83775		ke Energy
Source ID: 16215 Source Name The Village of Valley Grove The Village of Valley Grove HUC-8 Code: 5030106	Source Latitude: -	
Drainage Area (sq. mi.): 25000 County: Ohio ☐ Endangered Species? ✓ Mussel Stream? ☐ Trout Stream? ☐ Tier 3?	Anticipated withdrawal start date: Anticipated withdrawal end date: Total Volume from Source (gal):	7/1/2013 7/1/2014 4,032,000
 ✓ Regulated Stream? ✓ Proximate PSD? ✓ Gauged Stream? Ohio River Min. Flow Wheeling Water Department 	Max. Pump rate (gpm): Max. Simultaneous Max. Truck pump rat	
Reference Gaug 9999999 Ohio River Station: Willow Island L Drainage Area (sq. mi.) 25,000.00	ock & Dam Gauge Threshold (cfs):	6468
Median Threshold Estimated monthly flow (+ pump Available (cfs) water (cfs)		
1 45,700.00		
1 45,700.00 -		
1 45,700.00		
1 45,700.00		
1 45,700.00		
1 45,700.00		
1 45,700.00		
1 45,700.00 - - 2 49,200.00 - - 3 65,700.00 - - 4 56,100.00 - - 5 38,700.00 - - 6 24,300.00 - - 7 16,000.00 - -		
1 45,700.00		
1 45,700.00 - - 2 49,200.00 - - 3 65,700.00 - - 4 56,100.00 - - 5 38,700.00 - - 6 24,300.00 - - 7 16,000.00 - - 8 13,400.00 - - 9 12,800.00 - -		

11

10

12

9

7

Median Monthly Flow - Threshold

Headwater Safety (cfs):

Ungauged Stream Safety (cfs):

Min. Gauge Reading (cfs):

Passby at Location (cfs):

3

5

20000

0

1

2

0.00

0.00


[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

	2000	500	Source D			
	WMP-0)1180			Operator: Chesapeal	ke Energy
			Carl Rotter OH	1H - 837750		
Source II	D: 16216 Sou	irce Name Ohio O	County PSD		Source Latitude: -	
		Ohio	county PSD		Source Longitude: -	
	HUC-8 Code:	5030106		12.00		7/4/2042
	Drainage Area	(sq. mi.): 25000	County: O	nio	ted withdrawal start date:	7/1/2013
☐ En	dangered Species		ream?		ated withdrawal end date:	7/1/2014
	out Stream?	☐ Tier 3?	cuiii:	Total	Volume from Source (gal):	4,032,000
	gulated Stream?	Ohio River M	in Flow		Max. Pump rate (gpm):	
	oximate PSD?		ater Department		Max. Simultaneous	Trucks:
		wheeling wa	iter Department		Max. Truck pump rat	
Ŭ Ga	uged Stream?				Max. Truck pump rat	e (ghiii)
	Reference Gaug	9999999	Ohio River Station: Wil	low Island Lock & Dam		
	Drainage Area (so	ą. mi.) 25,00	0.00		Gauge Threshold (cfs):	6468
Month	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs)			
1	45,700.00		water (cis)			
2	49,200.00					
3	65,700.00	¥	1.5			
4	56,100.00					
5	38,700.00					
6	24,300.00					
7	16,000.00		-			
8	13,400.00		170			
9	12,800.00 15,500.00					
11	26,300.00					
12	41,300.00	V	-			
	V	Vater Availa	bility Profile		Water Availability Assessm	ent of Location
					Base Threshold (cfs):	-
8000	0 —				Upstream Demand (cfs):	
		A			Downstream Demand (cfs):	
6000	0 Flow on th	nis stream is reg	gulated by the Army	Corps of		
4000	Engineers	. Please adher	e to the stated three	sholds to	Pump rate (cfs):	
	maintain t	he minimum gu	aranteed flow requ	irements.	Headwater Safety (cfs):	0.00
2000	0		***	V	Ungauged Stream Safety (c	fs): 0.00
	0		 		ongauged stream salety (c	13). 0.00
	1 2	2 / 5	6 7 8 9	10 11 12	Min. Gauge Reading (cfs):	

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

◆ Median Monthly Flow ■ Threshold

Passby at Location (cfs):



8

7

Median Monthly Flow — Threshold

9

10

11

12

06/14/2013

Min. Gauge Reading (cfs):

Passby at Location (cfs):

1

2

3

5

[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.


	WMP-0	01180	API/ID Number: Carl Rotter C	047-069-00171 Operator: Chesapeake Energy
Source I	D: 16218 Sou		asfield Services asfield Services	Source Latitude: - Source Longitude: -
☐ Tro ✓ Re ✓ Pro	HUC-8 Code: Drainage Area (dangered Species) Out Stream? gulated Stream? oximate PSD? uuged Stream? Reference Gaug		eam? in. Flow sbee	Anticipated withdrawal start date: 7/1/2013 Anticipated withdrawal end date: 7/1/2014 Total Volume from Source (gal): 4,032,000 Max. Pump rate (gpm): Max. Simultaneous Trucks: Max. Truck pump rate (gpm)
	Drainage Area (so	д. mi.) 25,000	0.00	Gauge Threshold (cfs): 6468
Month 1 2 3	Median monthly flow (cfs) 45,700.00 49,200.00 65,700.00	Threshold (+ pump	Estimated Available water (cfs)	
4 5 6 7	56,100.00 38,700.00 24,300.00 16,000.00			
8 9 10 11 12	13,400.00 12,800.00 15,500.00 26,300.00 41,300.00		2	
	V	/ater Availal	oility Profile	Water Availability Assessment of Location
				Base Threshold (cfs):

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

◆ Median Monthly Flow ■ Threshold

Passby at Location (cfs):





Base Threshold (cfs):	+
Upstream Demand (cfs):	
Downstream Demand (cfs):	
Pump rate (cfs):	13.37
Headwater Safety (cfs):	0.00
Ungauged Stream Safety (cfs):	0.00
Min. Gauge Reading (cfs):	
Passby at Location (cfs):	


[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

11

12

26,300.00 41,300.00





0.00
0.00
13.37
_ `

[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

9

10

11 12 12,800.00

15,500.00 26,300.00

41,300.00



Month	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs)
1	293.29	45.60	247.82
2	374.26	45.60	328.78
3	519.05	45.60	473.58
4	385.31	45.60	339.84
5	234.87	45.60	189.40
6	106.90	45.60	61.43
7	47.24	45.60	1.77
8	27.63	45.60	-17.84
9	17.56	45.60	-27.91
10	29.09	45.60	-16.38
11	91.52	45.60	46.05
12	207.51	45.60	162.04


Water Availability Profile 600 400 200 1 2 3 4 5 6 7 8 9 10 11 12 Median Monthly Flow Threshold

Water Availability Assessment	of Location
Base Threshold (cfs):	40.03
Upstream Demand (cfs):	0.00
Downstream Demand (cfs):	0.00
Pump rate (cfs):	5.57
Headwater Safety (cfs):	0.00
Ungauged Stream Safety (cfs):	0.00
Min. Gauge Reading (cfs):	43.57
Passby at Location (cfs):	40.03

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

WMP-01180	API/ID Number:	047-069-00171	Operator: Chesa	apeake Energy
	Carl Rotter	OHI 1H - 837750		
Source ID: 16213 Source Nar	me Little Wheeling Creek WP	1 (Rt. 40 Staging Area)	Source Latitude:	40.078324
	JDS Investments, LLC		Source Longitude:	-80.591145
HUC-8 Code: 5 Drainage Area (sq. mi.) ☐ Endangered Species? ✓ ☐ Trout Stream? ☐ Regulated Stream?	030106 : 13.94 County: Mussel Stream? Tier 3?	Ohio Antio	pated withdrawal start date ipated withdrawal end date al Volume from Source (gal) Max. Pump rate (gpm)	7/1/2014 4,032,000
☐ Proximate PSD? ☐ Gauged Stream?			Max. Simulta Max. Truck pur	neous Trucks: mp rate (gpm)
Reference Gaug 31	L12000 WHEELING CREEK	AT ELM GROVE, WV		
Drainage Area (sq. mi.)	281.00		Gauge Threshold (cfs	s): 38

Month	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs) 3.55	
1	13.81	10.62		
2	17.62	10.62	7.36	
3	24.44	10.62	14.18	
4	18.14	10.62	7.88	
5	11.06	10.62	0.80	
6	5.03	10.62	-5.23	
7	2.22	10.62	-8.03	
8	1.30	10.62	-8.96	
9	0.83	10.62	-9.43	
10	1.37	10.62	-8.89	
11	4.31	10.62	-5.95	
12	9.77	10.62	-0.49	



Min. Gauge Reading (cfs): Passby at Location (cfs):	64.80
Ungauged Stream Safety (cfs):	0.47
Headwater Safety (cfs):	0.47
Pump rate (cfs):	4.46
Downstream Demand (cfs):	0.00
Upstream Demand (cfs):	3.34
Base Threshold (cfs):	1.89

[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

west virginia department of environmental protection



Water Management Plan: Secondary Water Sources



WMP-01180

API/ID Number

047-069-00171

Operator:

Chesapeake Energy

Carl Rotter OHI 1H - 837750

Important:

For each proposed secondary water source identified in your water management plan (i.e., groundwater well, lake/reservoir, recycled frac water, multi-site impoundment, out-of-state source), DEP makes no estimation of the availability of water. These sources may prove to be unsuitable water supplies. Please review the following notes:

- •For groundwater supply wells, DEP recommends that the operator contact the local health department prior to drilling any new well; and reminds the operator that all drinking water wells within 1,500 feet of a water supply well shall be flow- and quality-tested by the operator at the request of the drinking well owner prior to operation of the water supply well.
- •For each proposed multi-site impoundment water source identified in your water management plan (if applicable), DEP will review the withdrawal limits established in the referenced Water Management Plan for current suitability and provide to the operator these limits for each identified intake. Note that withdrawal limits may be modified as necessary based on changing demands upon that water supply.

Purchased Water

Pennsylvania American Water Source ID: 16214 Source Name 7/1/2013 Source start date: Public Water Provider 7/1/2014 Source end date: Source Lat: Source Long: County 4,032,000 Max. Daily Purchase (gal) 720,000 Total Volume from Source (gal): **DEP Comments:** Please ensure that the sourcing of this water confirms to all rules and guidance provided by PA DEP.

WMP-01180 API/ID Number 047-069-00171 Operator: Chesapeake Energy

Carl Rotter OHI 1H - 837750

Important:

For each proposed secondary water source identified in your water management plan (i.e., groundwater well, lake/reservoir, recycled frac water, multi-site impoundment, out-of-state source), DEP makes no estimation of the availability of water. These sources may prove to be unsuitable water supplies. Please review the following notes:

- •For groundwater supply wells, DEP recommends that the operator contact the local health department prior to drilling any new well; and reminds the operator that all drinking water wells within 1,500 feet of a water supply well shall be flow- and quality-tested by the operator at the request of the drinking well owner prior to operation of the water supply well.
- For each proposed multi-site impoundment water source identified in your water management plan (if applicable), DEP will review the withdrawal limits established in the referenced Water Management Plan for current suitability and provide to the operator these limits for each identified intake. Note that withdrawal limits may be modified as necessary based on changing demands upon that water supply.

Recycled Frac Water

Source ID: 16219	Source Name	George Gantzer OHI 1H	Source start date:	7/1/2013	
				Source end date:	7/1/2014
		Source Lat:	Source Long	g: County	
Max. Daily Purchase (gal)		Total Volume from Source (gal):	1,008,000		
	DEP Co	omments:			

