

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

September 26, 2013

WELL WORK PERMIT

Horizontal 6A Well

This permit, API Well Number: 47-6900175, issued to CHESAPEAKE APPALACHIA, L.L.C., is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to all conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

In addition to the applicable requirements of this permit, and the statutes and rules governing oil and gas activity in WV, this permit may contain specific conditions which must be followed. Permit conditions are attached to this cover letter.

Per 35CSR-4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926-0499 ext. 1654.

James Martin

Chief

Operator's Well No: ROY FERRELL OHI 206H

Farm Name: FERRELL, ROY E.

API Well Number: 47-6900175

Permit Type: Horizontal 6A Well

Date Issued: 09/26/2013

PERMIT CONDITIONS

West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

CONDITIONS

- 1. This proposed activity may require permit coverage from the United States Army Corps of Engineers (USACOE). Through this permit, you are hereby being advised to consult with USACOE regarding this proposed activity.
- 2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than fifty (50) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.
- 3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the fill material shall be within plus or minus 2% of the optimum moisture content as determined by the standard proctor density test, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort. Each lift must meet 95 % compaction of the optimum density based on results from the standard proctor density test of the actual soils used in specific engineered fill sites. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.
- 4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.
- 5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations*, 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.
- 6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.
- 7. If any explosion or other accident causing loss of life or serious personal injury occurs in or about a well or well work on a well, the well operator or its contractor shall give notice, stating the particulars of the explosion or accident, to the oil and gas inspector and the Chief, within 24 hours of said accident.
- 8. During the casing and cementing process, in the event cement does not return to the surface, the oil and gas inspector shall be notified within 24 hours.

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Operator:	Chesapeak	e Appalachia, LLC	49447757	69-Ohio	7-Triadelphia	648-Valley Grove
			Operator ID	County	District	Quadrangle
2) Operator's Well N	Number: Ro	y Ferrell OHI 206H	V	Vell Pad Nam	e: Roy Ferrell OH	l Pad
3 Elevation, current	ground:	1196' Ele	evation, proposed p	post-construc	tion: _1	i 196'
4) Well Type: (a) G	as	Oil	Underground	d Storage		
(Other			-		_
(b) If	Gas: Shall	ow	Deep			
	Hori	zontal				
5) Existing Pad? Yes	s or No: Ye	5				
6) Proposed Target I	Formation(s),	Depth(s), Anticipat	ed Thicknesses and	d Associated	Pressure(s):	
Target formation- Marcellu	s, Target top TVD-	6616', Target base TVD- 6	676', Anticipated thickness-	60', Associated Pre	essure -4432	
7) Proposed Total V	ertical Depth:	6,660'				
8) Formation at Tota	ıl Vertical Dej	oth: Marcellus				
9) Proposed Total M	leasured Depti	h: 16,700'				
10) Approximate Fre	esh Water Stra	ata Depths: 34	0'			
11) Method to Deter	mine Fresh W	ater Depth: Fi	om analysis of water wells i	in the area		
12) Approximate Sal	ltwater Depths					
13) Approximate Co	al Seam Dept	hs: 691'				
14) Approximate De	pth to Possibl	e Void (coal mine,	karst, other):	691' void at	pandoned mine.	
15) Does proposed wadjacent to an act		ontain coal seams d so, indicate name ar		r No.		
16) Describe propose			lal zones between and including the Be	enson to the Marcellus. **(f v	ve should encounter a void,	place basket above and below
void area - balance cement	to bottom of void and	grout from basket to surface.	Run casing not less than 20'	below void nor more	than 50' below void.	
(*If freshwater is encountered	ed deeper than anticip	ated it must be protected, set	casing 50' below and cts)			
17) Describe fracturi	ng/stimulating	g methods in detail:		CONTRACT	_	_
Well will be perforated within the	target formation and stin	nulated with a slurry of water, sand,	and chemical additives at a high	rate. This will-be perford	ne (Cabdes while a	ugand perf method along
		ulated within the target formation				urface.
The well is produced throug	jh surface facilities co	nsisting of high pressure produced	uction units, vertical separation	on units, water and o	l storage tanks.	
18) Total area to be o	disturbed, incl	uding roads, stockr	ile area, pits, etc. (acres):	11.0	
19) Area to be distur				Office	of Oil and Gas nvironmental Pro	lection
	•	••	,,.	W	PH -8-13	Page 1 of 3

20)

CASING AND TUBING PROGRAM : 69 00175

ТҮРЕ	Size	New or Used	Grade	Weight per ft.	FOOTAGE: For Drilling	INTERVALS: Left in Well	CEMENT: Fill -up (Cu. Ft.)
Conductor	20"	New	J-55	94#	100'	100'	CTS
Fresh Water	13 3/8"	New	J-55	54.5#	741'	741'	680 sx/CTS
Coal	9 5/8"	New	J-55	40#	2,210'	2,210'	820 sx/CTS
Intermediate	7"	New	P-110	20#	If Needed	If Needed	If needed/As Possible
Production	5 1/2"	New	P-110	20#	16,700'	16,700'	Lead 1,260 sx Tail 2,120sx/100 inside intermediate
Tubing	2 3/8"	New	N-80	4.7#	Approx. 7,744'	Approx. 7,744'	
Liners							

WRH 9.8-13

ТҮРЕ	Size	Wellbore Diameter	Wall Thickness	Burst Pressure	Cement Type	Cement Yield
Conductor	20"	30"	0.25	2120	15.6 ppg	1.19/50% Excess
Fresh Water	13 3/8"	17.5"	0.380	2740	15.6 ppg	1.19/50% Excess
Coal	9 5/8"	12 1/4"	0.395	3950	15.6 ppg	1.19/50% Excess
Intermediate	7"	8 3/4"	.0317	4360	15.6 ppg	1.20/15% Excess
Production	5 1/2"	8 3/4"	0.361	12360	15.6 ppg	1.20/15% Excess
Tubing	2 3/8"	4.778"	0.190			
Liners						

PACKERS

Kind:	10K Arrowset AS1-X	
Sizes:	5 1/2"	
Depths Set:	Approx. 6,197'	

Received

Page 2 of 3

Office of Oil and Gas WV Dept. of Environmental Protection

All casing string	ralizer placement for each casing string. s will be ran with a centralizer at a minimum of 1 per every 3 joints of casing.
	protesty openies of caching.
2) Describe all c	ement additives associated with each cement type.
Flease see a	ttached sheets for Chemical Listing of Cement & Additives for Chesapeake Energy wells.
) Proposed bore	hole conditioning procedures.
	l be conditioned with circulation and rotation for a minimum of one bottoms up and continuing u
operator is satis	fied with borehole conditions.

Page 3 of 3



SLB Cement Additives

Product Name **Product Use** D046 antifoam D130 polyester flake - Icm S001 calcium chloride SPACER D130 polyester flake - Icm D020 bentonite extender antifoam D046 D130 polyester flake - Icm D044 granulated salt D153 Anti-Settling Agent Intermediate **SPACER** D020 bentonite extender D130 polyester flake - lcm D080 cement liquid dispersant D801 mid-temp retarder D047 antifoam agent SPACER MUDPUSH* Express B389 D206 Antifoaming Agent D031 Kick Off Plug barite B220 surfactant D167 UNIFLAC* S D154 low-temperature extender D400 EasyBLOK D046 antifoam D201 basic cements enabler D202 low-temperature solid dispersant D046 antifoam D167 UNIFLAC* S D065 TIC* Dispersant

69 00175

09/27/2013

Received

D201	basic cements enabler
D153	Anti-Settling Agent
CDACED	
SPACER	
B389	MUDPUSH* Express
D206	Antifoaming Agent
D031	barite
B220	surfactant

69 00175

<u>Chemical Name</u>	CAS Number	% Concentration Used
Fuller's earth (attapulgite)	8031-18-3	0.2% BWOC
Polypropylene glycol	25322-69-4	
polyethylene terephthalate	25038-59-9	0.125 lb/sk 6 9
calcium chloride	10043-52-4	2% BWOC
polyethylene terephthalate	25038-59-9	1 lb/bbl
bentonite	1302-78-9	20 lb/bbl
Fuller's earth (attapulgite)	8031-18-3	0.2% BWOC
Polypropylene glycol	25322-69-4	
polyethylene terephthalate	25038-59-9	0.125 lb/sk
sodium chloride	7647-14-5	10% BWOW
chrystalline silica	14808-60-7	0.15% BWOC
bentonite	1302-78-9	20 lb/bbl
polyethylene terephthalate	25038-59-9	1 lb/bbl
product classified as non-hazardous.		0.05 gal/sk
product classified as non-hazardous		0.01 gal/sk
polypropylene glycol	25322-69-4	0.02 gal/sk
		Joint Gamer
Carbohydrate	proprietary	1 lb/bbl
Silica Organic Polymer	proprietary	0.1 gal/bbl
barium sulfate	7727-43-7	310 lb/bbl
fatty acid amine	proprietary	0.10.100.
ethoxylated alcohol	proprietary	
glycerol	56-81-5	
2.2'-Iminodiethanol	111-42-2	1 gal/bbl
		1 94//221
aliphatic amide polymer	proprietary	0.35% BWOC
non-crystalline silica	7631-86-9	6% BWOC
boric acid	10043-35-3	0.8% BWOC
Fuller's earth (attapulgite)	8031-18-3	0.070 BVVCC
Polypropylene glycol	25322-69-4	0.2% BWOC
chrystalline silica	14808-60-7	0.276 BVVCC
metal oxide	proprietary	0.2% BWOC
sulphonated synthetic polymer	proprietary	J.2.70 DVVOO
formaldehyde (impurity)	50-00-0	0.3% BWOC
Fuller's earth (attapulgite)	8031-18-3	0.570 0000
Polypropylene glycol	25322-69-4	0.2% BWOC
aliphatic amide polymer	proprietary	0.2% BWOC
Sodium Polynaphthalene Sulfonate	9008-63-3	0.33 % BVVOC
Sodium Sulfate	7757-82-6	0.25% PWOC
Codiant Gunate	1101-02-0	0.25% BWOC


00175



chrystalline silica	14808-60-7	
metal oxide	proprietary	0.2% BWOC
chrystalline silica	14808-60-7	0.2% BWOC
		. 6
Carbohydrate	proprietary	proprietary
Silica Organic Polymer	proprietary	proprietary
barium sulfate	7727-43-7	7727-43-7
fatty acid amine	proprietary	proprietary
ethoxylated alcohol	proprietary	proprietary
glycerol	56-81-5	56-81-5
2.2'-Iminodiethanol	111-42-2	111-42-2

00175

09/27/2013 Received



WRH 3-3-13



STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS

FLUIDS/ CUTTINGS DISPOSAL & RECLAMATION PLAN

Operator Name Chesapeake A	ppalachia, LLC		OP Code _49447757
Watershed (HUC 10) Wheeli	ng Creek	Quadrangle	648-Valley Grove
Elevation 1196	County 69-Ohio		District7-Triadelphia
Will a pit be used for drill cutt If so, please describe Will a synthetic liner Proposed Disposal M Lar Une Ret Off	anticipated pit waste: Closed loop be used in the pit? Yes ethod For Treated Pit Wastes: d Application derground Injection (UIC Permi use (at API Number at next anticipate Site Disposal (Supply form WW	No X If so I	s time- cuttings will be taken to a permitted landfill. so, what ml.? 19/ 2D0413175/ 2D0610306/ 2D0610317 ed with the WR-34/DDMR &/or permit addendum. ation) d reused or taken to a permitted disposal facility.
Will closed loop system be use	ed? Yes		
	or this well? Air, freshwater, oil		alt saturate mud
Additives to be used in drilling	pe? Synthetic, petroleum, etc. Synthetic, petroleum, etc. Synthetic		
	? Leave in pit, landfill, removed		
-If left in pit and plan -Landfill or offsite na	to solidify what medium will be me/permit number? Meadow/# SWF-1032, St	used? (cement, lim	
I certify that I unders on August 1, 2005, by the Offi provisions of the permit are elaw or regulation can lead to e I certify under penal application form and all atta obtaining the information, I be	tand and agree to the terms and one of Oil and Gas of the West Vinforceable by law. Violations of the order of the conforcement action. The of law that I have personally coments thereto and that, based	conditions of the GI rginia Department of f any term or condi examined and am d on my inquiry of true, accurate, and	ENERAL WATER POLLUTION PERMIT issued of Environmental Protection. I understand that the ition of the general permit and/or other applicable a familiar with the information submitted on this of those individuals immediately responsible for complete. I am aware that there are significant
Company Official (Typed Nar	ne) Danielle Southall		Received
Company Official Title Regu	atory Analyst		110001100
Subscribed and sworn before n	ne this 2nd day of (luguot	Notar Pries Buckhannon, WV 2 My commission expires Novem

Chesapeake App	palachia, LLC		- V & 1
Proposed Revegetation Treat	ment: Acres Disturbed	0+/- Prevegetation p	он
	Tons/acre or to corre		
	or equivalent) 500	lbs/acre (500 lbs minimum)	
Mulch Hay/Str	aw 2.5	,	
Mulch		_Tons/acre	
		Seed Mixtures	
	ea I		rea II
Seed Type White Clover	lbs/acre 15	Seed Type	lbs/acre
		White Top	15
Red Top	15	Red Top	15
Orchard Grass	20	Orchard Grass	20
Plan Approved by:	Handeste		
Comments:			
Title: Oil and Gas In	spector	Date: 8-3-12	
Field Reviewed?	Yes) No	

Received

Octon or Ct. and Gas WV Dept. of Environmental Protection

Supplier Name	Product Name	Product Use	Chemical Name	CAS Number
			Didecyl Dimethyl Ammonium Chloride	007173-51-1
			Ethanol	000064-17-5
	ALPHA 1427	Biocide	Glutaraldehyde (Pentanediol)	000111-30-8
			Quaternary Ammonium Compound	068424-85-1
			Water	007732-18-5
	BF-7L	Buffer	Potassium Carbonate	000584-08-7
			Choline Chloride	000067-48-1
	ClayCare	Clay Stabilizer	Water	007732-18-5
BAKER HUGHES	Enzyme G-I	Breaker	No Hazardous Components	NONE
	ENZYME G-NE	Breaker	No Hazardous Components	NONE
	FRW-18	Friction Reducer	Petroleum Distillate Hydrotreated Light	064742-47-8
	OW 21 DE	0-1	Petroleum Distillate Blend	N/A-014
	GW-3LDF	Gel	Polysaccharide Blend	N/A-021
	2041 577 01 700		Diethylene Glycol	000111-46-6
	SCALETROL 720	Scale Inhibitor	Ethylene Glycol	000107-21-1
			Boric Acid	010043-35-3
	XLW-32	Crosslinker	Methanol (Methyl Alcohol)	000067-56-1
	APB01 (AMMONIUM PERSUFATE BREAKER)	Breaker	Ammonium Persulfate	007727-54-0
	B05 (LOW PH BUFFER)	Buffer	Acetic acid	000064-19-7
	BXL03 Borate XL Delayed High Temp	Crosslinker	No Hazardous Components	NONE
FRAC TECH SERVICES	FRW-200	Friction Reducer	No Hazardous Components	NONE
	HVG01 (TURQUOISE-1 BULK)	Gelling Agent	Petroleum Distillate Hydrotreated Light	064742-47-8
	KCLS-4	Clay Stabilizer	No Hazardous Components	NONE
	LTB-1	Breaker	Ammonium Persulfate	N/A



Supplier Name	Product Name	Product Use	Chemical Name	CAS Number
			Ethanol	000064-17-5
NALCO	EC6110A	Biocide	Glutaraldehyde (Pentanediol)	000111-30-8
ONESOURCE			Quaternary Ammonium Compounds	N/A-063
	EC6629A	Biocide	No Hazardous Components	NONE
	WBK-133 OXIDIZER	Breaker	Ammonium Persulfate	007727-54-0
	WBK-134	Danakas	Ammonium Persulfate	007727-54-0
	VVBN-134	Breaker	Crystalline Silica (Quartz Sand, Silicon Dioxide)	014808-60-7
	W00 0041 0		Proprietary Non Hazardous Salt	N/A-229
	WCS-631LC	Clay Stabilizer	Water	007732-18-5
	WFR-55LA	Friction Reducer	No Hazardous Components	NONE
	WGA-15L	Potroloum Di		064742-47-8
WEATHERFORD		P	Potassium Carbonate	000584-08-7
	WPB-584-L	Buffer	Potassium Hydroxide	001310-58-3
	WXL-101LE	Corsslinker	No Hazardous Components	NONE
	WXL-101LM	Crosslinker	Petroleum Distillate Hydrotreated Light	064742-47-8
			Water	007732-18-5
		The second secon	Ethylene Glycol	000107-21-1
	WXL-105L	Crosslinker	Boric Acid	010043-35-3
			Ethanolamine	000141-43-5
	B244 Green-Cide 25G	Biocide	Glutaraldehyde	111-30-8
	L071 Temporary Clay Stabilizer	Clay Stabilizer	Cholinium Chloride	67-48-1
	Breaker J218		Diammonium Peroxidisulphate	7727-54-0
SCHLUMBERGER	EB-Clean* J475 Breaker	Breaker	Diammonium Peroxidisulphate	7727-54-0
			Distillates (petroleum),	64742-47-8
	Friction Reducer B315	Friction Reducer	Hydrotreated light Aliphatic Alcohol Glycol Ether	Proprietary
	Friction Reducer J609		Ammonium Sulfate	7783-20-2



4 - 13 2018

Supplier Name	Product Name	Product Use	Chemica Suane 0 0	LAS Number	
	Water Gelling Agent J580	Gel	Carbohydrate Polymer Propriet		
SCHLUMBERGER	Scale Inhibitor B317	Scale Inhibitor	Trisodium ortho phosphate Ethane-1, 2-diol	7601-54-9 107-21-1	
COLICONIDENCE	Borate Crosslinker J532	Crosslinker	Aliphatic polyol Sodium tetraborate decahydrate	Proprietary 1303- 96-4	
	Crosslinker J610	Crossilikei	Aliphatic polyol Potassium hydroxide	Proprietary 1310- 58-3	

09/27/2013 Received

west virginia department of environmental protection



Water Management Plan: Primary Water Sources



WMP-01398

API/ID Number:

047-069-00175

Operator:

Chesapeake Energy

Roy Ferrell OHI 206H

Important:

For each proposed primary water source (including source intakes for purchased water sources) identified in your water management plan, and summarized herein, DEP has made an evaluation concerning water availability over the specified date range. DEP's assessment is based on the following considerations:

- •Statistical analysis of historical USGS stream gauge data (transferred to un-gauged locations as necessary);
- •Identification of sensitive aquatic life (endangered species, mussels, etc.);
- Quantification of known existing demands on the water supply (Large Quantity Users);
- •Minimum flows required by the Army Corps of Engineers; and
- Designated stream uses.

Based on these factors, DEP has provided, for each intake location (and origination point for purchased water), a reference gauge location and discharge flow reading which must be surpassed prior to withdrawals. Additionally, DEP has established a minimum passby flow at the withdrawal location which must also be surpassed prior to withdrawals. These thresholds are considered terms of the permit and are enforceable as such.

DEP is aware that some intake points will be used for mutiple wells and well sites. In these cases, the thresholds set by the Water Management Plan are to be interepreted as total withdrawal limits for each location over the specified date range regardless of how many wells are supported by that intake.

For all purchased water intakes, determinations of water availability are made at the original source intake location. It is the responsibility of the Oil and Gas Operator, not the seller, to cease withdrawal of water from the seller when flows are less than the minimum gauge reading at the stream gauge referenced by the Water Management Plan in order to protect stream uses.

Note that the determinations made herein are based on the best available data, but it is impossible to predict water availability in the future. While the DEP has carefully established these minimum withdrawal thresholds, it remains the operator's responsibility to protect aquatic life at all times. Approval to withdrawal is contingent upon permission from the land owner. It is the responsibility of the operator to secure and maintain permission prior to any withdrawals.

The operator is reminded that 24-48 hours prior to withdrawing (or purchasing) water, DEP must be notified by email at DEP.water.use@wv.gov.

APPROVED SEP 2 0 2013

Source Summary

WMP-01398 API Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H Stream/River **Brownlee Land Ventures** Ohio River WP 1 (Beech Bottom Staging Area) Brooke Owner: Source Start Date End Date Total Volume (gal) Max. daily purchase (gal) Intake Latitude: Intake Longitude: 9/1/2013 9/1/2014 6,552,000 40.226889 -80.658972 ✓ Regulated Stream? Ohio River Min. Flow Ref. Gauge ID: 9999999 Ohio River Station: Willow Island Lock & Dam Max. Pump rate (gpm): 6.000 Min. Gauge Reading (cfs): Min. Passby (cfs) 6,468.00 Refer to the specified station on the National Weather Service's Ohio River forecast DEP Comments: website: http://www.erh.noaa.gov/ohrfc//flows.shtml Ohio Little Wheeling Creek WP 1 (Rt. 40 Staging Area) Owner: JDS Investments, LLC Source Max. daily purchase (gal) Start Date End Date Total Volume (gal) Intake Latitude: Intake Longitude: -80.591145 9/1/2013 9/1/2014 6,552,000 40.078324 Regulated Stream? Ref. Gauge ID: 3112000 WHEELING CREEK AT ELM GROVE, WV Max. Pump rate (gpm): Min. Gauge Reading (cfs): 64.80 Min. Passby (cfs) 2.83 2,000 **DEP Comments:** Source Middle Wheeling Creek @ Anderson Withdrawal Site Brooke Owner: Paul & Verna Anderson Total Volume (gal) Max. daily purchase (gal) Intake Latitude: Intake Longitude: Start Date End Date 9/1/2013 9/1/2014 6,552,000 40.04409 -80.55348 Regulated Stream? WHEELING CREEK AT ELM GROVE, WV Ref. Gauge ID: 3112000 Min. Gauge Reading (cfs): Min. Passby (cfs) 4.17 Max. Pump rate (gpm): 2,500 62.57

DEP Comments:

Source Summary

WMP-01398

API Number:

047-069-00175

Operator:

Chesapeake Energy

Rov Ferrell OHI 206H

Purchased Water

Source Ohio River @ J&R Excavating Marshall

Owner:

J&R Excavating

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

9/1/2013

9/1/2014

6,552,000

1,890,000

39.998509

-80.737336

✓ Regulated Stream?

Ohio River Min. Flow Ref. Gauge ID:

999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

The Village of Valley Grove

Ohio

Owner:

The Village of Valley Grove

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

9/1/2013

9/1/2014

6,552,000

Ohio River Min. Flow Ref. Gauge ID:

720,000

999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

✓ Regulated Stream?

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:

Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

Source

Ohio County PSD

Ohio

Owner:

Ohio county PSD

Start Date

End Date

Total Volume (gal)

Max. daily purchase (gal)

Intake Latitude: Intake Longitude:

9/1/2013

9/1/2014

6,552,000

720,000

✓ Regulated Stream?

Ohio River Min. Flow Ref. Gauge ID:

9999999

Ohio River Station: Willow Island Lock & Dam

Max. Pump rate (gpm):

Min. Gauge Reading (cfs):

6,468.00

Min. Passby (cfs)

DEP Comments:


Refer to the specified station on the National Weather Service's Ohio River forecast

website: http://www.erh.noaa.gov/ohrfc//flows.shtml

WMP-01398 API/ID Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H Ohio River @ J&R Excavating Source Latitude: 39.998509 Source ID: 23103 Source Name J&R Excavating Source Longitude: -80.737336 5030106 HUC-8 Code: 9/1/2013 Anticipated withdrawal start date: 25000 Marshall Drainage Area (sq. mi.): County: 9/1/2014 Anticipated withdrawal end date: **Endangered Species?** ✓ Mussel Stream? 6,552,000 Total Volume from Source (gal): Trout Stream? ☐ Tier 3? Max. Pump rate (gpm): Ohio River Min. Flow Regulated Stream? Max. Simultaneous Trucks: Proximate PSD? Max. Truck pump rate (gpm) Gauged Stream? Ohio River Station: Willow Island Lock & Dam 9999999 Reference Gaug 25,000.00 6468 Gauge Threshold (cfs): Drainage Area (sq. mi.)

Month	Median monthly flow (cfs)	Threshold (+ pump	Available water (cfs)
1	45,700.00	-	
2	49,200.00	14	-
3	65,700.00		4
4	56,100.00	100	-
5	38,700.00	1.40	-
6	24,300.00		
7	16,000.00	-	-
8	13,400.00		-
9	12,800.00		
10	15,500.00	1.6	-
11	26,300.00	4	-
12	41,300.00	-	





Water Availability Assessment of Location

Min. Gauge Reading (cfs):	
Ungauged Stream Safety (cfs):	0.00
Headwater Safety (cfs):	0.00
Pump rate (cfs):	
Downstream Demand (cfs):	0.00
Upstream Demand (cfs):	0.00
Base Threshold (cfs):	

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.


Source Detail WMP-01398 API/ID Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H The Village of Valley Grove Source ID: 23105 Source Name Source Latitude: -The Village of Valley Grove Source Longitude: -5030106 HUC-8 Code: 9/1/2013 Anticipated withdrawal start date: Ohio Drainage Area (sq. mi.): 25000 County: 9/1/2014 Anticipated withdrawal end date: **Endangered Species?** ✓ Mussel Stream? Total Volume from Source (gal): 6,552,000 Trout Stream? Tier 3? Ohio River Min. Flow Max. Pump rate (gpm): Regulated Stream? Proximate PSD? Wheeling Water Department Max. Simultaneous Trucks: Max. Truck pump rate (gpm) Gauged Stream? Reference Gaug 9999999 Ohio River Station: Willow Island Lock & Dam 25,000.00 Drainage Area (sq. mi.) Gauge Threshold (cfs): 6468 Median Estimated Threshold monthly flow Available (+ pump Month (cfs) water (cfs) 45,700.00 1 2 49,200.00 65,700.00 3 56,100.00 4 5 38,700.00 6 24,300.00 7 16,000.00 8 13,400.00 9 12,800.00 10 15,500.00 11 26,300.00 12 41,300.00

Water Availability Assessment of Location Water Availability Profile Base Threshold (cfs): 80000 Upstream Demand (cfs): Downstream Demand (cfs): 60000 eam is regulated by the Army Corps of here to the stated thresholds to Pump rate (cfs): 40000 maintain the minimum guaranteed flow requirements. Headwater Safety (cfs): 0.00 20000 Ungauged Stream Safety (cfs): 0.00 1 2 3 4 5 6 9 7 8 10 11 12 Min. Gauge Reading (cfs): Passby at Location (cfs): Median Monthly Flow — Threshold

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

WMP-01398 API/ID Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H Source ID: 23106 Ohio County PSD Source Name Source Latitude: -Ohio county PSD Source Longitude: -5030106 HUC-8 Code: 9/1/2013 Anticipated withdrawal start date: Ohio Drainage Area (sq. mi.): 25000 County: Anticipated withdrawal end date: 9/1/2014 **Endangered Species?** ✓ Mussel Stream? Total Volume from Source (gal): 6,552,000 Trout Stream? Tier 3? Ohio River Min. Flow Max. Pump rate (gpm): Regulated Stream? Proximate PSD? Max. Simultaneous Trucks: Wheeling Water Department Max. Truck pump rate (gpm) Gauged Stream? Reference Gaug 9999999 Ohio River Station: Willow Island Lock & Dam 25,000.00 Drainage Area (sq. mi.) Gauge Threshold (cfs): 6468


Month	Median monthly flow (cfs)	Threshold (+ pump	<u>Estimated</u> <u>Available</u> water (cfs)	
1	45,700.00	G.	-	
2	49,200.00	le l	-	
3	65,700.00	- 2		
4	56,100.00	-	- *	
5	38,700.00	-		
6 7	24,300.00		· ·	
	16,000.00			
8	13,400.00	/4 /	-	
9	12,800.00			
10	15,500.00	*		
11	26,300.00	1.0	4	
12	41,300.00	,		



"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

			<u>5041</u>	cc Detail			
	WMP-0	1398	API/ID Number: Roy Fe	047-069-0017 rrell OHI 206H	5 Operator:	Chesapea	ke Energy
Source II	D: 23100 Sou		o River WP 1 (Beech B wnlee Land Ventures	ottom Staging Area		titude: 40.2 gitude: -80.	226889 .658972
	HUC-8 Code: Drainage Area (dangered Species? out Stream?		000 County: Stream?	Brooke	Anticipated withdrawal sta Anticipated withdrawal e Total Volume from Sour	nd date:	9/1/2013 9/1/2014 6,552,000
 ✓ Regulated Stream? Ohio River Min. Flow ✓ Proximate PSD? Beech Bottom Water Dept. ✓ Gauged Stream? 					s Trucks: 0		
	Reference Gaug Drainage Area (sq	9999999 . mi.) 25	Ohio River Station	: Willow Island Lock	c & Dam Gauge Thresh	nold (cfs):	6468
Month	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs)				
1	45,700.00	-					
2	49,200.00	-	14				
3	65,700.00		34				
4	56,100.00	-					
5	38,700.00	7					
6	24,300.00						

Water Availability Profile



Water Availability Assessment of Location

-
13.37
0.00
0.00

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

16,000.00

13,400.00

12,800.00 15,500.00

26,300.00

41,300.00

8

9

10

11 12

WMP-01398 API/ID Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H Little Wheeling Creek WP 1 (Rt. 40 Staging Area) Source ID: 23101 Source Name Source Latitude: 40.078324 JDS Investments, LLC Source Longitude: -80.591145 5030106 HUC-8 Code: Anticipated withdrawal start date: 9/1/2013 Ohio Drainage Area (sq. mi.): 13.94 County: Anticipated withdrawal end date: 9/1/2014 **Endangered Species?** ✓ Mussel Stream? Total Volume from Source (gal): 6,552,000 Trout Stream? Tier 3? Max. Pump rate (gpm): 2,000 Regulated Stream? Proximate PSD? Max. Simultaneous Trucks: Max. Truck pump rate (gpm) Gauged Stream? Reference Gaug 3112000 WHEELING CREEK AT ELM GROVE, WV

Month	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs)
1	13.81	10.62	3.55
2	17.62	10.62	7.36
3	24.44	10.62	14.18
4	18.14	10.62	7.88
5	11.06	10.62	0.80
6	5.03	10.62	-5.23
7	2.22	10.62	-8.03
8	1.30	10.62	-8.96
9	0.83	10.62	-9.43
10	1.37	10.62	-8.89
11	4.31	10.62	-5.95
12	9.77	10.62	-0.49

Drainage Area (sq. mi.)

Water Availability Profile

Median Monthly Flow — Threshold

5

281.00

Water Availability Assessment of	Location
Base Threshold (cfs):	1.89
Upstream Demand (cfs):	3.34
Downstream Demand (cfs):	0.00
Pump rate (cfs):	4.46
Headwater Safety (cfs):	0.47
Ungauged Stream Safety (cfs):	0.47
Min. Gauge Reading (cfs):	64.80
Passby at Location (cfs):	2.83

Gauge Threshold (cfs):

38

11

12

3

1

2

[&]quot;Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

WMP-01398 API/ID Number: 047-069-00175 Operator: Chesapeake Energy Roy Ferrell OHI 206H Source ID: 23102 Middle Wheeling Creek @ Anderson Withdrawal Sit Source Name Source Latitude: 40.04409 Paul & Verna Anderson Source Longitude: -80.55348 5030106 HUC-8 Code: Anticipated withdrawal start date: 9/1/2013 Drainage Area (sq. mi.): 20.54 Brooke County: Anticipated withdrawal end date: 9/1/2014 **Endangered Species?** ✓ Mussel Stream? Total Volume from Source (gal): 6,552,000 Trout Stream? ☐ Tier 3? 2,500 Max. Pump rate (gpm): Regulated Stream? Proximate PSD? Max. Simultaneous Trucks: 0 Gauged Stream? Max. Truck pump rate (gpm) Reference Gaug 3112000 WHEELING CREEK AT ELM GROVE, WV

<u>Month</u>	Median monthly flow (cfs)	Threshold (+ pump	Estimated Available water (cfs)	
1	20.35	9.74	10.73	
2	25.97	9.74	16.35	
3	36.01	9.74	26.39	
4	26.73	9.74	17.11	
5	16.30	9.74	6.68	
6	7.42	9.74	-2.20	
7	3.28	9.74	-6.34	
8	1.92	9.74	-7.70	
9	1.22	9.74	-8.40	
10	2.02	9.74	-7.60	
11	6.35	9.74	-3.27	

4.78

281.00

Water Availability Profile 40 30 20 10 1 2 3 4 5 6 7 8 9 10 11 12 Median Monthly Flow — Threshold

Min. Gauge Reading (cfs): Passby at Location (cfs):	62.57 4.17
Ungauged Stream Safety (cfs):	0.69
Headwater Safety (cfs):	0.69
Pump rate (cfs):	5.57
Downstream Demand (cfs):	0.00
Upstream Demand (cfs):	0.00
Base Threshold (cfs):	2.78

Gauge Threshold (cfs):

38

"Threshold", as depicted in the chart above is meant only to indicate the calculated base threshold at the proposed withdrawal location. This value does not include the proposed pump rate or existing demand on the stream. Refer to the monthly breakdown above for a more complete estimation of water availability by month.

Drainage Area (sq. mi.)

12

14.40

west virginia department of environmental protection



Water Management Plan: Secondary Water Sources



WMP-01398

API/ID Number

047-069-00175

Operator:

Chesapeake Energy

Roy Ferrell OHI 206H

Important:

For each proposed secondary water source identified in your water management plan (i.e., groundwater well, lake/reservoir, recycled frac water, multi-site impoundment, out-of-state source), DEP makes no estimation of the availability of water. These sources may prove to be unsuitable water supplies. Please review the following notes:

- For groundwater supply wells, DEP recommends that the operator contact the local health department prior to drilling any new well; and reminds the operator that all drinking water wells within 1,500 feet of a water supply well shall be flow- and quality-tested by the operator at the request of the drinking well owner prior to operation of the water supply well.
- For each proposed multi-site impoundment water source identified in your water management plan (if applicable), DEP will review the withdrawal limits established in the referenced Water Management Plan for current suitability and provide to the operator these limits for each identified intake. Note that withdrawal limits may be modified as necessary based on changing demands upon that water supply.

Purchased Water

Source ID: 23104 Source Name

Pennsylvania American Water

Source start date:

9/1/2013

Public Water Provider

Source end date:

9/1/2014

Source Lat:

Source Long:

County

Max. Daily Purchase (gal)

720,000

Total Volume from Source (gal):

6,552,000

DEP Comments:

Please ensure that the sourcing of this water confirms to all rules and guidance

provided by PA DEP.

WMP-01398 API/ID Number 047-069-00175 Operator: Chesapeake Energy

Roy Ferrell OHI 206H

Important:

For each proposed secondary water source identified in your water management plan (i.e., groundwater well, lake/reservoir, recycled frac water, multi-site impoundment, out-of-state source), DEP makes no estimation of the availability of water. These sources may prove to be unsuitable water supplies. Please review the following notes:

- •For groundwater supply wells, DEP recommends that the operator contact the local health department prior to drilling any new well; and reminds the operator that all drinking water wells within 1,500 feet of a water supply well shall be flow- and quality-tested by the operator at the request of the drinking well owner prior to operation of the water supply well.
- •For each proposed multi-site impoundment water source identified in your water management plan (if applicable), DEP will review the withdrawal limits established in the referenced Water Management Plan for current suitability and provide to the operator these limits for each identified intake. Note that withdrawal limits may be modified as necessary based on changing demands upon that water supply.

Recycled Frac Water

Source ID: 23107 Source Name Chad Glauser OHI 10H Source start date: 9/1/2013

Source end date: 9/1/2014

Source Lat: Source Long: County

Max. Daily Purchase (gal) Total Volume from Source (gal): 1,638,000

DEP Comments:

