

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

PERMIT MODIFICATION APPROVAL

April 08, 2015

SWN PRODUCTION COMPANY, LLC POST OFFICE BOX 12359 SPRING, TX 77391

Re: Permit Modification Approval for API Number 6900184 , Well #: ALICE EDGE OHI 6H Modify casing for directional work

Oil and Gas Operator:

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

Please call James Martin at 304-926-0499, extension 1654 if you have any questions.

Sincerely,

Gene Smith

Assistant Chief of Permitting

- Le Gene Smith

Office of Oil and Gas



Jane Lew, WV 26378 PHONE: (832) 796-1610

April 8, 2015

Ms. Laura Adkins Office of Oil & Gas 601 57th Street Charleston, WV 25304

RE: Modification to Alice Edge OHI 6H, and Alice Edge OHI 210H

Dear Laura:

Enclosed please find modification requests for the above captioned wells. We would like to modify the casing for directional work only. We will not be crossing any additional leases. These wells are situated on the Edge's property, in Liberty District, Ohio County, West Virginia.

If you have any questions or desire additional information, please me at 304-884-1614

Thank you.

Sincerely,

Dee Southall

Regulatory Supervisor

Southwestern Energy Production Company, LLC

PO Box 1300

Jane Lew, WV 26378

Received

APR - 8 2015

Office of Oil and Gas
WV Dept. of Environmental Protection

R2 AV+

The Right People doing the Right Things, wisely Investing the cash flow from our underlying Assets, will create Value+

A4 70.4769 9 0 0 1 8 4 M6 A OPERATOR WELL NO. Alice Edge OHI 6H

Well Pad Name: Alice Edge OHI Pad

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS WELL WORK PERMIT APPLICATION

1) Well Operat	tor: SWN Prod	uction Co.,	LLC 4	1945129	24	69- Ohio	3- Libert	648- Valley Grove
				Operator	ID	County	District	Quadrangle
2) Operator's V	Well Number: Al	ice Edge O	HI 6H	V	Vell Pad	Name: Alice	e Edge OHI	Pad
3) Farm Name	/Surface Owner:	Alice Mae	Edge	Pub	olic Road	d Access: Sta	ate Route 4	.0
4) Elevation, c	urrent ground:	1198'	Elev	ation, pro	oposed j	post-construct	tion: 1198'	
5) Well Type	(a) Gas x		Oil		Unde	rground Stora	ige	
	Other							
	(b)If Gas Sha	allow x		D	еер			
	Но	rizontal						
6) Existing Pac	d: Yes or No ye	s						
	arget Formation(s ion- Marcellus, Targe						()	: ciated Pressure- 4176'
8) Proposed To	otal Vertical Dept	th: 6390'						
9) Formation a	t Total Vertical I	Depth: Mai	rcellus					
10) Proposed T	otal Measured D	epth: 19,	200'					
11) Proposed F	Horizontal Leg Le	ength: 12,0	032'					
12) Approxima	nte Fresh Water S	trata Depths	s: <u>4</u>	25'				
13) Method to	Determine Fresh	Water Dept	ths: from	m log an	nalysis a	and nearby w	vater wells	
14) Approxima	ite Saltwater Dep	ths: 1050'						
15) Approxima	ate Coal Seam De	epths: 580'						
16) Approxima	ate Depth to Poss	ible Void (c	oal mine	, karst, o	ther): _	None that we	are aware	of.
12 T 20 12 12 12 12 12 12 12 12 12 12 12 12 12	osed well location			Yes	x	No	0	eived
(a) If Yes, pro	ovide Mine Info:	Name:	Tunnel	Ridge			HEU	Civos
		Depth:	558'				APR	- 8 2 015
		Seam:	Pittsbur	gh #8			1,000	
		Owner:	Tunnel	Ridge		-	Office	of Oll and Gas environmental Protection
					wk	2-15	MA Debr. or p	76470

47 0 6 9 0 0 1 8 4 MO API NO. 47-69 OPERATOR WELL NO. Alice Edge OHI 6H

Well Pad Name: Alice Edge OHI Pad

18)

CASING AND TUBING PROGRAM

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	20"	New	F-25	94#	100'	100'	CTS
Fresh Water	13 3/8"	New	J-55	54.5#	630'	630'	580 sx/CTS
Coal	9 5/8"	New	J-55	40#	2107'	2107'	630 sx/CTS
Intermediate	7"	New	HCP-110	20#	If Needed	If Needed	If Needed/As Needed
Production	5 1/2"	New	HCP-110	20#	19,200'	19,200'	Least 1150ax 1500 tall sw/100* Inside laws
Tubing	2 3/8'	New	P-110	4.7#	Approx. 6779'	Approx. 6779'	
Liners							

4-7-15

ТУРЕ	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Max. Associated Surface Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20"	30"	0.25	2120	0.020	Class A	1.19/50% Excess
Fresh Water	13 3/8"	17.5"	0.380	2740	0.020	Class A	1.19/50% Excess
Coal	9 5/8"	12 1/4"	0.395	3950	0.020	Class A	1.19/50% Excess
Intermediate	7"	8 3/4"	0.317	4360	0.020	Class A	1.20/15% Excess
Production	5 1/2"	8 3/4"	0.361	12360	0.020	Class A	1.20/15% Excess
Tubing	2 3/8"	4.778"	0.190				
Liners							

		PACKERS	Received
Kind:	10K Arrowset AS1-X		0015
Sizes:	5 1/2"		Arti
Depths Set:			Office of Oil and Gas WV Dept. of Environmental Protection

Page 2 of 3



