

## west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, S.E. Charleston, WV 25304 (304) 926-0450 fax: (304) 926-0452

Austin Caperton, Cabinet Secretary www.dep.wv.gov

Wednesday, December 18, 2019 PERMIT MODIFICATION APPROVAL Horizontal 6A / New Drill

SWN PRODUCTION COMPANY, LLC **POST OFFICE BOX 12359** 

SPRING, TX 773914954

Re:

Permit Modification Approval for FRANZ THOMAN OHI 10H

47-069-00312-00-00

Change cement density for production.

## SWN PRODUCTION COMPANY, LLC

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

If there are any questions, please feel free to contact me at (304) 926-0450.

James A. Martin

Chief

Operator's Well Number: FRANZ THOMAN OHI 10H

Farm Name: FRANZ THOMAN

U.S. WELL NUMBER: 47-069-00312-00-00

Horizontal 6A New Drill

Date Modification Issued: December 18th, 2019

Promoting a healthy environment.



SWN Production Company, LLC 1300 Fort Pierpont Dr, Ste 201 Morgantown, WV 26508 Tel: 304 884 1610 Fax: 304 471 2497 www.swn.com

December 18, 2019

Ms. Laura Adkins Office of Oil & Gas 601 57<sup>th</sup> Street Charleston, WV 25304

RE: Proposed Modification: Franz Thoman OHI 10H

Dear Ms. Adkins

Enclosed please find a new WBD with modified production density for the above captioned well. Drilling is wanting to change the production density to 14.5 in the cement details. We are wanting to use this density on the Franz Thoman OHI 10H as a test well to see if we want to use this on future wells. The change is a slurry which is currently being used in WV.

If you have any questions or desire additional information, please me at 304-884-1613

Thank you.

Sincerely,

Brittany Woody

Brittany Woody Senior Regulatory Analyst Southwestern Energy Production Company, LLC Office of oil and Gass

Office of oil and Gass

DEC 1 & 2019

WV Department of Environmental Protection



## **Proposed Drilling Program Southwestern Energy Company** Well: Re-entry Rig: TBD FRANZ THOMAN OHI 10 Field: PANHANDLE FIELD \ Prospect: **PANHANDLE** WV County: OHIO State: -80.6599 Longitude SHL: 40.1367 Latitude outhwestern Energy -80.6455 Longitude BHL: 40.1209 Latitude **KB Elev:** 1,164 ft MSL KB: 26 ft AGL **GL Elev:** 1,138 ft MSL 0'to 446' Air / Mist PROD TOC Lead @ 1,767 'MD 446 ' to 1,767 ' PROD TOC Tail @ 5,100 ' MD Air / Mist **TUBULAR DETAIL** Size (in) Weight Grade From To 100 ' 0 ' 1,767 ' to 5,361 ' Conductor: 20 94.0# H-40 Air / Mist 0 ' Surf./Coal: 13.375 48.0# H-40 426' Intermediate: 9.625 36.0# J-55 0 ' 1,747 0' 12,788 **Production:** 5.5 20.0# HCP-110 **CEMENT DETAIL** Sacks Class Density Conductor 151 19.3 Α 415 15.6 Surface Α Intermediate 678 15.6 Production Lead 828 POZ/A 14.5 Officuation Tail 1742 POZ/A 14.5 Rieshwater Depth - 326 'TVD TD at 5,361 ' KOP at 5,361 'MD 5,361 'to 6,298 ' Coal Depth - 343 'TVD 12.0 - 12.5 ppg Saltwater Depth - 470 'TVD TVD - 5,895 ' TMD - 12,788 ' TD at 12,788 'MD 5,710 ' TVD 5,895 ' Target Center Onondaga 5,726 'TVD EOB at 5,895 'TVD 6,298 ' to 12,788 ' SHL Onondaga 5,911 'TVD 12.0 - 12.5 ppg Created by: C R Hall on 12/16/2019