

.....District, Ohio County, W. Va.
 Wheeling Producing Oil & Gas Co.
 S. W. Brockmeyer.
 Elevation, 655'; starts 60' below Pittsburgh Coal.
 3600' S. 30° E. of Thompson No. 2 well.

	Top.	Bottom.
Gravel	0	60
Lime	60	105
Fire clay	105	130
Red shale, slate	130	132
Fire clay, fine	132	150
Red rock	165	185
White slate, lime, and some shale	185	300
Shell	300	302
Red rock	302	322
Slate, white (horizon of Up. Freeport C.)	322	400
Lime	400	486½
Slate, white	486½	492½
Coal, Lower Freeport	526½	531½
Lime	537½	565
Slate, black	565	637
Cow Run Sand, coarse, (Homewood SS.) (Few inches coal--Mercer)	637	746
Sand	746	798
Top Salt Sand (salt water)	798	855
Black slate	855	861
Sand, white, hard	891	930
Big Lime	930	986
Kemper Sand	986	1020
Break	1020	1025
Big Injun Sand (show oil, 1025')	1025	1065
Black slate		