



NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL  
DEPARTMENT OF MINES AND GEOLOGICAL SURVEY  
BUREAU OF OIL AND GAS

Collins & Wilson  
c/o A. B. Mason  
P.O. Box 100  
Tulsa, Oklahoma

July 25, 1930

State

County

City

Address

Oil and Gas

Proposed Location

Notice is hereby given that the undersigned proposes to locate an oil and gas well on the land owned by the State of Oklahoma, in the County of Tulsa, State of Oklahoma, in the Township of ...

The proposed location of the well is shown on the attached map and is situated on the ...

Very truly yours,  
Collins & Wilson  
By \_\_\_\_\_  
Well Operator



WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No. Rit-364 Well No. 1

Collins and Hilson Company of Harrisville, W. Va.

on the Aaron Tinsler Farm

containing 140 acres. Location Dry Fork of Spruce Creek

Murphy District, in Ritchie County, West Virginia

The surface of the above tract is owned in fee by Aaron Tinsler

of Burnt House address, and the mineral rights are owned by

Aaron Tinsler of Burnt House

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit

No. Rit-364 issued by the West Virginia Department of Mines, Oil and Gas Division

August 5, 1935.

Elevation of surface at top of well, 1021 feet Spirit Barometric.

The number of feet of the different sized casings used in the well.

10 feet 13 inch size. Wood conductor.

310 feet 10" size, csg. feet sized csg.

1065 feet 8 1/4" size, csg. feet sized csg.

feet size, csg. feet sized csg.

--- packer of --- size, set at ---

--- packer of --- size, set at ---

---, in casing perforated at --- feet to --- feet.

---, in casing perforated at --- feet to --- feet.

Coal was encountered at none feet, thick ness --- inches, and at ---

feet; thickness --- inches; and at --- feet; thickness --- inches.

Liners were used as follows: (Give details) none.

Nov, 6, 1935

Date.

Approved Collins and Hilson, Owner.

By ---

(TITLE)

11-7-35

OIL OR GAS WELL Dry hole

## COMPLETION DATA SHEET

NO. 2

## FORMATION RECORD

WELL No. 1FARM Aaron SinglerCompany Collins and NilsonAddress Harrisville, W. Va.

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Big Red				750	825	75		
slate & shells	White		fresh water 80	825	1105	280		310' - 10'
Red Rock				1105	1120	15		1065' - 8 1/4
slate	White			1120	1130	10		
Big Bunkard				1130	1145	15		
slate	White			1145	1200	55		
sand	Dark			1200	1285	85		
slate & shells				1285	1335	50		
sand				1335	1400	65		
slate	black			1400	1420	20		
sand				1420	1435	15		
slate & shells				1435	1530	95		
sand				1530	1540	10		
slate	black			1540	1620	80		
First salt sand				1620	1645	25		
slate	black			1645	1680	35		
second salt sand			Gas - smell 1700	1680	1715	35		Hole reduced from 8 1/4 to 6 5/8 at 1950.
slate & shells				1715	1795	80		
Mayow sand			Gas - mere show 1920	1795	1840	45		
shale	black			1840	1920	80		
Little Lime	Dark			1920	1930	10		
Pencil Cave	Black			1930	1940	10		
Big lime	Grey		Gas show 1943-1945	1940	2012	72		
Heaver sand				2012	2033	21		
Big Injun sand				2033	2070	37		
shale & shell	black			2070	2095	25	2095	

~~shot~~Well was not shot at not shot feet; well was shot at \_\_\_\_\_ feet.~~Salt~~

salt

Fresh water at \_\_\_\_\_ 8.0 feet; fresh water at \_\_\_\_\_ feet.

~~producing~~Well was \_\_\_\_\_ hole.  
dryNov. 6, 1935  
DateApproved \_\_\_\_\_  
Owner

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.

NOTICE OF INTENTION TO PLUG AND ABANDON WELL  
(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)  
WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS DIVISION

To THE DEPARTMENT OF MINES,  
Charleston, W. Va.

*No Coal*

COAL OPERATOR OR COAL OWNER

*Collins & Wilson*

NAME OF WELL OPERATOR

ADDRESS

*Harrisonville W. Va.*

COMPLETE ADDRESS

COAL OPERATOR OR COAL OWNER

*Nov 7<sup>th</sup>*

*1935*

WELL TO BE ABANDONED

ADDRESS

*Murphy*

District

*Aron Tingles*

LEASE OR PROPERTY OWNER *& Mineral*

*Ritchie*

County

*Burnt House W. Va.*

ADDRESS

Well No. *1-*

*Aron Tingles*

Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the *12<sup>th</sup>* day of *November*, 19*35*, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

*Collins & Wilson*  
Well Operator.  
*By Willie Collins*

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of same, the names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)

PROPOSED MANNER OF PLUGGING AND FILLING WELL  
(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS DIVISION  
WORK ORDER

Well to be plugged and filled as follows:

Bottom 2095'  
2095' to 1992' Clay--20' above Keenen Sand  
1992' to 1989' Wood Plug  
1989' to 1979' Cement--Sealing Hole Completely  
1979' to 1920' Clay  
1920' to 1910' Cement Seal Top of Big Line  
Bridge 1870' -- 30' Below Maxton  
1870' to 1775' Clay--20' above Maxton  
1775' to 1765' Cement Sealing Maxton Sand & Bottom of Salt Sand  
1765' to 1600' Clay  
1600' to 1590' Cement Sealing Salt Sand  
Bridge 1175' --30' below Big Duncard  
1175' to 1110' Clay --20' above Big Duncard  
Bridge 1095' --30' Below 8 $\frac{1}{4}$ " Casing  
1095' to 1075' Clay  
1075' to 1072' Wood Plug--Pull 8 $\frac{1}{4}$ " Casing  
1072' to 1025' Clay  
Bridge 340' --30' Below 10" Casing  
340' to 320' Clay  
320' to 317' Wood Plug--Pull 10" Casing  
317' to Surface Clay--Erect Marker Rule 18  
1110' to 1105' Cement Sealing Big Duncard

To the Department of Mines,  
Coal Owner or Operator,  
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this.....7th.....day of.....November....., 193...5.....

DEPARTMENT OF MINES  
Oil and Gas Division

By: .....

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.

AFFIDAVIT IN TRIPLICATE TO TIME AND MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES OIL AND GAS DIVISION

Form with fields for Coal Operator or Owner, Address, Name of Well Operator, Complete Address, Well and Location, District, County, Well No., and Farm.

AFFIDAVIT TO BE MADE IN TRIPLICATE. ONE COPY TO BE MAILED BY REGISTERED MAIL TO THE DEPARTMENT. ONE COPY TO BE RETAINED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES IF REQUIRED) TO BE MAILED TO EACH COAL OPERATOR ABOVE NAMED AT THEIR RESPECTIVE ADDRESSES.

AFFIDAVIT

STATE OF WEST VIRGINIA, COUNTY OF Ritchie } ss:

Willie Collins and S.O. Wilson being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Collins and Wilson, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17th day of February, 1936, and that the well was plugged and filled in the following manner:

Manner in which sand was plugged: Bottom to 1992 clay- 1992 to 1989 wood plug. 1989 to 1979 cement. 1979 to 1920 clay- 1920 to 1910 cement. 1910 to 1775 clay, 1775 to 1765 cement- 1765 to 1600 clay. 1600 to 1590 cement. 1590 to 1110 clay, 1110 to 1105 cement. 1105 to 1075 clay- 1075 to 1072 wood plug. 1072 to 320 clay, 320 to 317 wood plug. 317 to surface clay.


Manner in which coal was plugged:

Description of monument: Concrete and iron.

(THE ABOVE DESCRIPTIONS MUST BE IN DETAIL AND IN ACCORDANCE WITH THE PROVISIONS OF SECTION 10, ARTICLE 4, CHAPTER 22 OF THE CODE)

and that the work of plugging and filling said well was completed on the 27 day of february, 1936.

And further deponents saith not.



Collins and Wilson

By Willie Collins

Sworn to and subscribed before me this 19 day of May, 1936

B.B. Shiner

Notary Public.

My Commission expires: July 9 1940

364-P

Rit-364

