

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: BECKNER, O.C. Operator Well No.: 1

LOCATION: Elevation: 689' Quadrangle: Petroleum  
District: Grant County: Ritchie  
Latitude: 6179' Feet South of 39 Deg. 10 Min. 00 Sec.  
Longitude: 9014' Feet West of 81 Deg. 15 Min. 00 Sec.

Well Type: OIL  GAS

Company UNKNOWN - DEP PAID PLUGGING CONTRACT WVDEP Coal Operator Jerry Westfall, WVDNR D6 Wildlife Biologist  
601 57TH STREET or Owner West Virginia Department of Natural Resources  
CHARLESTON, WV 25304 2311 Ohio Avenue, Parkersburg WV 26101  
Agent H. JASON HARMON Coal Operator \_\_\_\_\_  
Permit Issued Date 06-22-2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of LEWIS ss:

MICHAEL D. GOODWIN, JR. and KEVIN QUESENBERRY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1ST day of AUGUST, 2023, and the well was plugged and filled in the following manner:


| TYPE                      | FROM | TO   | PIPE REMOVED                     | LEFT   |
|---------------------------|------|------|----------------------------------|--|
| TAG TD                    | 1953 |      |                                  |  |
| BOND LOG                  | 1911 | 15   | *ATTEMPTED BH PLUG 1953'-1753'   | *ATTEMPTED BH PLUG 1700'-1360'. W/L TAG PLUG 1911' |
| BH PLUG CEMENT            | 1700 | 1360 | *W/L TAG PLUG 1390'              |  |
| PERF 6 5/8" CSG           | 660  | 300  | *660' (6 SHOTS), 550' (4 SHOTS), | 500' (4 SHOTS), 300' (4 SHOTS)                     |
| TRIP TBG & ATTEMPT CEMENT | 721  | 0    | *NO CEMENT RETURN TO SURFACE     | *W/L TAG PLUG 504'                                 |
| SURFACE PLUG CEMENT       | 504  | 0    | 0                                | 1414', 6 5/8" CSG                                  |

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 24TH day of AUGUST, 2023.

And further deponents saith not. [Signature]

Sworn and subscribe before me this 25TH day of AUGUST, 2023

My commission expires: OCTOBER 10, 2024



[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature]

Title: OOG Inspector

09/08/2023