

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: BECKNER, O. C. Operator Well No.: 7

LOCATION: Elevation: 640' Quadrangle: SHULTZ
District: GRANT County: RITCHIE
Latitude: 39.133480 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -81.291979 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL GAS

Company UNKNOWN - WV DEP PAID PLUGGING CONTRACT Coal Operator N/A
601 57TH STREET or Owner _____
CHARLESTON, WV 25304
Coal Operator N/A
Agent H. JASON HARMON or Owner _____
Permit Issued Date 08-24-2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of LEWIS ss:

MICHAEL D. GOODWIN, JR. and KEVIN P. QUESENBERRY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22ND day of DECEMBER, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	1170		NO TBG TO PULL: CBL 6-5/8" CEM SOLID	925' 6-5/8" CSG
BH PLUG CEMENT	1170	1056		
GEL SPACER	1056	856		925' 6-5/8" CSG
CEMENT PLUG	856	701		
GEL SPACER	701	665		
CEMENT PLUG	665	300	PERF 6-5/8" CSG	3 SHOTS EACH AT 300' & 100'
SURFACE PLUG CEMENT	300	0		

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 18TH day of JANUARY, 2024.


And further deponents saith not.

Kevin P. Quisenberry

Sworn and subscribe before me this 22ND day of JANUARY, 2024

My commission expires: OCTOBER 10, 2024

P. Wayne Ammons
Notary Public



Affidavit reviewed by the Office of Oil and Gas: ALLEN FLOWERS Title: INSPECTOR

01/26/2024