

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tech Service Center Operator Well No.: Shanley #2

LOCATION: Elevation: 1029' Quadrangle: Ellenboro 7.5'  
District: Clay County: Ritchie  
Latitude: 980 Feet South of 39 Deg. 17 Min. 30 Sec.  
Longitude: 4100 Feet West of 81 Deg. 00 Min. 00 Sec.

RECEIVED  
Office of Oil and Gas

APR 17 2025

WV Department of  
Environmental Protection

Well Type: OIL X GAS X

Company Hall Drilling, LLC  
1137 E. Washington Ave.  
Ellenboro, WV 26346

Coal Operator N/A  
or Owner

Agent M.T. Hall

Permit Issued Date 07-13-2017

Coal Operator  
or Owner

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Jackson ss:

Justin L. Meadows and Chad B. Harper being first duly sworn according to-law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of July, 2017, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
CEMENT	3250'	3150'	4 1/2" 1324'	1896'
CEMENT	3150'	3050'	7" 104'	1127'
CEMENT	2835'	2735'	9 5/8" 0'	130' CTS
CEMENT	1945'	1431'	6 % gel between each plug	Set down at 3220'; started drilling, drilled cement
CEMENT	1380'	988'	Shot 7" @ 520', 203', 104', Free	the plug and the shoe, continued 30 ft,
CEMENT	575'	475'	Tagged cement plug @ 1431', 988'	still drilling cement. After discussion
CEMENT	255'	0' (surface)	Set CIBP (cast iron bridge plug) @ 3150', 2835', 1945'.	w/ state inspector set BHP.


Description of monument: 6' x 7" w/ API#, Date Plugged welded on it. and that the work of plugging and filling said well was completed on the 2nd day of August, 2017.

And further deponents saith not.

Sworn and subscribe before me this 9th day of August, 2017

My commission expires: 7/2/20

Notary Public



Affidavit reviewed by the Office of Oil and Gas: Michael Hoff

Title: Oil & Gas Inspector

04/18/2025