

## west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

### PERMIT MODIFICATION APPROVAL

July 02, 2014

EQT PRODUCTION COMPANY POST OFFICE BOX 280 BRIDGEPORT, WV 26330

Re: Permit Modification Approval for API Number 8510093 , Well #: 515275

Extended freshwater casing

Oil and Gas Operator:

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

Please call James Martin at 304-926-0499, extension 1654 if you have any questions.

Gene Smith

Regulatory/Compliance Manager

Office of Oil and Gas



July 1, 2014

Mr. Gene Smith
West Virginia Department of Environmental Protection
Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304

Re: Modification of 47-08510093, 08510094, 08510095, 08510096, 08510097

Dear Mr. Smith,

EQT would like to modify the depth of the fresh water casing (13 3/8") from 973' to 1075'. This will be below the current elevation of 1119'due to the potential show of red rock. I have enclosed a new WW-2B, well schematics, and rec plan for your review.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark

Permitting Supervisor-WV

Enc.

# 4708510093

# STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS W.VA. CODE §22-6A - WELL WORK PERMIT APPLICATION

) Well Operator: EQT Production	- Company		1	1 085	! <u>'</u>	539
	n Company		Operator ID	County	District	Quadrangle
2) Operator's Well Number:		515275		_Well Pad Name	:	PEN15
) Farm Name/Surface Owner :		yne Britton	et ux	_Public Road Ac	cess:	WV-74
) Elevation, current ground:				ost-construction:	1,	119.0
•						
i) Well Type: (a) Gas	_ Oil	Un	derground Stora	age		
Other	·	<del></del>			<del></del>	
(b) If Gas:	Shallow	<u> </u>	Deep			
н	lorizontal	<u>.                                    </u>				
6) Existing Pad? Yes or No:	yes					
7) Proposed Target Formation(s), D  Target formation is Marcellus	Depth(s), Antic at a depth of 6395	with the anti	cipated thickness to	be 50 feet and antic	pated target	pressure of 4176 PSI
B) Proposed Total Vertical Depth:				6,395		
Formation at Total Vertical Depti	h:			Marcellus		<u> </u>
0) Proposed Total Measured Dep	th			14,326		
1) Proposed Horizontal Leg Lengt				4,710		
(2) Approximate Fresh Water Strat	ta Depths:	83, 163, 242, 394, 770, 873				
3) Method to Determine Fresh Wa	ater Depth:			By offset we	ells	
14) Approximate Saltwater Depths:	:		16	552, 1943, 2521		
15) Approximate Coal Seam Depth	1s:			<u>14, 273, 379, 744</u>		
16) Approximate Depth to Possible	a Vold (coal mi)	ne, karst, o	ther):		Non	e reported
	contain coal s	eams direc	tly overlying or			
17)Does proposed well location						
17)Does proposed well location						
17)Does proposed well location adjacent to an active mine?  (a) If Yes, provide Mine Info:	Name:					
17)Does proposed well tocation adjacent to an active mine?	Name:					
17)Does proposed well location adjacent to an active mine?	Name: Depth:					
17)Does proposed well location adjacent to an active mine?	Name: Depth: Seam:					
17)Does proposed well location adjacent to an active mine?	Name: Depth: Seam:					

Due

RECEIVED
Office of Oil and Gas

APR 0 8 2014

WV Department of Environmental Protection

# CASING AND TUBING PROGRAM

18) TYPE	Size	New	Grade	Weight per	FOOTAGE:	INTERVALS;	CEMENT:
		<u>or</u>	Ì	<u>ft.</u>	<u>for Drilling</u>	Left in Well	Fill- up (Cu.Ft.)
		Used					
Conductor	20	New	MC-50	81	40	40	38 C.T.S.
Fresh Water	13 3/8	New	MC-50	54	1,075	1,075	931 C.T.S.
Coal	•	•		·	-	· .	•
Intermediale	9 5/8	New	MC-50	40	5,330	5,330	2,092 C.T.S.
Production	5 1/2	New	P-110	20	14,326	14,326	See Note 1
Tubing	2 3/8		J-55	4.6			May not be ear, if ear will be set 100 less than TD
Liners			1				<u> </u>

TYPE	Size	Wellbore Diameter	<u>Wall</u> Thickness	Burst Pressure	Cement Type	Cement Yield (cu. IL/k)
Conductor	20	24	0.375	•	Construction	1.18
Fresh Water	13 3/B	17 1/2	0.38	2,480	1	1.21
Coal	•	-	•	•	•	
Intermediate	9 5/8	12 3/8	0.395	3,590	1 _	1.21
Production	5 1/2	8 1/2	0.361	12,640	•	1.27/1.86
Tubing						
Liners					l	

### **Packers**

		· · · · · · · · · · · · · · · · · · ·	
Kind:	N/A		
Sizes:	N/A		
Depths Set:	N/A		 

Note 1: EQT plans to bring the TOC on the production casing cement job 1,000' above kick off point, which is at least 500' above the shallowest production zone, to avoid communication.


Page 2 of 3

Jan 1 116m

(3/13)

B) Describe proposed well work, including the drilling and plugging back of any pa	
Drill and complete a new horizontal well in the Marcettus Formation. The vertical drill to go down to	о ап арргохитате оврт от 3620.
Then kick off the horizontal leg into the Marcellus using a slick water frac.	
(20) Describe fracturing/stimulating methods in detail, including anticipated max pro	essure and max rate:
bytanilis tracturing is completed in accordance with state regulations using water recycled from previo	ously fractured wells and obtained from
eshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemic eiling agent, gel breaker, friction reducer, blockle, and scale inhibitor), referred to in the industry as a	als (including 15% Hydrochiotic acid,
inticipated treating pressures are expected to average approximately 8500 psl, maximum anticipated	treating rates are expected to average
approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 200,000 b	arrels of water per stage. Sand sizes
vary from 100 mesh to 20/40 mesh. Average approximately 200,000 pounds of sand per stage.	
21) Total area to be disturbed, including roads, stockpile area, pits, etc, (acres):	No additional Disturbance
	±.3 ac
22) Area to be disturbed for well pad only, less access road (acres):  23) Describe centralizer placement for each casing string.	1.3 ac
Surface: Bow spring centralizers – One at the shoe and one spaced every 500.	
Intermediate: Bow spring centralizers—One cent at the shoe and one spaced every 1000' from KOP to Int csg shoe	ery 500'.
24) DB301100 LB 001110111 LB 01111011 LB 01111011 LB 011110111 LB 01111011 LB 0111101 LB 0111101 LB 0111101 LB 01111011 LB 0111101 LB 011101 LB 0111011 LB 011101 LB 011101 LB 011101 LB 011101 LB 011101 LB 011101 L	(Type 1 Cement): 0-3% Calcium Chloride
Ised to speed the setting of cement slurries. 1,4% flake. Loss Circulation Material (LCM) is used to combat the loss of the cement slurry	to a thief zone.
ntermediate (Type 1 Cement): 0-3% Calcium Chloride. Salt is used in shallow, low temperature	re formations to speed the setting of cement
durries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of whole draw to a thief zone.	ining indic or centern sicilly (not mirate)
Production:	
ead (Type 1 Cement): 0.2-0.7% Lignosulfonate (Retarder). Lengthens thickening time.	
0.3% CFR (dispersant). Makes cement easier to mix.	
Tail (Type H Cement): 0.25-0.40% Lignosulfonate (Retarder). Lengthens thickening time.	
0.2-0.3% CFR (dispersant). This is to make the cement easier to mix.	
30 % Calcuim Carbonate. Acid solubility.	
0.4-0.6% Halad (fluid loss). Reduces amount of water lost to formation.	
25) Proposed borehole conditioning procedures. <u>Surface</u> : Circulate hole clean (Approx	imately 30-45 minutes) rotating & reciprocating
one full joint until cuttings diminish at surface. When cuttings returning to surface diminish,	
minutes. To ensure that there is no fill, short trip two stands with no circulation. If there is fi	
and circulate hole clean. A constant rate of higher than expected cuttings volume likely ind	
intermediate: Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one	
ntermediate: Circulate note clean (Approximater) 55 to minute of circulate an additional 5	
note cleaning use a soap sweep or increase injection rate & foam concentration.	
nole cleaning use a soap sweep of increase injection rate a total concention.  Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a g	auge holes bottoms up volume.
Production: Pump marker sweep with not plug to determine actual note washout. Calculate by Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check	
	recent of demings greeness
the shakers every 15 minutes.	
*Note: Attach additional sheets as needed.	$\mathcal{U}$

Page 3 of 3



Well

**EQT** Production

515275 (PEN15H6)

Then kick off the horizontal leg into the Marcellus using a stick water frac.

Azmuth 225 Pennsboro Ritchie West Virgina Vertical Section 8872 TVD Depth Formation Tops (TVD) Casing Wt (ppf)/Grade Hole Size Type Size (feet) (inches) 24 (nches) Conductor 50 250 500 750 Date Fresh Water 13.38 54FMC-50 (1000) 17.12 1,000 Base Field from 1343 1,250 1.500 1741 1759 1.750 Attention 1082 - 2033 Bytens 2009 - 2147 (2000) 2.000 Highipm 2.250 Max 2113 2472 210 2472 2100 2140 2700 2704 2001 2003 2004 2000 2005 2000 2005 2000 2006 2000 2.500 Gust Fifty foot 2.750 Their fact Gestra 2940 (3000) 3.000 Form Soul Daywork 3.250 2114 Water 3.500 Speciality 35217 3,750 4.000 (4000) Baltimore 2019 - 4500 4.250 4.500 5AL 1003 4.750 -Become 4101 6124 (5000) 5,000 (211 1335 Discord 5,250 15.22 Intermediate 9.5 B 40# MC 50 \$4 (C) [1] 5.500 Serger \$100 \$100 Mathema (21) 1273 5.750 Georges Secretor 6278 8339 KOP € 3,620° 6256 6355 Tight 1353 4344 (60007) 6,000 Hamilton 6000 5074 0.518 6.250 Marrich or 100 Production Casing 5 1/2 201/P-110 Target Inside Marcellus 6395 6.500 6.62-8 Parks be-Land curve @ 6,395 11 TVD 9,118 11 MD Est. TD @ 6,395' 11 TVD 13,826 11 MD Proposed Well Work: Drill and complete a new horizontal well in the Marcelius formation. The vertical drill to go down to an approximate depth of 3620".

4,710 ft Lateral

De L

