

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

PERMIT MODIFICATION APPROVAL

January 02, 2015

EQT PRODUCTION COMPANY 303 SAND CUT ROAD CLARKSBURG, WV 26301

Re: Permit Modification Approval for API Number 8510132, Well #: 513756

Extend Lateral

Oil and Gas Operator:

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

Please call James Martin at 304-926-0499, extension 1654 if you have any questions.

Sincerely,

Gene Smith

Assistant Chief of Permitting

I Per Gene Snith

Office of Oil and Gas



October 30, 2014

Mr. Gene Smith West Virginia Department of Environmental Protection Office of Oil and Gas 601 57th Street SE Charleston, WV 25304

Re: Modification of OXF163, 513756, 513757, 513759, 513760 API#47-085-10132, 10133, 10135, 10136

Dear Mr. Smith,

Attached is a modification of the lateral length for the above 4 API numbers. Included is a new WW-6B, well schematics, WW-6A1, mylar plat and rec plan.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark

Permitting Supervisor-WV

Enc.

RECEIVED
Office of Oil and Gas

NOV 03 2014

WV Department of Environmental Protection

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS W.VA. CODE \$22-6A - WELL WORK PERMIT APPLICATION

1) Well Operator: EQT Production	on Company			085	4	526	
			Operator ID	County	District	Quadrangle	
2) Operator's Well Number:		513756		Well Pad Name	OXF	163	
3) Farm Name/Surface Owner :		Pierce		Public Road Ac	cess:	CR 7/18	
4) Elevation, current ground:	1,175.0	Elevat	ion, proposed po	st-construction:	1,158.5		
5) Well Type: (a) Gas	Oil	Und	derground Storag	ge			
Other							
(b) If Gas:	Shallow	•	Deep				
н	orizontal	•					
6) Existing Pad? Yes or No:	No						
7) D				'- 4 - 4 D			
7) Proposed Target Formation(s), Darget formation is Marcellus		•			• •	of 2100 BCI	
Targer formation is Marcellus	at a deptit of 652	/ Will life affic	pated inchiess to b	e 33 leet and anticipa	ated talget pressure	01 2 190 F31	
8) Proposed Total Vertical Depth:	_			6,527			
9) Formation at Total Vertical Depth	n:		(Onondaga			
10) Proposed Total Measured Dept	.h			14,869			
11) Proposed Horizontal Leg Lengt				7,430		<u> </u>	
12) Approximate Fresh Water Strat	a Depths:	173, 450, & 514					
13) Method to Determine Fresh Wa	By offset wells						
14) Approximate Saltwater Depths:				1,153	-		
15) Approximate Coal Seam Depth	s:		No Co	oal Seams Prese	ent		
16) Approximate Depth to Possible	Void (coal mi	ne, karst, oth	ner):		None reporte	d .	
17)Does proposed well location (contain coal s	eams directly	y overlying or				
adjacent to an active mine?							
(a) If Yes, provide Mine Info:	Name:	_					
	Depth:						
	Owner						

Page 1 of 3

RECEIVED
Office of Oil and Gas

NOV 03 2014

WV Department of Environmental Protection 01/02/2015

CASING AND TUBING PROGRAM

18)

TYPE	. <u>Size</u>	New	Grade	Weight per	FOOTAGE:	INTERVALS:	CEMENT:
		<u>or</u> <u>Used</u>		<u>ft.</u>	for Drilling	Left in Well	Fill- up (Cu.Ft.)
Conductor	20	New	MC-50	81	40	40	38 C.T.S.
Fresh Water	13 3/8	New	MC-50	54	1,055	1,055	914 C.T.S.
Coal	-	-	-	<u>-</u>	•		-
Intermediate	9 5/8	New	MC-50	40	2,955	2,955	1,152 C.T.S.
Production	5 1/2	New	P-110	20	14,869	14,869	See Note 1
Tubing	2 3/8		J-55	4.6			May not be run, if run will be set 100' less than TD
Liners							

TYPE	Size	Wellbore Diameter	<u>Wall</u> <u>Thickness</u>	<u>Burst</u> <u>Pressure</u>	Cement Type	Cement Yield (cu. ft./k)
Conductor	20	24	0.375	•	Construction	1.18
Fresh Water	13 3/8	17 1/2	0.38	2,480	* See Note 2	1.21
Coal	•	-	-	<u>-</u>	-	-
Intermediate	9 5/8	12 3/8	0.395	3,590	* See Note 2	1.21
Production	5 1/2	8 1/2	0.361	12,640	•	1.27/1.86
Tubing						
Liners						

Packers Packers

Kind:	N/A		
Sizes:	N/A		
Depths Set:	N/A		

Note 1: EQT plans to bring the TOC on the production casing cement job 1,000' above kick off point, which is at least 500' above the shallowest production zone, to avoid communication.

Note 2: Reference Variance 2014-17.

Page 2 of 3

RECEIVED
Office of Oil and Gas


NOV 03 2014

WV Department of Environmental Protection/2015


(3/13)

19) Describe proposed well work, including the drilling and plugging back	ck of any pilot hole:
Drill and complete a new horizontal well in the Marcellus formation. The vertical drill	to go down to an approximate depth of 6657'. Tag the
Onondaga not more than 100', run logs, then plug back to approximately 5123'. Th	en kick off the horizontal leg into the Marcellus formation
using a slick water frac.	
 Describe fracturing/stimulating methods in detail, including anticipat 	
Hydraulic fracturing is completed in accordance with state regulations using water recycle freshwater sources. This water is mixed with sand and a small percentage (less than 0.3	
gelling agent, gel breaker, friction reducer, biocide, and scale inhibitor), referred to in the	industry as a "slickwater" completion. Maximum
anticipated treating pressures are expected to average approximately 8500 psi, maximur approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximate	
vary from 100 mesh to 20/40 mesh. Average approximately 200,000 pounds of sand pe	<u> </u>
21) Total area to be disturbed, including roads, stockpile area, pits, etc,	(acres): 24.6
22) Area to be disturbed for well pad only, less access road (acres):	14.6
23) Describe centralizer placement for each casing string.Surface: Bow spring centralizers – One at the shoe and one spaced e	very 500'
 Intermediate: Bow spring centralizers — One cent at the shoe and one 	
Production: One spaced every 1000' from KOP to Int csg shoe	
24) Describe all cement additives associated with each cement type. Used to speed the setting of cement slurries.	Surface (Type 1 Cement): 0-3% Calcium Chloride
0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of the ce	
Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Salt is used in shallow, low slurries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss	
to a thief zone.	o, many many (not mileto)
Production:	
Lead (Type 1 Cement): 0.2-0.7% Lignosulfonate (Retarder). Lengthens thickening	time.
0.3% CFR (dispersant). Makes cement easier to mix.	
Tail (Type H Cement): 0.25-0.40% Lignosulfonate (Retarder). Lengthens thickenin	g time.
0.2-0.3% CFR (dispersant). This is to make the cement easier to mix.	
60 % Calcuim Carbonate. Acid solubility.	
0.4-0.6% Halad (fluid loss). Reduces amount of water lost to formation.	
25) Proposed borehole conditioning procedures. <u>Surface</u> : Circulate hole cl	ean (Approximately 30-45 minutes) rotating & reciprocating
one full joint until cuttings diminish at surface. When cuttings returning to surface	e diminish, continue to circulate an additional 5
minutes. To ensure that there is no fill, short trip two stands with no circulation.	If there is fill, bring compressors back on
and circulate hole clean. A constant rate of higher than expected cuttings volun	ne likely indicates washouts that will not clean up.
Intermediate: Circulate hole clean (Approximately 30-45 minutes) rotating & recipro	ocating one full joint until cuttings diminish at
surface. When cuttings returning to surface diminish, continue to circulate an a	dditional 5 minutes. If foam drilling, to enhance
hole cleaning use a soap sweep or increase injection rate & foam concentration	<u> </u>
Production: Pump marker sweep with nut plug to determine actual hole washout. C	Calculate a gauge holes bottoms up volume.
Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are cle	an. Check volume of cuttings coming across
the shakers every 15 minutes.	
	RECEIVED
*Note: Attach additional sheets as needed.	Office of Oil and Gas

NOV **0 3** 2014 Page 3 of 3



NOV 03 2014





west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary dep.wv.gov

March 18, 2014

Nabors Completion & Production Services Company 1380 Route 286 Hwy E #121 Indiana PA 15701

Re: Cement Variance Request

Dear Sir or Madam,

This agency is approving a variance request for the cement blend listed below to be used on surface and coal protection strings for the drilling of oil and gas wells in the state of West Virginia. The variance cannot be used without requesting its use on a permit application and approval by this agency:

Type 1 (2% Calcium Chloride-Accelerator, 0.25% Super Flake-Lost Circulation, 5.2% Water, 94% Type "1" Cement)

If you have any questions regarding this matter feel free to contact me at 304-926-0499, ext. 1653.

) '.

James Pelerson

Environmental Resources Specialist / Permitting

Promoting a healthy environment.

RECEIVED
Office of Oil and Gas

NOV 03 2014

WV Department of Environmental Protection 2/2015



west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax

Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary dep.wv.gov

BEFORE THE OFFICE OF OIL AND GAS DEPARTMENT OF ENVIRONMENTAL PROTECTION STATE OF WEST VIRGINIA

IN THE MATTER OF A VARIANCE FROM)	ORDER NO.	2014 - 17
REGULATION 35 CSR § 4-11.4/11.5/14.1)		
AND 35 CSR § 8-9.2.h. 4/5/6/8 OF THE)		
THE OPERATIONAL)		
REGULATIONS OF CEMENTING OIL)		
AND GAS WELLS)		

REPORT OF THE OFFICE

Nabors Completion & Production Services Co. requests approval of a different cement blend for use in cementing surface and coal protection casing of oil and gas wells.

FINDINGS OF FACT

- 1.) Nabors Completion & Production Services Co. proposes the following cement blend:
 - 2% Calcium Chloride (Accelerator)
 - 0.25 % Super Flake (Lost Circulation)
 - 94% Type "1" Cement
 - 5.20 % Water
- 2.) Laboratory testing results indicate that the blend listed in Fact No.1 will achieve a 500 psi compressive strength within 6 hours and a 2,435 psi compressive strength within 24 hours.

Promoting a healthy environment.

RECEIVED
Office of Oil and Gas

NOV **03** 2014

WV Department of Environmental Profeotion 2015

CONCLUSIONS OF LAW

Pursuant to Articles 6 and 6A, Chapter 22 of the Code of West Virginia, the Office of Oil and Gas has jurisdiction over the subject matter embraced in said notice, and the persons interested therein, and jurisdiction to promulgate the hereinafter prescribed Order.

Pursuant to 35 CSR § 4-11.5 and 35 CSR § 8-9.2.h.8 the Chief of the Office of Oil and Gas may approve different cement blends upon the well operator providing satisfactory proof that different cement types are adequate.

ORDER

It is ordered that Nabors Completion & Production Services Co. may use the cement blend listed in Findings of Fact No.1 for the cementing of surface and coal protection casing of oil and gas wells in the State as may be requested by oil and gas operators. The waiting time on the cement blend shall be 8 hours. The cement blend shall be mixed in strict accordance with the specifications for each blend and weight measurements made on-site to assure the cement slurries meet the minimum weight specifications. A sample shall be collected and, if after 8 hours the cement is not set up, additional time will be required. Nabors Completion & Production Services Co. shall keep a record of cement blend jobs in which the cement blend approved under this order is to be used and made available to the Office of Oil and Gas upon request.

Dated this, the 18th day of March, 2014.

IN THE NAME OF THE STATE OF WEST VIRGINIA

OFFICE OF OIL AND GAS DEPARTMENT OF ENVIRONMENTAL PROTECTION OF THE STATE OF WEST VIRGINIA

James Martin, Chief Office of Oil and Gas

RECEIVED
Office of Oil and Gas

NOV **03** 2014

WV Department of Environmental Protection 2/2015

