

west virginia department of environmental protection

Office of Oil and Gas 601 57th Street SE Charleston, WV 25304 (304) 926-0450 (304) 926-0452 fax Earl Ray Tomblin, Governor Randy C. Huffman, Cabinet Secretary www.dep.wv.gov

PERMIT MODIFICATION APPROVAL

May 19, 2015

EQT PRODUCTION COMPANY 120 PROFESSIONAL PLACE BRIDGEPORT, WV 26330

Re: Permit Modification Approval for API Number 8510137, Well #: 513761

Extend Lateral

Oil and Gas Operator:

The Office of Oil and Gas has reviewed the attached permit modification for the above referenced permit. The attached modification has been approved and well work may begin. Please be reminded that the oil and gas inspector is to be notified twenty-four (24) hours before permitted well work is commenced.

Please call James Martin at 304-926-0499, extension 1654 if you have any questions.

Sincerely,

Gene Smith

Assistant Chief of Permitting

Office of Oil and Gas



April 14, 2015

Mr. Gene Smith
West Virginia Department of Environmental Protection
Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304

Re: Modification to 47-085-10137

Dear Mr. Smith,

Enclosed is a new WW-6B, schematics, WW6A1, Mylar plat for the above API#, signed by the inspector. EQT would like to extend the lateral portion of the well.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark

Permitting Supervisor-WV

Enc.

Received

APR 2 1 2015

085-10137 MOD 2

STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS W.VA. CODE §22-6A - WELL WORK PERMIT APPLICATION

1) Well Operator: EQT Product	ion Company		306686	085	1 4	
			Operator ID	County	District	526 Quadrangle
2) Operator's Well Number:		513761		_Well Pad Name		OXF163
3) Farm Name/Surface Owner : _		Pierce		_Public Road Ac	cess:	CR 7/18
4) Elevation, current ground:	1,175.0	Elevat	ion, proposed po	ost-construction:	1,158.	5
5) Well Type: (a) Gas	Oil	Uno	derground Stora	ge		
Other						
(b) If Gas:	Shallow	•	Deep			
ŀ	Horizontal	•				
6) Existing Pad? Yes or No:	yes					
7) Proposed Target Formation(s), Target formation is Marcellus	Depth(s), Antic at a depth of 6560	cipated Thick	nesses and Ass pated thickness to b	ociated Pressure e 53 feet and anticip	e(s): ated target press	ure of 2190 PSI
8) Proposed Total Vertical Depth:				6,560		
Formation at Total Vertical Dept	h:			Marcellus		
10) Proposed Total Measured Dep	A La			15,312		
11) Proposed Horizontal Leg Lengt				7,410		
12) Approximate Fresh Water Stra	ta Depths:			176, 453, 51	7	
13) Method to Determine Fresh Wa	ater Depth:			By offset well		
14) Approximate Saltwater Depths:				1,156		
15) Approximate Coal Seam Depth	is:			oal Seams Prese	ent	
16) Approximate Depth to Possible	Void (coal mir	ne, karst, oth	er):		None repo	orted
17)Does proposed well location				•	Trong repe	iteu
adjacent to an active mine?			, ,			
(a) If Yes, provide Mine Info:	Name:					
	Seam:					
	Owner:					

OCS 2015 Unis lateral Received APR 2 / 2015 Office of Oil and Gas Office of Oil and Gas Office of Environmental Protection

CASING AND TUBING PROGRAM

18)

TYPE	Size	New or	Grade	Weight per ft.	FOOTAGE: for Drilling	INTERVALS: Left in Well	CEMENT:
		Used		s == .	rer saming	Left III Well	Fill- up (Cu.Ft.)
Conductor	20	New	MC-50	81	40	40	38 C.T.S.
Fresh Water	13 3/8	New	MC-50	54	1,055	1,055	914 C.T.S.
Coal	-	3-6	-	<i>y</i> .	-	•	
Intermediate	9 5/8	New	MC-50	40	3,036	3,036	1,184 C.T.S.
Production	5 1/2	New	P-110	20	15,312	15,312	See Note 1
Tubing	2 3/8		J-55	4.6			May not be run, if run will be set 100' less than TD
Liners							

TYPE	Size	Wellbore Diameter	Wall Thickness	<u>Burst</u> <u>Pressure</u>	Cement Type	Cement Yield (cu. ft./k)
Conductor	20	24	0.375	*	Construction	1.18
Fresh Water	13 3/8	17 1/2	0.38	2,480	* See Note 2	1.21
Coal	3		×	Æ <	-	÷
Intermediate	9 5/8	12 3/8	0.395	3,590	* See Note 2	1.21
Production	5 1/2	8 1/2	0.361	12,640	-	1.27/1.86
Tubing						
Liners						

memediale	VO 2 082	1000000000	0.000	0,000	Oce Note 2	1.21	
Production	5 1/2	8 1/2	0.361	12,640		1.27/1.86	
Tubing							, i
Liners							1 N.N 3
			<u>Packers</u>			ox.	JCIN 2013
							4/1/
Kind:	N/A						_
Sizes:	N/A						

Note 1: EQT plans to bring the TOC on the production casing cement job 1,000' above kick off point, which is at

least 500' above the shallowest production zone, to avoid communication.

Note 2: Reference Variance 2014-17.

Page 2 of 3

Received

APR 2 | 2015

ww	-	6В
(4/15	5)	

API NO. 47 - 85 - 10137
OPERATOR WELL NO. 513761
Well Pad Name: OXF163

CASING AND TUBING PROGRAM

18)

TYPE	Size	<u>New</u>	Grade	Weight per ft.	FOOTAGE: For	INTERVALS:	CEMENT:
	<u>(in)</u>	<u>or</u>		(ib/ft)	Drilling (ft)	Left in Well	Fill- up (Cu.Ft.)
		<u>Used</u>				<u>(ft)</u>	
Conductor	20	New	MC-50	81	40	40	38 C.T.S.
Fresh Water	13 3/8	New	MC-50	54	1,055	1,055	914 C.T.S.
Coal	-	_	_	_	_	-	_
Intermediate	9 5/8	New	MC-50	40	3,036	3,036	1,184 C.T.S.
Production	5 1/2	New	P-110	20	15,312	15,312	See Note 1
Tubing	2 3/8		J-55	4.6		<u>. </u>	May not be run, if run will be set 100' less than TD
Liners							

TYPE	<u>Size (in)</u>	<u>Wellbore</u> <u>Diameter (in)</u>	<u>Wall</u> <u>Thickness</u> <u>(in)</u>	<u>Burst Pressure</u> (psi)	Anticipated Max. Internal Pressure (psi)	<u>Cement</u> <u>Type</u>	Cement Yield (cu. ft./k)
Conductor	20	24	0.375	•	18	Construction	1.18
Fresh Water	13 3/8	17 1/2	0.38	2,480	2184	* See Note 2	1.21
Coal							
Intermediate	9 5/8	12 3/8	0.395	3,590	3160	* See Note 2	1.21
Production	5 1/2	8 1/2	0.361	12,640	10112	-	1.27/1.86
Tubing							
Liners							

Packers

Kind:	N/A		
Sizes:	N/A		
Depths Set:	N/A		

Note 1: EQT plans to bring the TOC on the production casing cement job 1,000' above kick off point, which is at least 500' above the shallowest production zone, to avoid communication.

Note 2: Reference Variance 2014-17. (Attached)


Page 2 of 3


Proceived

APR 2 1 2015

(3/13)

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:	
Drill and complete a new horizontal well in the Marcellus formation. The vertical drill to go down to an approximate depth of 4703'. Then kick	
off the horizontal leg into the Marcellus formation using a slick water frac.	
	 "
20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:	
Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from	
freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, gelling agent, gel breaker, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum	
anticipated treating pressures are expected to average approximately 8500 psi, maximum anticipated treating rates are expected to average	
approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 200,000 barrels of water per stage. Sand sizes	
vary from 100 mesh to 20/40 mesh. Average approximately 200,000 pounds of sand per stage.	
21) Total area to be disturbed, including roads, stockpile area, pits, etc, (acres):	 -
22) Area to be disturbed for well pad only, less access road (acres):	
23) Describe centralizer placement for each casing string.	
Surface: Bow spring centralizers – One at the shoe and one spaced every 500'. Intermediate Pays pring centralizers — One central the shoe and one spaced every 500'.	
Intermediate: Bow spring centralizers— One cent at the shoe and one spaced every 500'. Production: One spaced every 1000' from KOP to Int csg shoe	
24) Describe all cement additives associated with each cement type. Surface (Type 1 Cement): 0-3% Calcium Chloride	
Used to speed the setting of cement slurries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of the cement slurry to a thief zone.	
Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Salt is used in shallow, low temperature formations to speed the setting of cement	·
slurries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of whole drilling fluid or cement slurry (not filtrate)	
to a thief zone.	
Production:	
Lead (Type 1 Cement): 0.2-0.7% Lignosulfonate (Retarder). Lengthens thickening time.	
0.3% CFR (dispersant). Makes cement easier to mix.	<u>∞</u>
Tail (Type H Cement): 0.25-0.40% Lignosulfonate (Retarder). Lengthens thickening time.	
0.2-0.3% CFR (dispersant). This is to make the cement easier to mix.	
60 % Calcuim Carbonate. Acid solubility.	
0.4-0.6% Halad (fluid loss). Reduces amount of water lost to formation.	
SENTENING CONTROL OF THE SENTENING OF THE SENTENING CONTROL OF THE SENT	
25) Proposed borehole conditioning procedures. <u>Surface</u> : Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating	
one full joint until cuttings diminish at surface. When cuttings returning to surface diminish, continue to circulate an additional 5	
minutes. To ensure that there is no fill, short trip two stands with no circulation. If there is fill, bring compressors back on	
and circulate hole clean. A constant rate of higher than expected cuttings volume likely indicates washouts that will not clean up.	
Intermediate: Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one full joint until cuttings diminish at	
surface. When cuttings returning to surface diminish, continue to circulate an additional 5 minutes. If foam drilling, to enhance	Received
hole cleaning use a soap sweep or increase injection rate & foam concentration.	Tibuuii
Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume.	APR 2 1 2015
Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check volume of cuttings coming across	APH Z I ZUIS
the chakers every 15 minutes	0.00
	Office of Oil and Gas WV Dept. of Environmental Protection
*Note: Attach additional shoots as pooded	WV Dept. of Environment
*Note: Attach additional sheets as needed.	





05/22/2015

Well Number:

513761 (OXF163H6)

Casing and Cemer	nting		Deepe	st Fresh Water:	517'
		Mine	1		
Type	Conductor	Protection	Surface	Intermediate	Production
Hole Size, In.	24		17 1/2	12 3/8	8 1/2
Casing Size, OD In.	20		13 3/8	9 5/8	5 1/2
Casing Wall Thickness, In.	0.375	P1	0.380	0.395	0.361
Depth, MD	40'	-	1,055'	3,036'	15,312'
Depth, TVD	40'		1,055'	3,036'	6,560'
Centralizers Used	Yes	ä	Yes	Yes	Yes
Weight/Grade	81#/MC-50	-	54#/MC-50	40#/MC-50	20#/P-110
New or Used	New	-	New	New	New
Pressure Testing	-	:5	20% Greater than exp. Pressure	20% Greater than exp. Pressure	20% greater than exp. fracture pressure
After Fracture Pressure Testing	-	:-	-		20% greater than exp. shut pressure
ID, in	19.25	-	12.615	8.835	4.778
Burst (psi)			2,480	3,590	12,640
Collapse (psi)	*	% =	1,110	2,470	11,100
Tension (mlbs)	4	12	455	456	587
Cement Class	+	~		-	Н
Cement Type	Construction		1	1	-
Cement Yield	1.18	,	1.21	1.21	1.27/1.86
Meets API Standards	7 K		Yes	Yes	Yes
WOC Time	(*		Min. 8 hrs	Min. 8 hrs	Min. 8 hrs
Top of Cement (Planned)	Surface	Œ	Surface	Surface	3,703'
Fill (ft.)	40'	-	1,055'	3,036'	11,109'
Percent Excess	::::::::::::::::::::::::::::::::::::::	-	20	20	10
Est. Volume (cu ft)	38	-	914	1,184	2,825
Est. Volume (BBLS)	7		163	211	503

Received

APR 2 1 2015

Office of Oil and Gas
WV Dept. of Environmental Protection

SSP Dage 05/22/2015

Lateral Final for Say 655

Elevation:

WEST VIRGINIA GEOLOGICAL PROGNOSIS

Horizontal Well 513761 (OXF163H6) 470851013

Marcellus2 **Drilling Objectives:** County: Ritchie Quad: Oxford

1172 KB

1159 GL

Surface location Northing: 234445.3 Easting: 1619075.4 **Landing Point** Northing: 233325 Easting: 1617963.9 Northing: 226277.6 1620253.7 Easting: Toe location

162 Degrees Recommended Azimuth Recommended LP to TD:

Proposed Logging Suite: Formation tops based off logging on pilot hole well 513756

Mudloggers to be on location at kickoff point to run samples and measure gas

thru both the curve and lateral sections.

Recommended Gas Tests: 1800, 2050, 2600, Intm Csg. Pt., 3400, 4900, 5250, KOP, (Gas test at any mine void)

Gas test during any trip or significant downtime while drilling the lateral section.

Possible red rock at:

46,86,182,235,290,396,462,513,580, 643,704,802,864,916,967,1008,1919

ESTIMATED FO	DRMATION	TOPS
--------------	----------	------

Formation	Top (TVD)	Base (TVD)	Lithology	Comments	- 1
resh Water Zone	1	517		FW @ 176,453,517,,	
Maxton	1771	1798 Sandst	one	No Coal Seams Identified to Exist	1.5
lig Lime	1951	2090 Limest	one	SW @ 1156.,	
Veir	2241	2363 Sandst	one	Red Rock Possible @ 46,86,182,235,290,396,462,513,580,	Ba
op Devonian	2469			643,704,802,864,916,967,1008,1919	
Gantz	2469	2489 Silty S	and		
Fifty foot	2563	2633 Silty S	and		
Thirty foot	2649	2683 Silty S	and		
Gordon	2711	2773 Silty S	and		
Forth Sand	2799	2811 Silty S	and		
Bayard	2956	2986 Silty S	and		
Int. csg pt	3036				10
Warren	3295	3340 Silty S	and	Received	
Speechley	3348	3399 Silty S	and	Doceliveu	
Balltown A	3843	3866 Silty S	and		
Riley	4427	4475 Silty S	and	SE 15	
Benson	4763	4794 Silty S	and		
Alexander	5096	5170 Silty S	and	APR 2 1 2015	
Elks	5170	6203 Gray S	hales and Silts	APRIZ 1 2013	
Sonyea	6203	6347 Gray s	hale		
Middlesex	6347	6398 Shale			
Genesee	6398	6474 with bl	ack shale	Office of Oil and Gas	
Geneseo	6474	6509 Black	Shale	Office of Oil and Gas WV Dept. of Environmental Pro	techi
Tully	6509	6522 Limest	one	WAY Dept. of Environmental	
Hamilton	6522	6532 calcare	ous shales	000 A 20 A	
Marcellus	6532	6585 Black	Shale		
-Purcell	6545	6550 Limest	one		- 1
Lateral Zone	6560	6560		Start Lateral at 6560 ft, drill to 6560 ft	
-Cherry Valley	6567	6570 Limest	one		- 1
Onondaga	6585	Limest	one		

Target Thickness	53 feet	
Anticipated Target Pressure	2190 PSI	

Comments: Note that this is a TVD prog for a horizontal well. All measurements taken from estimated KB elevation. Water and coal information estimated from surrounding well data. Intermediate casing point is recommended 50' beneath the Bayard to shut off any water production from the upper Devonian sands. Intermediate casing should be cemented into the surface string, per WV regulations. The estimated TD is the TVD landing point for the horizontal section of well, with the plan to then drill to a final TVD of 6560' at the toe of the lateral. Bed dips are expected to be near 88-90 degrees in the lateral.

LATERAL DRILLING TOLERANCES

Mapview - Left of borehole: Deviate as little as possible left to avoid planned lateral 513758 Deviate as little as possible right to avoid planned lateral 513759

DO NOT EXTEND beyond recommended wellbore to avoid leaseline. Mapview - Right of borehole: Mapview - TD:

RECOMMENDED CASING POINTS

CSG DEPTH: 1055 CSG OD 13.3/8 set below deepest RR Fresh Water/Coal CSG DEPTH: 3036 Intermediate 1: CSG OD 9 5/8 CSG OD 5 1/2 CSG DEPTH: @ TD Production:

J. Dereume/ E. Glick Plat Date Author Date Created

5/27/2014 6/2/2014 Prog created: EVG 8/22/2014 EVG 9/2/2014 10/27/2014 Changed target and bottomhole co JMD 12/8/2014 Tophole Final EVG 1/21/2015

TVD: 6560 TVD: 6560

7,410

Section VII: Collision Avoidance

Collision avoidance is managed by utilizing gyro tools, downhole steering tools (MWD/EM), and anticollision software by engineers. Two drilling scenarios that occur are normal pad drilling and return to pad drilling. EQT categorizes these two scenarios as such because the two scenarios utilize very different mitigation plans.

Normal pad drilling is defined when a top hole rig drills each well on the pad down to kick off point (KOP) and then a bottom hole rig moves onto the pad after the top-hole rig moves off and drills the curve and lateral sections. Normal pad drilling can also be defined when a bottom hole rig moves to a pad and drills each well on the pad from surface to TD (Grassroots Well). Normal pad drilling carries much less risk and thus does not require frequent surveying and collision avoidance maneuvers because no producing wells are present and risk of unexpected pressure or well control events are not present.

Return to pad drilling is a scenario where a top-hole rig or a bottom hole rigs returns to a pad to drill additional well(s) that currently have producing (live) wells on the pad. Return to pad drilling requires more frequent surveying and anti-collision avoidance management because producing wells are present. By utilizing good engineering well design, anti-collision software and frequent surveys, wells can safely be drilled while existing or producing wells exist on the pad.

With both normal and return to pad drilling operations, every well planned to be drilled has a surface plot diagram, 2-D plot diagram, and a pad plot diagram prepared. (Plots attached under "Collision Avoidance Diagrams") In each scenario, north seeking gyro tools, MWD/EM tools, and anti-collision processes are utilized to mitigate the risk of downhole collisions. Anti-collision processes include conformation of gyro accuracy, evaluation of anti-collision software (Compass or equivalent program), and 2-D/3-D model plotting. In both scenarios, it is EQT's standard operating procedure (SOP) for the onsite supervisor of EQT and the directional drilling company supervisor to confirm the orientation of the directional tools and ensure that the tools are orientated consistent with the directional motor's high side. When anti-collision is a risk and directional assemblies are required to navigate utilizing a gyro tool, it is EQT's SOP to use the Gyro company's muleshoe to ensure the accuracy of the gyro seat in the muleshoe. In addition, when using this muleshoe, it is EQT's SOP to have the EQT's on-site supervisor, directional drilling company supervisor, and gyro company supervisor confirm the alignment and orientation of the tool and ensure that the tools are orientated consistent with the directional high side. This ensures the azimuthal direction is correct when steering the well.

APR 2 1 2015

Normal Pad Drilling

In this scenario, there are no existing wells on the pad. A top-hole rig will move on to the pad and drill near protection each well to KOP and then a bottom hole rig will move on after the top hole rig finishes and drill the each well to horizontal TD. At times, the bottom hole rig may drill each well from surface to horizontal TD.

During this scenario, if two wells come within 10 feet or a separation factor of 1.5, each survey is monitored closely and anti-collision is run after each survey until the wells are clear of a collision risk. If a $SF \le 1.0$ or $\le 5'$ separation is encountered or a collision occurs, an email notification will be sent by the EQT on-site drilling supervisor to the appropriate state inspector. In the event the proximity of wells get



to a point where a collision cannot be avoided or a collision occurs, EQT will properly secure each well and evaluate the most prudent plan forward while communicating plans with the state inspector.

Vertical Section:

Each hole is drilled to KOP by either the top-hole rig or bottom hole rig. Once KOP is achieved then a gyro survey is run. No nudges are planned.

 Each gyro is analyzed and certified accurate by the gyro company before it is used for any directional planning or modeling. Each tool is roll tested on location and if all surveys are within tolerances the gyro survey is sent to the gyro company's office to be further analyzed and certified accurate.

Horizontal Section:

After the top-hole section of the well is complete and the well is at KOP, anti-collision is run on each well and the most efficient well path with the lowest risk of collision is selected by engineers. Directional bottom hole assemblies (BHA) are run in the hole and used to drill the well from vertical to horizontal. Gyros or MWD/EM surveys are taken as needed to steer the well until the well is away from the other wells and the risk of collision is eliminated. Surveys utilizing MWD/EM tools are taken from that point on to the total depth of the well is achieved. After each survey is taken, the surveys are analyzed by both EQT engineers and the directional drilling well planning technicians and anti-collision is run to ensure current well path is not in the direction of a producing well(s) and consistant with the permitted well path.

- Anti-Collision is a software program into which gyro surveys or MWD/EM surveys are uploaded. The software runs 2-D and 3-D well paths of all wells within the vicinity of the well being drilled.
- Surveys are taken every 100'.
- While directionally drilling the well, anti-collision software is constantly updated and separation factors (SF) are analyzed.
- Each survey is analyzed and certified accurate by the directional company before it is used for any directional planning or modeling.

APR 2 1 2015

Return to Pad Drilling

In this scenario a top-hole rig or bottom hole rig will move on a pad that currently has producing (live) wells on the pad. Prior to drilling additional wells on the pad, the gyro from the existing wells on the pad rotection are analyzed by engineers to evaluate how the existing wells walk in the vertical part of the well. Then preliminary directional plans are prepared to mitigate downhole collisions. EQT plans to drill and develop the pad while producing existing offset wells. However, additional well path management (more frequent surveying and anti-collision modeling) is performed by engineers during the drilling process both in the vertical and horizontal sections of each well.

During this scenario, the well is surveyed from surface to TD as it is drilled and if two wells come within 14 feet or a SF of 2.0, each survey is monitored closely and anti-collision is run after each survey until the wells are clear of a potential collision. If a SF \leq 1.0 or \leq 5' separation is encountered, an email notification will be sent by the EQT on-site drilling supervisor to the

085-10137 MODZ

appropriate state inspector. In the event the proximity of wells get to a point where a collision cannot be avoided, EQT will properly secure each well and evaluate the most prudent plan forward while communicating plans with the state inspector.

Vertical Section:

After the rig moves on the pad and starts drilling, gyro surveys are taken several times from surface to KOP. After each gyro is taken, the surveys are analyzed by both EQT engineers and the directional drilling well planning technicians and anti-collision is run to ensure current well path is not in the direction of a producing well(s). All of these steps are completed prior to the resumption of drilling. Actual frequency of gyros is determined by engineers and the position of the hole as it relates to existing wells on the pad. No nudges are planned.

- Anti-Collision is a software program into which gyro surveys or MWD/EM surveys are uploaded. The software runs 2-D and 3-D well paths of all wells within the vicinity of the well being drilled.
- While vertically drilling the well, anti-collision software is constantly updated and separation factors (SF) are analyzed.
- Each gyro is analyzed and certified accurate by the gyro company before it is used for any directional planning or modeling. Each tool is roll tested on location and if all surveys are within tolerances the gyro survey is sent to the gyro company's office to be further analyzed and certified accurate.


Horizontal Section:


Directional BHAs are run in the hole and used to drill the well from vertical to horizontal. Gyros or MWD/EM surveys are taken as needed to steer the well until the well is away from the other wells and the risk of collision is eliminated. Surveys utilizing MWD/EM tools are taken continuously until the total depth of the well is achieved. After each survey is taken, the surveys are analyzed by both EQT engineers and the directional drilling well planning technicians and anti-collision is run to ensure current well path is not in the direction of a producing well(s) and consistent with the permitted well path.


- Anti-Collision is a software program into which gyro surveys or MWD/EM surveys are uploaded. The software runs 2-D and 3-D well paths of all wells within the vicinity of the well being drilled.
- Surveys are taken every 100'.
- While directionally drilling the well, anti-collision software is constantly updated and separation factors (SF) are analyzed.
- Each survey is analyzed and certified accurate by the directional company before it is used for any directional planning or modeling.

Received

APR 2 1 2015







WW-6A	l
(5/13)	

Operator's Well No.

5	1	3	7	6

INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE Chapter 22, Article 6A, Section 5(a)(5) IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that —

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or				
Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
Lease 118212			min pd 1/8th	
	J. E. Pierce, L. L. Pierce & Felsie Pierce	Pittsburgh & WV Gas. Co.		LB 45/257
	Pittsburg & WV Gas Co.	Equitable Gas Company		DB 126/473
	Equitable Gas Company	Equitrans, Inc.		LB 201/253
	Equittrans, Inc.	Equitable Production Company		LB 192/19
	Equitable Production Company	EQT Production Co		DB 281/346
			min pd 1/8th	
Lease 118210	B. M. Pierce & G. M. Pierce	Pittsburgh & WV Gas. Co.		LB 45/253
	Pittsburg & WV Gas Co.	Equitable Gas Company		DB 126/473
	Equitable Gas Company	Equitrans, Inc.		LB 201/253
	Equittrans, Inc.	Equitable Production Company		LB 192/19
	Equitable Production Company	EQT Production Co.		DB 281/346
Lease 987447			min pd 1/8th	
	Craig H. Williams & Amy L. Williams	EQT Production Co		DB 370/952
Lease 107857			min pd 1/8th	
	Beatty Jean Nutter	EQT Production Co		LB 255/510
	Jerry Allen Riddle	EQT Production Co		LB 255/516
			min pd 1/8th	
Lease 988339	Whittle Corporation	Antero Resources Corp.		LB254/1024
-	Antero Resources Corp.	EQT Production Co.		LB273/865
	•			

Upon information and belief, Operator's lease and/or other real property rights permit it to conduct drilling operations for the subject well in the location shown on the plat, including under any public roads that the well lateral crosses.

APR 2 1 2015

Acknowledgement of Possible Permitting/Approval In Addition to the Office of Oil and Gas

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

Well Operator:	EQT Production Company
Ву:	Must It
Its:	Permitting Supervisor
	Page 1 of 1

Received

APR 2 1 2015