



1097

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD


Permit No. **1107-A**
EQUITABLE GAS COMPANY
 Pittsburgh & West Va. Gas Company.
 Company **Clarksburg, West Va.**
 Address **E. R. Taylor** Acres **1600**
 Farm **West Union 8/7. 3-4**
 Location (waters) **4671** Elev. _____
 Well No. **Clay** County **Ritchie**
 District **Grover Collins**
 The surface of tract is owned in fee by **Rennsboro, W. Va.**
R.D.#1 Address _____
 Mineral rights are owned by **Grover Taylor et al.**
Rennsboro, W. Va. Address _____
 Drilling commenced **August 12, 1916**
 Drilling completed **September 13, 1916**
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

Oil or Gas Well **"GAS"**
(KIND)

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Bottom Hole
10	308'	1254'	Size 2-1/4" X 5-5/8"
8 3/4	1294'	1294'	Depth set 1978'
6 3/4	1978'	1978'	
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT **275** FEET **36** INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES
 _____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate	Red	Soft	0	40			
Sand	Light	Hard	40	65			
Slate	Red	Soft	65	125			
"	White	"	125	200			
Slate Shells	Light	Soft/Hard	200	275			
Coal	Black	Soft	275	278			
Slate	White	"	278	300			
Sand	"	Hard	300	330			
Slate	"	Soft	330	330			
"	Red	"	330	385			
"	White	"	385	400			
Sand	"	Hard	400	420			
Slate	"	Soft	420	445			
"	Red	"	445	480			
Line	White	Hard	480	460			
Sand	"	"	460	485			
Slate	"	Soft	485	500			
Line	"	Hard	500	520			
Sand	"	Hard	520	540			
Line	Red	"	540	560			
Slate	"	Soft	560	610			
Line	White	Hard	610	630			
Sand	"	"	630	660			
Slate	"	Soft	660	700			
Sand	Light	Hard	700	705			
Slate	White	Soft	705	720			
"	Black	"	720	725			
Line	Dark	Hard	725	760			
Slate	Red	Soft	760	765			
"	White	"	765	785			
Sand	"	Hard	785	790			
Slate	"	Soft	790	825			
Sand	"	Hard	825	845			
Slate	Red	Soft	845	855			
Sand	White	Hard	855	870			
Line	"	"	870	890			
Slate	Red	Soft	890	915			
Slate Shells	Light	Soft/Hard	915	960			
Sand	"	Hard	960	970			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate&Shells	Light	Hard&Soft	970	1010			
Little Dunkard	White	Hard	1010	1035			
Slate	"	Soft	1035	1050			
Slate	Red	"	1050	1106			
Big Dunkard	White	Hard	1106	1135			
Slate	Red	Soft	1135	1150			
Lime	White	Hard	1150	1155			
Slate	"	Soft	1155	1200			
Lime	"	Hard	1200	1205			
Slate&Shells	Light	Soft&Hard	1205	1220			
Slate	Black	Soft	1220	1245			
Gas Sand	White	Hard	1245	1255			
Slate&Shells	"	Soft&Hard	1255	1340			
Sand	"	Hard	1340	1360			
Slate&Shells	Dark	Soft&Hard	1360	1390			
1st. Salt Sand	White	Hard	1390	1410			
Slate&Shells	Light	Soft&Hard	1410	1450			
2nd. Salt Sand	White	Hard	1450	1515			
Slate	Dark	Soft	1515	1520			
Lime	White	Hard	1520	1540			
3rd. Salt Sand	"	"	1540	1650	Water	1560'	6 Bailleurs Hr.
Slate	Dark	Soft	1650	1655			
4th. Salt Sand	Light	Hard	1655	1700			
Slate&Shells	Dark	Soft&Hard	1700	1765			
Sand	White	Hard	1765	1825			
Lime	Dark	Hard	1825	1868			
Slate	"	Soft	1868	1873			
Lime	White	Hard	1873	1881			
Slate	Dark	Soft	1881	1886			
Masson Sand	White	Hard	1886	1895			
Slate&Shells	Black	Soft&Hard	1895	1935			
Little Lime	Dark	Hard	1935	1952			
Coal	Black	Soft	1952	1955			
Lime	White	Hard	1955	1961			
Slate	Dark	Soft	1961	1965			
Big Lime	White	Hard	1965	2043	Gas	1988-1990'	
Big Injun	"	"	2043	2150	Gas	2138-2143'	
Slate	Dark	Soft	2150	2152			
Lime	White	Hard	2152	2172			
Slate&Shells	Dark	Soft&Hard	2172	2209			
Total Depth..				2209			

December 11, 1944

EQUITABLE GAS COMPANY

194

APPROVED

Owner

By W. J. Johnston
(Title)