



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1093

WELL RECORD
WELL TO BE ABANDONED

Oil or Gas Well Gas
(KIND)


Permit No. 1187-A
Company Carnegie Natural Gas Company
Address 1015 Frick Building, Pittsburgh 19, Pa.
Farm Eva J. Ayers Acres 40
Location (waters) Lynn Camp Run
Well No. 955 Elev. 1142
District Clay County Ritchie
The surface of tract is owned in fee by J. C. Hogue,
Pennsboro Address West Virginia
Mineral rights are owned by Eva J. Ayers,
Smithville, Address West Virginia
Drilling commenced 9-17-19
Drilling completed 10-18-19
Date Shot _____ From _____ To _____
With _____
Open Flow _____ /10ths Water in _____ Inch
60 /10ths Merc. in 6-5/8 Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	267	267	Size of
8 1/4	1090	None	
6 5/8	1957	1957	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 530 FEET INCHES
640 FEET INCHES FEET INCHES
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapleton Coal			530	532			
Pittsburgh Coal			640	641			
Big Dunkard			1080	1105			
Gas Sand			1257	1287			
1st Salt Sand			1400	1420			
2nd Salt Sand			1450	1880			
Maxon			1890	1904			
Little Lime			1918	1931			
Pencil Cave			1931	1942			
Big Lime			1942	2047			
Big Injan			2047	2118	Gas Gas Gas	2049-2061 2068-2073 2087-2097	
		Total Depth		2148			



FEB 11 1953

(Over)

