

#### west virginia department of environmental protection

Office of Oil and Gas 601 57th Street, S.E. Charleston, WV 25304 (304) 926-0450 fax: (304) 926-0452

Austin Caperton, Cabinet Secretary www.dep.wv.gov

Wednesday, April 11, 2018 WELL WORK PERMIT Vertical / Plugging

ICG TYGART VALLEY, LLC 100 TYGART DR

GRAFTON, WV 26354

Re:

Permit approval for B803 47-091-01089-00-00

This well work permit is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to any additional specific conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas Inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days of completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

Per 35 CSR 4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926-0450.

James A. Martin

Chief

Operator's Well Number:

Farm Name: BRADLEY, WESLEY J.

U.S. WELL NUMBER: 47-091-01089-00-00

Vertical Plugging

Date Issued: 4/11/2018

## **PERMIT CONDITIONS**

West Virginia Code §22-6-11 allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

## **CONDITIONS**

- 1. All pits must be lined with a minimum of 20 mil thickness synthetic liner.
- 2. In the event of an accident or explosion causing loss of life or serious personal injury in or about the well or while working on the well, the well operator or its contractor shall give notice, stating the particulars of the accident or explosion, to the oil and gas inspector and the Chief within twenty-four (24) hours.
- 3. Well work activities shall not constitute a hazard to the safety of persons.

WW-4BRev. 2/01

1) Date January 5	,	20 18
2) Operator's		-
Well No. B-803		
3) API Well No.	47-91	- 01089

#### STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS

	APPLICATION FOR A PERM	MIT TO PLUG AND ABANDON
4)	Well Type: Oil/ Gas/ Liquid	d injection/ Waste disposal/
	(If "Gas, Production or Unc	derground storage) Deep/ Shallow X
5)	Location: Elevation 1603'	Watershed Glade Run
	District Knottsville	County Taylor Quadrangle Thornton (638)
6)	Well Operator ICG Tygart Valley, LLC	7) Designated Agent Charles E. Duckworth
0 /	Address 100 Tygart Drive	Address 100 Tygart Drive
		Grafton, WV 26354
	Grafton, WV 26354	Granton, WV 20334
8)	Oil and Gas Inspector to be notified	9)Plugging Contractor
	Name Kenneth Greynolds	Name Coastal Drilling East, LLC
	Address 613 Broad Run Road	Address 130 Meadows Ridge Road
	Jane Lew, WV 26378	Mt. Morris, PA 15349
	Work Order: The work order for the manner See Exhibit Nos. 1 and 2 and MSHA 101-C E  ICG Tygart Valley, LLC (47-091-01089)  Leer Mine (MSHA ID# 46-09192  MSHA 101-C Docket No. M-2012-065-C  Appropriate coal seam top = 524.0'	
1	Approximate coal seam bottom = 529.	.3'
wor	k can commence.	il and gas inspector 24 hours before permitted  Alapaer Date 3-19-18

#### EXHIBIT NO. 1

From the experience and technology developed since 1970 in plugging oil and gas wells for mining through, ICG Tygart Valley, LLC will utilize the following method to plug all future wells.

### SOLID PLUG METHOD



- a) If active well: clean out to total depth and plug back according to state regulations to a minimum of 200 feet below lowest minable coal seam.
- b) If abandoned well: clean out to first plug 200 feet below lowest minable coal seam.
- c) Circulate through tubing or drill steel an expanding cement plug from a minimum of 200 feet below minable coal seam to a point 100 feet above minable coal.

Circulate through tubing or drill steel from 100 feet above coal seam to surface.

A monument will be installed with API No. and stating "solid plug".

WELL IS DEEPER THAN 4000'.

- · CLEAN OUT TO TO OF 4528, SET CLASS A. -CEMENT PLUG FROM TO TO 400' BELOW LOWEST MINABLE COAL (\$ 1028').
  - SET EXPANDING CEMENT FROM 1028' TO 100' ABOUR
    THE SHALLOWEST MINABLE COAL.

    RECEIVED Gas

ABOUR SHALLOWEST COAL TO SURFACE. WV Department of Environmental Protection

gwm



## EXHIBIT No. 2

Coastal Drilling East LLC • 130 Meadow Ridge Road, Mt. Morris, PA 15349

Phone 304-296-1120 Fax 304-413-0061

"A Shaft Drillers International Company"

05/26/2016

Mr. Chuck Duckworth Gas Well & Property Manager Arch Coal, Inc. – Leer Mine Complex 100 Tygart Drive Grafton, WV 26354

Mr. Duckworth,

Below is the proposed plugging plan we discussed that can be used on wells similar to the wells we have been plugging for the last few years.

## Plugging Plan

• Move to site, rig up, mix mud, drill rathole

 Run cement bond log on 4 ½" casing to determine top of cement Environmental Protection
 Set bottom hale cement place and the second • Set bottom hole cement plug as required by the WV DEP from TD to top of cement determined by the bond log.

- Tag top of bottom hole plug to insure plug is at correct depth. Re-cement if necessary.
- Cut and pull 4 ½" casing from the free point determined by the bond log.
- Clean out wellbore to top of remaining 4 ½" casing
- Run suite of logs to determine casing size, bottom of casing, depth of coal seams, deviation of wellbore and cement bond to casing.
- Cement hole from top of bottom hole plug to a depth within 25' of the bottom of the 8 5/8" casing.
- If necessary cut and pull any free casing.
- Perforate, cut, rip or mill any remaining casing at depths determined by MSHA's 101C Petition.

- Cement hole from top of intermediate plug to surface using cement required by MSHA's 101C Petition.
- Rig down and set monument as required by WV DEP.

RECEIVED Office of Oil and Gas

MAR 2 0: 2018



face area will be available. The fire hose will be located near the working face.

(5) Sufficient supplies of roof support and ventilation materials will be available and located near the working face. In addition, an emergency plug and/or plugs will be available within the immediate area of the well

(6) Equipment involved in mining through the well will be checked for permissibility and serviced on the maintenance shift prior to mining through the well. The methane monitor on the continuous mining machine involved in mining through the well will also be calibrated on the maintenance shift prior to mining

through the well.

(7) When mining is in progress, tests for methane will be made with a handheld methane detector at least every 10 minutes, from the time that mining with the continuous mining machine is within 30 feet of the well until the well is intersected, and immediately prior to mining through. During the actual cutting-through process, no individual will be allowed on the return side until mining-through has been completed and the area has been examined and declared safe.

(8) The working area will be free from accumulations of coal dust and coal spillages, and rock dust will be placed on the roof, rib, and floor to within 20 feet of the face when mining through the

well

(9) When the well is intersected, all equipment will be deenergized and the place thoroughly examined and determined safe before mining is resumed.

(10) Any casing will be removed and no open flame will be permitted in the area until adequate ventilation has been established around the well.

(11) After a well has been intersected and the working place determined safe, mining will continue inby the well at a distance sufficient to permit adequate ventilation around the area of the well.

(12) No person will be permitted in the area of the mining-through operation except those actually engaged in the operation, company personnel, personnel from MSHA, and personnel from the Kentucky OMSL.

(13) The mining-through operation will be under the direct supervision of a certified individual. Instructions concerning the mining-through operation will be issued only by the certified individual in charge, MSHA personnel may interrupt or halt the mining through operation when

necessary for the safety of the miners.
(14) Within 30 days after this Order becomes final, the petitioner will submit (Oil and gas wells).

proposed revisions for its approved mine emergency evacuation and firefighting plan required by 30 CFR 75.1501. The petitioner will revise the plans to include the hazards and evacuation procedures to be used for well intersections.

The petitioner further states that this petition will apply to all types of mining (conventional, continuous, and longwall) and asserts that the proposed alternative method will at all times provide a measure of protection no less than that of the existing standard.

Docket Number: M-2012-064-C.

Petitioner: Lone Mountain Processing, Inc., Drawer C, St. Charles, Virginia 24282.

Mine: Mine No. 1, MSHA I.D. No. 15-18734, Route 636 Benedict Road, St. Charles, Virginia 24282, located in

Harlan County, Kentucky.

Regulation Affected: 30 CFR 75.208

(Warning devices).

Modification Request: The petitioner requests a modification of the existing standard to permit a readily visible warning to be posted at the second row of permanent roof support outby unsupported roof or a physical barrier to be installed to impede travel beyond permanent support, except during the installation of roof supports. The petitioner states that:

(1) The Kentucky Office of Mine Safety and Licensing requires "a warning device to be installed on the second row of permanent roof support

outby unsupported roof."
(2) MSHA's approved Precautions for Remote Control Operation of Continuous Mining Machines states that "While using remote controls, the continuous mining machine operator and all other persons will position themselves no closer than the second 'full row' of installed roof bolts outby the face."

(3) This petition is necessary to improve safety and to attain commonality between State and Federal

regulations.

(4) Safety increases when the distance an employee keeps from unsupported roof increases.

The petitioner asserts that the proposed alternative method will at all times guarantee no less than the same measure of protection afforded by the existing standard.

Docket Number: M-2012-065-C. Petitioner: ICG Tygart Valley, LLC, 1200 Tygart Drive, Grafton, West Virginia 26354.

Mine: Tygart #1 Mine, MSHA I.D. No. 46–09192, located in Taylor County, West Virginia.

Regulation Affected: 30 CFR 75.1700

Modification Request: The petitioner requests a modification of the existing standard requiring that barriers be established and maintained around oil and gas wells penetrating coalbeds or underground areas of coal mines to permit an alternative method of compliance. The petitioner states that:

(1) The mine is projected to encounter vertical in-seam boreholes, typical to oil and natural gas wells, as mine

development progresses.

(2) The active development section is approaching these boreholes, and is projected to encounter additional boreholes in the future as mining

operations continue.

(3) The procedure presented in this petition will be used to ensure that mining through these boreholes is accomplished safely and, as an alternative to compliance with 30 CFR 75.1700, will provide no less than the same measure of protection to the miners, as required by the MSHA standard.

The petitioner proposes to use the following procedures when plugging oil or gas wells:

(1) Prior to plugging an oil or gas well, a diligent effort will be made to clean the borehole to the original total depth. If this depth cannot be reached, the borehole will be cleaned out to a depth that would permit the placement of at least 200 feet of expanding cement below the base of the lowest minable

(2) When cleaning the borehole, a diligent effort will be made to remove all of the casing in the borehole. If it is not possible to remove all of the casing, the casing that remains will be perforated or ripped at intervals spaced close enough to permit expanding cement slurry to infiltrate the annulus between the casing and the borehole wall for a distance of at least 200 feet below the base of the lowest minable

(3) If the cleaned-out borehole produces gas, a mechanical bridge plug will be placed in the borehole in a competent stratum at least 200 feet below the base of the lowest minable coal bed, but above the top of the uppermost hydrocarbon-producing stratum. If it is not possible to set a mechanical bridge plug, a substantial brush plug may be used in its place. The District Manager may allow the

use of other effective methods of stopping any and all gas flow emitting from the wellbore before placement of cement through the minable coal seam(s). Such approval will be documented in a written response to the operators' submittal of a detailed explanation of the method to be used

RECEIVED Office of Oil and Gas

MAR 2 0: 2018

and an engineering evaluation of the relative effectiveness of the alternative.

(4) A suite of logs will be made, consisting of a caliper survey, directional deviation survey, and log(s) suitable for determining the top and bottom of the lowest minable coal bed and potential hydrocarbon-producing strata and the location for the bridge

plug. (5) If the uppermost hydrocarbonproducing stratum is within 200 feet of the base of the lowest minable coal bed, properly placed mechanical bridge plugs or a suitable brush plug described in paragraph (3) above will be used to isolate the hydrocarbon-producing stratum from the expanding cement plug. Nevertheless, a minimum of 200 feet of expanding cement will be placed below the lowest minable coal bed.

(6) The wellbore will be completely filled and circulated with a gel that inhibits any flow of gas, supports the walls of the borehole, and increases the density of the expanding cement. This gel will be pumped through open-end tubing run to a point approximately 20 feet above the bottom of the cleaned out area of the borehole or bridge plug. The petitioner proposes to use the

following procedures when plugging gas

and oil wells to the surface:

(1) A cement plug will be set in the wellbore by pumping expanding cement slurry down the tubing to displace the gel and fill the borehole to the surface. As an alternative, the cement slurry may be pumped down the tubing so that the borehole is filled. There will be at least 200 feet of expanding cement below the base of the lowest minable coal bed.

(2) A marker conforming to the requirements of the state regulatory authority will be installed at the borehole, or a small quantity of steel turnings or other small magnetic particles will be embedded in the top of the cement near the surface. The method used will be suitable to serve as a permanent magnetic monument of the

borehole.

The following procedures will be used for the vent pipe method for

plugging oil and gas wells:

(1) A 41/2-inch or larger pipe will be run into the wellbore to a depth of 100 feet below the lowest minable coal bed and wedged to a smaller diameter pipe that, if desired, will extend to a point approximately 20 feet above the bottom of the cleaned-out area of the borehole

or bridge plug.
(2) A cement plug will be set in the wellbore by pumping expanding cement slurry, Portland cement, or a Portland cement-fly ash mixture down the tubing to displace the gel so that the borehole is filled with cement. The borehole and

the vent pipe will be filled with expanding cement for a minimum of 200 feet below the base of the lowest minable coal bed. The top of the expanding cement will extend upward to a point approximately 100 feet above the top of the lowest minable coal bed.

(3) All fluid will be evacuated from the vent pipe to facilitate testing for gases. During the evacuation of fluid, the expanding cement will not be

disturbed.

(4) The top of the vent pipe will be protected to prevent liquids or solids from entering the wellbore, but permit ready access to the full internal diameter of the vent pipe when necessary.

The petitioner proposes to use the following procedures when plugging oil or gas wells for subsequent use as

degasification boreholes:

(1) A cement plug will be set in the wellbore by pumping expanding cement slurry down the tubing to displace the gel and provide at least 200 feet of expanding cement below the lowest minable coal bed. The top of the expanding cement will extend upward to a point above the top of the coal bed being mined. This distance will be based on the average height of the roof strata breakage for the mine.
(2) To facilitate methane drainage,

degasification casing of suitable diameter, slotted or perforated throughout its lower 150 to 200 feet, will be set in the borehole to a point 10 to 30 feet above the top of the expanding

(3) The annulus between the degasification casing and the borehole wall will be cemented from a point immediately above the slots or perforations to the surface.

(4) The degasification casing will be cleaned out for its total length.

(5) The top of the degasification casing will be fitted with a wellhead equipped as required by the District Manager. Such equipment may include check valves, shut-in valves, sampling port, flame arrestor equipment, and

security fencing.

The following alternative procedures for preparing and plugging oil and gas wells will apply to wells that the petitioner and the District Manager agree cannot be completely cleaned out due to damage to the well caused by subsidence, caving, or other factors; as determined by the petitioner and agreed to by the District Manager. These provisions will apply unless alternative measures are agreed upon and based upon a plan submitted to the District Manager:

(1) The petitioner will drill a hole adjacent and parallel to the well to a depth of at least 200 feet below the lowest minable coal seam.

(2) The petitioner will use a geophysical sensing device to locate any casing that may remain in the well.
(3) If the well contains casing(s), the

petitioner will drill into the well from the parallel hole. From 10 feet below the coal seam to 10 feet above the coal seam, the petitioner will perforate or rip all casings at intervals of at least 5 feet. Beyond this distance, the petitioner will perforate or rip at least every 50 feet from at least 200 feet below the base of the lowest minable coal seam up to 100 feet above the seam being mined. The petitioner will fill the annulus between the casing, and between the casings and the well wall with expanding cement (minimum 0.5 percent expansion upon setting), and will ensure that these areas contain no voids. If the petitioner, using a casing bond log, can demonstrate to the satisfaction of the District Manager that the annulus of the well is adequately sealed with cement, then the petitioner will not be required to perforate or rip the casing for that particular well or fill these areas with cement. When multiple casing and tubing strings are present in the coal horizon(s), any casing that remains will be ripped or perforated and filled with expanding cement as indicated above. An acceptable casing bond log for each casing and tubing string is needed if used in lieu of ripping or perforating

multiple strings.
(4) Where the petitioner determines and the District Manager agrees that there is insufficient casing in the well to allow the method outlined in paragraph (3) above to be used, then the petitioner will use a horizontal hydraulic fracturing technique to intercept the original well. From at least 200 feet below the base of the lowest minable coal seam to a point at least 50 feet above the seam being mined, the petitioner will fracture at least six places at intervals to be agreed upon by the petitioner and the District Manager after considering the geological strata and the pressure within the well. The petitioner will then pump expanding cement into the fractured well in sufficient quantities and in a manner that fills all intercepted voids.

(5) The petitioner will prepare downhole logs for each well. The logs will consist of a caliper survey and log(s) suitable for determining the top, bottom, and thickness of all coal seams and potential hydrocarbon-producing strata and the location for the bridge plug. The petitioner may obtain the logs from the adjacent hole rather than the well if the condition of the well makes it impractical to insert the equipment

RECEIVED
Office of Oil and Gas

MAR 2 0:2018

necessary to obtain the log. The District Manager may approve the use of a down-hole cameral survey in lieu of down-hole logs if, in his or her judgment, such logs would not be suitable for obtaining the data or are impractical to obtain due to the condition of the drill hole. A journal will be maintained describing the length and type material used to plug the well; the length of casing(s) removed, perforated, or ripped or left in place; and other pertinent information

concerning sealing the well.
(6) After the petitioner has plugged the well, the petitioner will plug the open portions of both holes from the bottom to the surface with Portland cement or a lightweight cement mixture. The petitioner will embed steel turnings or other small magnetic particles in the top of the cement near the surface to serve as a permanent magnetic monument of the well. In the alternative, a 41/2-inch or larger casing set in cement will extend at least 36 inches above the ground level. A combination of the methods outlined in paragraph (3) and (4) above may have to be used in a single well, depending upon the conditions of the hole and the presence of casings. The petitioner and the District Manager may discuss the nature of each hole and the District Manager may require the use of more than one method.

The petitioner proposes to use the following cut-through procedures whenever the safety barrier diameter is reduced to a distance less than the District Manager would approve pursuant to \$75.1700 or the petitioner proceeds with an intent to cut through a plugged well:

(1) Prior to reducing the safety barrier to a distance less than the District Manager would approve or proceeding with intent to cut through a plugged well, the petitioner will notify the District Manager.

(2) Mining in close proximity to or through a plugged well will be done on a shift approved by the District

Manager.

(3) The District Manager, a representative of the miners, and the appropriate States agency will be notified by the operator in sufficient time prior to the mining-through operation to provide an opportunity for them to have a representative present.

(4) When using continuous mining equipment, drivage sights will be installed at the last open crosscut near the place to be mined to ensure intersection of the well. The drivage sights will not be more that 50 feet from the well. When using longwall mining methods, drivage sights will be installed on 10-foot centers for a distance of 50 feet in advance of the well bore. The drivage sights will be installed in the headgate and tailgate.

(5) Firefighting equipment, including fire extinguishers, rock dust, and sufficient fire hose to reach the working face area of the mining-through will be available when either the conventional or continuous mining method is used. The fire hose will be located in the last open crosscut of the entry or room. All fire hoses will be ready for operation during the mining-through.

(6) Sufficient supplies of roof support and ventilation materials will be available and located at the last open crosscut. In addition, an emergency plug and/or plugs will be available in the immediate area of the cut-through.

(7) The quantity of air required by the approved mine ventilation plan, but not less than 6,000 cubic feet per minute (cfm) of air for scrubber-equipped continuous miners or not less than 9,000 cfm for continuous miner sections using auxiliary fans or line brattice only, will be used to ventilate the working face during the mining-through operation. The quantity of air required by the ventilation plan, but not less than 30,000 cfm, will reach the working face of each longwall during the miningthrough operation.

(8) Equipment will be checked for permissibility and serviced on the shift prior to mining-through the well. The methane monitors on the continuous mining machine or the longwall shear and face will be calibrated on the shift prior to mining through the well.

(9) When mining is in progress, tests for methane will be made with a handheld methane detector at least every 10 minutes from the time that mining with the continuous mining machine is within 30 feet of the well until the well is intersected and immediately prior to mining through. When mining with longwall mining equipment, tests for methane will be made at least every 10 minutes when the longwall face is within 10 feet of the well. During the actual cutting-through process, no individual will be allowed on the return side until mining through has been completed and the area has been examined and declared safe.

(10) When using continuous mining methods, the working area will be free from accumulations of coal dust and coal spillages, and rock dust will be placed on the roof, rib, and floor to within 20 feet of the face when mining through or near the well on the shift or shifts during which the cut-through will occur. On longwall sections, rockdusting will be conducted and placed

on the roof, rib, and floor up to both headgate and tailgate gob.

(11) When the wellbore is intersected, all equipment will be deenergized and the area thoroughly examined and determined safe before mining is resumed. Any well casing will be removed and no open flame will be permitted in the area until adequate ventilation has been established around the wellbore.

(12) After a well has been intersected and the working area determined safe, mining will continue inby the well at a distance sufficient to permit adequate ventilation around the area of the

(13) No person will be permitted in the area of the mining-through operation except those actually engaged in the operation, company personnel, representatives of the miners, personnel from MSHA, and personnel from the

appropriate State agency.
(14) The mining-through operation will be under the direct supervision of a certified official. Instructions concerning the mining-through operation will be issued only by the certified official in charge. MSHA personnel may interrupt or halt the mining-through operation when necessary for the safety of the miners.
(15) The petitioner will file a plugging

affidavit setting forth the persons who participated in the work, a description of the plugging work, and a certification by the petitioner that the well has been plugged as described.

(16) Within 60 days after the Proposed Decision and Order (PDO) becomes final, the petitioner will submit proposed revisions for its approved 30 GFR Part 48 training plan to the District Manager. The provisions will include initial and refresher training regarding compliance with the terms and conditions stated in the PDO.

The petitioner asserts that the proposed alternative method will at all times guarantee miners no less than the same measure of protection as afforded by the existing standard.

Petitioner: Hecla Greens Creek Mining Office of Oil and Gas Ompany, P.O. Box 32199, Juneau laska 90202 Company, P.O. Box 32199, Juneau, Alaska 99803.

No. 50-01267, located in Juneau County, Alaska.

Regulation Affected: 30 CFR 57.14130 Environmental Protection toll-over protective structures (PCN) (Roll-over protective structures (ROPS) and seat belts for surface equipment).

Modification Request: The petitioner requests a modification of the existing standard to permit employees to be transported 1,600 feet to and from the surface dry facility to work sites underground using underground mine

MAR 2 0. 2018

WR-35 Rev (5-01)	20		
عدد (درمی)	Department of Office	of West Virging of Environmenta ce of Oil and G	l Protection as
	. well-Operat	or's Report of V	WELL MOEK
Paun name: Bradley	•	Op	erator Well
LOCATION: Elevation:	1603'	Qu	adrangle: _
District: Knot	tsville	Co	mty Tayl
Latitude:	Feet South of	Deg	Min.
Longitude	Feet West of	Deg	Min.
Company: Berry Energy.	Inc.		
		Casing & Tubing	Used in drilling
Address: P.O Box 5		7"	108
Clarksburg, WV 26301			
Agent: David Berry			
Inspector: Bill Hatfield			
Date Permit Issued: 10/29/	2007		
Date Well Work Commen			
Date Well Work Complete	d: 2/15/2008		
Verbal Phaging			7

DATE: 5/8/2008 API#: 47-091-01089

Well Operator	's Report o	f Well Work		e E					
Parm name: Bradley		Operator Well No.: B803							
LOCATION: Elevation: 1603	(	Quadrangle:Thornton							
District: Knottsville		County Taylor							
Latitude:Feet South of	Deg	Min	Sec.						
Longitude Feet West of	Deg	Min	Sec.						
Company: Berry Energy, Inc.									
	Casing &	Used in drilling	Left in well	Cement fill up Cn. Ft.					
Address: P.O Box 5	7"	1080'	1080'	To surface					
Clarksburg, WV 26301									
Agent: David Berry									
Inspector: Bill Hatfield									
Date Permit Issued: 10/29/2007									
Date Well Work Commenced: 2/9/2008			AF.	CEIVED					
Date Well Work Completed: 2/15/2008			-Office of	of Oil & Gas					
Verbal Plugging: Date Permission granted on:				1.01.01.01.00					
Rotary X Cable Rig			1 65/48	27 2011					
Total Depth (feet): 4528'			1901	1 2 2 2011					
Fresh Water Depth (ft.): 90'			148/5	<del></del> _					
Treat water pepin (the): 50			T ANA DE	partment of					
Salt Water Depth (ft.): None	<del> </del>	<del>- </del>	<del>Invironm</del> e	Intal Protection					
			<del> </del>						
Is coal being mined in area (N/Y)? No			1						
Coal Depth: 619'									
OPEN FLOW DATA									
Producing formation To Be Deepened		Pay zone depth	(ft)						
Gas: Initial open flow 26 MCF/d	Oil	l: Initial open flow	w Rhi	d d					
Final open flow 0 MCF/d		Final open flow	Dhi	/d					
Time of open flow between initial and f	final tests_	Hou	rs						
Time of open flow between initial and i Static rock Pressure psig (su	rface pres	sure) after	· Hours	/					
Second producing formation  Gas: Initial open flow MCF/d Oil:  Final open flow MCF/d F				81					
Final open flow MCE/d CE	munai ope	IN HOW	Bbl/d	*:					
Time of open flow between initial and f	mai open	HOWE	sbl/a						
Static rock Pressurepsig (surfac	e meccura	riou	rs						
NOTE: ON BACK OF THIS FORM PUT THE FOLLOWING: 1). DETAILS OF PERFORATED INTERVALS, FRACTURING OR STIMULATING, PHYSICAL CHANGE, ETC. 2). THE WELL LOG WHICH IS A SYSTEMATIC DETAILED GEOLOGICAL RECORD OF ALL FORMATIONS, INCLUDING COAL ENCOUNTERED BY THE WELLBORE.									
Signed: Lavid S. A	Deri								
By: David Berry									
Date: 5/8/2008									

RECEIVED Office of Oil and Gas

MAR 2 0 2018

WV Department of Environmental Protection

05/13/2011

B803 con't			
No Perforations			
No Stimulation	•		
•			<del></del>
Geologic Record		•	:
Sand and Shale  — Coal Shale and Sand  — Little Lime  — Pencil Cave  _ Big Lime	0 619 628 1236 1249 1276	619 ¼" stream fresh water @ 90' 628 1236 1249 1276 1468	
Sand and Shale  — Benson Sand  Shale and Silistone	1468 4247 4252	4247 4252 Gas show @ 4113' 26M 4528 T.D. (10' KB)	· .*··

05/13/2011

RECEIVED Office of Oil and Gas

MAR 2 0: 2018



Select County: (091) Taylor	Select datatypes:	Check All)	
Enter Permit #: 01089		Production	☑ Plugging
Get Data Reset	✓ Owner/Completion ✓ Pay/Show/Water		Sample  Btm Hole Loc

Contact Info

WV Geological & Economic Survey:

Well: County = 91 Permit = 01089

Report Time: Monday, April 09, 2018 4:15:26 PM

 Location Information:
 View Map

 API
 COUNTY PERMIT TAX\_DISTRICT
 QUAD\_75 QUAD\_15 LAT\_DD
 LON\_DD
 UTME
 UTMN

 4709101089
 Taylor
 1089
 Knottsville
 Thornton
 Thornton
 39.326612
 -79.931399
 592106.2
 4353566.4

There is no Bottom Hole Location data for this well

Owner Information:

API CMP\_DT SUFFIX STATUS SURFACE\_OWNER WELL\_NUM CO\_NUM LEASE LEASE\_NUM MINERAL\_OWN OPERATOR\_AT\_COMPLETION PROP\_VD PROP\_TRGT\_FM TFM\_EST\_PR 4709101089 2/15/2008 Original Loc Completed Bradley Bradley Bradley Bradley Berry Energy, Inc. 4209 Benson

 
 Completion Information:

 IAPI
 CMP\_DT
 SPUD\_DT
 ELEV DATUM
 FIELD DEEPEST\_FM
 DEEP EAT\_FM
 CMP\_MTHD TVD TMD NEW\_FTG G\_BEF G\_AFT O\_BEF O\_AI unknown 4528 4528 26

G\_BEF G\_AFT O\_BEF O\_AFT WATER\_QNTY

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
	Berry Energy, Inc.	2010	152	0	0	0	0	0	0	36	32	21	28	35	0
	Berry Energy, Inc.	2011	289	40	18	48	12	32	33	29	28	10	20	19	0
	Berry Energy, Inc.	2012	182	17	21	11	17	18	26	18	31	20	1	2	0
4709101089	Berry Energy, Inc.	2013	244	0	0	3	39	22	23	27	31	33	23	15	28
4709101089	Berry Energy, Inc.	2014	309	31	29	28	29	77	31	11	6	31	22	14	0
4709101089	Berry Energy, Inc.	2015	269	0	0	29	43	15	32	37	34	31	21	29	0
4709101089	Berry Energy, Inc.	2016	12	0	0	12	0	0	0	0	0	0	0	0	0

Production Oil Information: (Volumes in Bbl) \*\* some operators may have reported NGL under Oil

API	PRODUCING OPERATOR	PRD YEAR	ANN OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4709101089	Berry Energy, Inc.	2010	_ 0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2011	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2012	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2016	0												

Production NGL Information: (Volumes in Bbl) \*\* some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4709101089	Berry Energy, Inc.	2013	_ 0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4709101089	Berry Energy, Inc.	2016	0												77.44

Production Water Information: (Volumes in Gallons)

API PRODUCING\_OPERATOR PRD\_YEAR ANN\_WTR JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DCM
4709101089 Berry Energy, Inc. 2016 0

Stratigraphy Information:

API	SUFFIX	FM	FM QUALITY	DEPTH TOP	DEPTH QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4709101089	Original Loc	unidentified coal			Reasonable		Reasonable		Ground Level
4709101089	Original Loc	Little Lime	Well Record	1236	Reasonable	13	Reasonable	1603	Ground Level
4709101089	Original Loc	Pencil Cave	Well Record	1249	Reasonable	27	Reasonable	1603	Ground Level
4709101089	Original Loc	Big Lime	Well Record	1276	Reasonable	192	Reasonable	1603	Ground Level
4709101089			Well Record	4247	Reasonable	5	Reasonable	1603	Ground Level

There is no Wireline (E-Log) data for this well

There is no Plugging data for this well

There is no Sample data for this well

WW-4A Revised 6-07

1) Date:	January 5, 2018	
2) Operator's	s Well Number	_
B-803		

3) API Well No.: 47 -

01089

### STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS NOTICE OF APPLICATION TO PLUG AND ABANDON A WELL

4) Surface Ow	ner(s) to be served:	5) (a) Coal Operator	•	
(a) Name	Wesley J. Bradley	Name	CoalQuest Development, LLC	
Address	6698 Knottsville Road	Address	100 Tygart Drive	
	Grafton, West Virginia 26354		Grafton, West Virginia 26354	
(b) Name	1	(b) Coal Ow	ner(s) with Declaration	1
Address	3 <del>2</del>	Name		
		Address		
(c) Name		Name	(	
Address		Address		
6) Inspector	Kenneth Greynolds	(c) Coal Les	ssee with Declaration	
Address	613 Broad Run Road	Name		
11441000	Jane Lew, WV 26378	Address		
Telephone	(304) 206-6613			
rerepriorie		2		
However, Take notic accompany Protection the Applic	n you received these documents is that you you are not required to take any action at all the that under Chapter 22-6 of the West Virying documents for a permit to plug and all, with respect to the well at the location detaction, and the plat have been mailed by accumstances) on or before the day of mailing	II.  ginia Code, the undersigned well bandon a well with the Chief of the escribed on the attached Applicat registered or certified mail or de	operator proposes to file or has f the Office of Oil and Gas, West Vi ton and depicted on the attached	Tiled this Notice and Application and reginia Department of Environmental Form WW-6. Copies of this Notice,
	Well Op By: Its: Address	Saca Dept. Committee Property Committee		RECEIVED Gas
	m 1 1	Grafton, West Virginia	a 26354	MAR 2 0:2018
Subscribed and	Telepho	day of _January 2018	Notary Public	WV Department of WV Department of Official Eta vironmental Protection Notary Public State of West Virginia
My Commission			( ) ( )	Thomas Gregory Nair
Section 200 - Section 200 Control of Control				Vebster Avenue, Morgantown, WV 26501 Commission Expires December 22, 2019
Oil and Gas Priv	acy Notice		mmm	· ····································

The Office of Oil and Gas processes your personal information, such as name, address and phone number, as a part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use of your personal information, please contact DEP's Chief Privacy Officer at depprivacyoffier@wv.gov.

04/13/2018

API No.	47-91-01089
Farm Name	Bradley
Well No.	B-803

## INSTRUCTIONS TO COAL OPERATORS OWNERS AND LESSEE

The well operator named on the obverse side of WW-4 (B) is about to abandon the well described in the enclosed materials and will commence the work of plugging and abandoning said well on the date the inspector is notified. Which date shall not be less then five days after the day on which this notice and application so mailed is received, or in due course should be received by the Department of Environmental Protection Office of Oil & Gas.

This notice and application is given to you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not the operator will proceed to plug and fill said well in the manner required by Section 24, Article 6, Chapter 22 of the Code and given in detail on obverse side of this application.

NOTE: If you wish this well to be plugged according to 22-6-24(d) then as per Regulation 35CSR4-13.9 you must complete and return to this office on form OB-16 "Request by Coal Operator, Owner, or Lessee for plugging" prior to the issuance of this plugging permit.

	WAIVER	
The undersigned coal operator X has examined this proposed plugging wo done at this location, provided, the well Virginia Code and the governing regulation	rk order. The undersigned has no operator has complied with a	/ of the coal under this well location no objection to the work proposed to be ll applicable requirements of the West
Date: 1/5/18	By: Greg Nair  Its Power of Attorne	Jug –
		RECEIVED Office of Oil and Gas MAR 2 0: 2018  WV Department of Environmental Protection

WW-9 Rev. 5/08

Page		of	
API Number 47 - 91	_	01089	
Operator's Well No. B-803			

# STATE OF WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS

CONSTRUCTION AND RECLAMATION PLAN AND SITE REGISTRATION APPLICATION FORM GENERAL PERMIT FOR OIL AND GAS PIT WASTE DISCHARGE

Operator Name ICG Tygart Valley, LLC		OP (	Code	
Vatershed Glade Run Quadrangle Thornton (638)		on (638)		
Elevation 1603'	<sub>County_</sub> Taylor	D	<sub>istrict</sub> Knottsville	
Description of anticipated Pit Waste:	N/A			
Will a synthetic liner be used in the pit?	N/A .			
	ation I Injection (UIC Permit N	Number		
Reuse (at A) Off Site Dist	PI Number pposal (Supply form WW	-9 for disposal location)	<u> </u>	)
X Other (Expl	ain Tanks - See attached	etter		
I certify that I understand and on August 1, 2005, by the Office of Oil	agree to the terms and co	ginia Department of Env	AL WATER POLLUTION PER	tand that the
application form and all attachments obtaining the information, I believe t penalties for submitting false informati	ent action.  That I have personally thereto and that, based that the information is true.	examined and am fami on my inquiry of the ne, accurate, and comp	liar with the information submise individuals immediately resplete. I am aware that there are	itted on this ponsible for
Company Official Signature	arles F Duckworth			
Company Official (Typed Name) Cha	I Agent			
Company Official Title Designated	ТАЗЕП			
Subscribed and sworn before me this	9 day of Jan	uary	Notory Public  Official Seal Notary Public State of West Virginia	_
My commission expires December 2.5	-,		Thomas Gregory Nair 9 Webster Avenue, Morgantown, WV 26901 by Commission Expires December 22, 2019 04	/13/2018

Operator's Well No. B-803

	EGEND	
Property Boundary	Diversion Legger 1111111111111111111111111111111111	111111111111111111111111111111111111111
Road = = = = = = = = = =	Spring -	
Existing Fence — X — X — X —	Wet Spot	
Planned Fence / / /	Drain Pipe with size in inches	— @ —→
Stream	Waterway $\longleftrightarrow$	$\rightarrow \hookrightarrow \hookrightarrow$
Open Ditch	Cross Drain 7/1/1/1	
Rock & See See	Artificial Filter Strip XXXXX	XXXXXXXXXXX
North N	Pit: cut walls	
Buildings	Pit: compacted fill walls	
Water wells	Area for Land Application of Pit Wi	iste
Drill site		
1.50	/2 0	
Proposed Revegetation Treatment: Acres Disturbed	Prevegetation pH	
Lime Tons/acre or to correct to pH	6.5	
Fertilizer (10-20-20 or equivalent) 500 lbs/a	acre (500 lbs minimum)	
Hay Bales	1	
MulchTons/ac	ere	
Seed	Mixtures	
Area I	Area II	
Seed Type lbs/acre	Seed Type	lbs/acre
	0 1 10	10
Orchard Grass 12	Orchard Grass	12
Orchard Grass 12 Landino Clover 3	Crchard Grass  Landino Clover	3
Landino Clover 3		
Landino Clover 3	Landino Clover	3
Landino Clover 3	Landino Clover	3
Landino Clover 3 Timothy 10	Landino Clover Timothy	3
Landino Clover 3 Timothy 10	Landino Clover Timothy	3
Landino Clover 3 Timothy 10	Landino Clover Timothy	3
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet. See attached	Landino Clover Timothy ication.	3
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet. See attached	Landino Clover Timothy ication.	3 10
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet. See attached	Landino Clover Timothy ication.	3 10  RECEIVED Office of Oil and Gas
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land appli	Landino Clover Timothy ication.	RECEIVED Office of Oil and Gas
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet. See attached	Landino Clover Timothy ication.	RECEIVED Office of Oil and Gas
Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet.  See attached  Plan Approved by:  Comments:  LECLBIM, LESEED & ME	Landino Clover Timothy  ication.	RECEIVED Office of Oil and Gas
Landino Clover 3  Timothy 10  Attach: Drawing(s) of road, location,pit and proposed area for land application of involved 7.5' topographic sheet. See attached	Landino Clover Timothy ication.	RECEIVED Office of Oil and Gas



## ICG TYGART VALLEY, LLC

100 Tygart Drive, Grafton, West Virginia 26354

January 4, 2018

WV Department of Environmental Protection Office of Oil and Gas  $601 - 57^{th}$  Street, S.E. Charleston, West Virginia 25304

To Whom It May Concern:

As per the WV Department of Environmental Protection, Office of Oil and Gas request, ICG Tygart Valley, LLC, submits the following procedures utilizing pit waste.

Upon submitting a well work application (without a general permit for Oil and Gas Pit Waste Discharge Application), ICG Tygart Valley, LLC, will construct no pits, but instead will use mud tanks to contain all drilling muds.

Once the well is completed, that material (minus the cave material) will be trucked to the next well to be plugged or to DEP impoundment facilities O-2017-06 or to an approved facility that can handle the material.


Sincerely

Charles E. Duckworth Designated Agent

Office of Oil and Gas
MAR 2 0 2018

91-010898

91-010898



LATITUDE: 39° 19′ 35°

LONGITUDE: 79° 55′ 52"

NEARTEST WATERCOURSE: Glade Run

NEAREST TOWN: Knottsville

OPERATOR'S WELL NO. API WELL NO. B-803

47 — 091 — 01089

STATE COUNTY PERMIT

WELL TYPE: OIL GAS X LIQUID INJECTION WASTE DISPOSAL (IF "GAS") PRODUCTION X STORAGE DEEP SHALLOW X

LOCATION: ELEVATION WATERSHED Glade Creek
DISTRICT Knottsville

OUL & GAS COVALTY OWNER COUNTY Taylor
QUADRANGLE Thornton? 1/2'

SURFACE OWNER: Wesley J. Bradley LEASE ACREAGE 83

OIL & GAS ROYALTY OWNER Wesley J. Bradley LEASE ACREAGE 83

PROPOSED WORK: DRILL X. CONVERT DRILL DEEPER REDRILL FRACTURE OR STIMULATE X PLUG OFF OLD FORMATION PERFORATE NEW FORMATION OTHER PHYSICAL CHANGE IN WELL (SPECIFY)

PLUG AND ABANDON X CLEAN OUT AND REPLUG TARGET FORMATION Benson ESTIMATED DEPTH 4209'

WELL OPERATOR ICG Tygart Valley, LLC DESIGNATED DESIGNATED AGENT Charles E. Duckworth ADDRESS 100 Tygart Drive, Grafton, WY 26354

ADDRESS 100 Tygart Drive, Grafton, WY 26354

REVISED BY:	DATE:	API WELL NŒ PO 101089 B-803	
		ICG TYGART	VALLEY, LLC
		DRAWN BY: Jorg A Nais	SCALE: 1' = 2000'
		DIRECTORY: DWG/TYG/TYG #V WV OIL & GAS PERMIT MAPS	DATE ORIGINATED: February, 2017
		DRAWING NO.: 47-091-01089	PLOTTING SOATES



Eastern Operations

100 Tygart Drive, Grafton, WV 26354 Phone: 304-265-9700 Fax: 304-265-2564

04/13/2018

04/13/2018



# West Virginia Department of Environmental Protection Office of Oil and Gas

	WELL LOCATION FO	RM: GPS	
API: 47-091-0108	89 v	VELL NO.: B-803	
	radley		
RESPONSIBLE P	ARTY NAME: ICG Tygart Valle	y, LLC	
COUNTY: Taylo	ARTY NAME: ICG Tygart Valle	TRICT: Knottsville	
QUADRANGLE:	Thornton		
	ER: Wesley J. Bradley		
ROYALTY OWN	ER:Wesley J. Bradley		
UTM GPS NORT	HING: 4353552.029	_	
	NG: 592147.533 G		
preparing a new we above well. The Of the following requing 1. Datum: height a 2. Accuracy 3. Data Consurvey grade Grand	arty named above has chosen to subsell location plat for a plugging permifice of Oil and Gas will not accept Grements:  NAD 1983, Zone: 17 North, Coordibove mean sea level (MSL) – meter y to Datum – 3.05 meters llection Method:  PS: Post Processed Differential  Real-Time Differential  GPS: Post Processed Differential  Real-Time Differential	t or assigned API number on to GPS coordinates that do not me nate Units: meters, Altitude: s.	he
	ize copy of the topography map shareby certify this data is correct to		
	I the information required by law an		
prescribed by the	office of Oil and Gas.		
Suc /	Power of Attorney	January 5, 201	8
Signature	Title	Date	 