

WR-38  
Rev. May 13, 2013  
650461

API # 47-095-00502P

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fred Allen Shreve Operator Well No.: WV 650461

LOCATION: Elevation: 865' Quadrangle: Porter Falls  
District: Ellsworth County: Tyler  
Latitude:        Feet South of        Deg.        Min.        Sec.  
Longitude:        Feet West of        Deg.        Min.        Sec.

Well Type: OIL        GAS XXXX

Company: EQT Production Company Coal Operator NA  
1710 Pennsylvania Avenue or owner         
Charleston, WV 25302       

Agent: Rex C. Ray Coal Lessee NA  
With declaration RECEIVED

Permit Issued Date: 05/03/2012

Office of Oil & Gas

AFFIDAVIT

JUL 16 2013

STATE OF WEST VIRGINIA,  
County of Tyler ss:

WV Department of  
Environmental Protection

Jacob Snider and Jackie Carpenter sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 20th day of May 2013 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2010'	1910'	5 1/2" 1002'	
Cement	1809'	1625'		
Cement	1060'	860'	7" 95'	No records on file
Cement	568'	439'		Amount of pipe in hole
Cement	301'	150'	2" 2013'	Unknown/unavailable
Cement	150'	100'		
Cement	100'	0		
Tagged 1878'; 1620'; 150'; 100'; Found packer 2079' did not go below it. Shot 5 1/2" @ 1724'; 1703'; 1002'; Shot 7" @ 998' twice; 494' twice; 245' twice; 95' free				


Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 29th day of May 2013.

And further deponents saith not.

Jason Meadows

Sworn and subscribe before me this 30th day of May, 2013

My commission expires: December 24, 2017



Gas Inspector

Zelma Meadows  
Notary Public

5.30-13

07/19/2013