

Date: June 12th, 2014

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Weese, Roger & Sandra
LOCATION: Elevation: 782'
District: McElroy
Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Operator Well No: Conaway Heirs, No. 1
Quadrangle: 7.5"
County: Tyler

Well Type: OIL _____ GAS XXXX

Company: Gastar Exploration, LTD
229 W. Main Street Suite 301
Clarksburg, WV 26301

Coal Operator N/A
or owner _____

Agent: Mike McCown

Coal Lessee N/A
With declaration _____

Permit Issued Date: 12-13-2013

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Tyler

ss:

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Michael Goff Oil and Gas Inspector representing the Director, say that said work was commenced on the 2nd day of June 2014 and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1765'	1600'	Rods 1800'	
Cement	Reset 1765'	1600'	2 3/8" 1808'	0
Cement	Reset 1765'	1600'	4 1/2" 1000'	735'
Cement	1550'	1450'		
Cement	1050'	950'	6 1/4" 96'	1619'
	860'	760'		
	400'	285'		
	140'	Surface		

Tag Plug @ 1596' , 940', 285'
Shot 4 1/2" @ 1500', 1000', Free Shot 6 1/4" @ 813', 346', 96', Free

Description of monument: 7 inch casing - 8 ft long with API# welded on it and that the work of plugging and filling said well was completed on the 12th day of June 2014
And further deponents saith not. Jason Meadows

Sworn and subscribe before me this 18 day of June 2014
My commission expires: June 3, 2020

RECEIVED
Office of Oil and Gas
SEP 10 2014
Department of Environmental Protection
09/19/2014



Mildred L. Casto
Notary Public
Michael A. Goff
Inspector