

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PM Furbee
LOCATION: **Elevation:** 966'
District: McElroy
Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Operator Well No.: No. 47-095-0638
Quadrangle: Shirley 7.5
County: Tyler

Well Type: OIL X GAS XXXX


Company: Gastar Exploration, Ltd.
229 W. Main Street
Clarksburg, WV 26301

Coal Operator or owner: NA

Coal Lessee With declaration: NA

Agent: Mike McCown

Permit Issued Date: 12/09/2011



AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Tyler ss:

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 1st day of February 2012 and that the well was plugged and filled in the following manner:


| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|-------|-------|--------------|-----------|
| Cement | 1500' | 1400' | Rods 1832' | 0' |
| Cement | 1202' | 1100' | 2 3/8" 1504' | 328' |
| Cement | 800' | 700' | | |
| Cement | 380' | 0' | 5 1/2" 793' | No Record |
| Cement | | | 7 " 0' | No Record |
| Cement | | | | |
| 6% Gel between each plug | | | | |
| Shot 2 3/8" @ 1828' 1 time; 1536'; 1 time; 1504'; 1 time; Free; Shot 5 1/2" @ 1151"; 1 time; 793'; 1 time; Free; Shot 7" @ 333'; 1 time; 224' 1 time; 106'; 1 time; Not Free; Tagged plug @ 1260'; 694'; 580'; 113'; reset plug 1200' - 1100'; 800' - 700'; Tried to back off and could not back 7" off. | | | | |

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 9th day of February 2012.

And further deponents saith not.

Sworn and subscribe before me this 19 day of March, 2012
 My commission expires: May 24 2016

Jason Madors
Swann Bryant
 Notary Public
3-19-12



03/30/2012