

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PM Furbee Operator Well No.: No. 10
 LOCATION: Elevation: 930' Quadrangle: Shirley 7.5'
 District: McElroy County: Tyler
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL X GAS XXXX

Company: Gastar Exploration, Ltd. Coal Operator NA
229 W. Main Street or owner
Clarksburg, WV 26301

Agent: Mike McCown Coal Lessee NA
With declaration

Permit Issued Date: 12/09/2011

RECEIVED
Office of Oil & Gas

AFFIDAVIT 2012

STATE OF WEST VIRGINIA,
County of Tyler ss:

WV Department of
Environmental Protection


Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 22nd day of February 2012 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1806'	1700'	Rods 1900'	0'
Cement	1170'	1050'	2 3/8" 1920'	0'
Cement	855'	750'		
Cement	570'	465'	5" 101'	No record
Cement	400'	200'		
Cement	200'	0'	7" 0'	1840'
Cement			8" none in well	
Cement			10" none in well	
6% Gel between each plug				
Shot 5 1/2" @ 1120'; 1 time; 803'; 1 time; 517'; 1 time; 389'; 1 time; 297'; 1 time; 199'; 1 time; 101'; Free; Shot 7" @ 84'; Not Free; Could not back off; Tagged plug @ 1045'; 400'; 200';				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 28th day of February 2012.

And further deponents saith not.

Sworn and subscribe before me this 24 day of May, 2012
 My commission expires: May 24, 2016



Susan Bryant
Notary Public
[Signature] S-30-06/08/2012