

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PM Furbee Operator Well No: No. 12
 LOCATION: Elevation: 1034' Quadrangle: Shirley 7.5'
 District: McElroy County: Tyler
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec

Well Type: OIL X GAS XXXX

Company: Gastar Exploration, Ltd. Coal Operator NA
229 W. Main Street or owner
Clarksburg, WV 26301

Coal Lessee NA
 With declaration

Agent: Mike McCown

RECEIVED
 DEPARTMENT OF ENVIRONMENTAL PROTECTION
 MAR 28 2012

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of Tyler ss:


Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 28th day of February 2012 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2070'	1870'	Rods 2080'	0'
Cement	1301'	1200'	2 3/8" 2080'	0'
Cement	800'	690'	5 1/2" 1246'	No Record
Cement	465'	150'		
Cement	150'	90'	7" 16'	1903'
Cement	96'	0'		
6% Gel between each plug				
Shot 5 1/2" @ 1246'; 1 time; Free; Shot 7" @ 1238'; 1 time; 741' 1 time; 415'; 1 time; 309'; 1 times; 217'; 1 time; 111'; 1 time; backed off 7" at 36'; Tagged plug @ 1189'; 150; 96';				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 7th day of March 2012.

And further deponents saith not. Jason Meador
 Sworn and subscribe before me this 19 day of March, 2012
 My commission expires: May 24, 2016

Susan Bryant
 Notary Public
3-19-12



03/30/2012