

WR-38

Date: 02.12.2014

API# 47-095-0656-P

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Spencer, Alva D... Estate Operator Well No: M.W. Spencer No. 14  
LOCATION: Elevation: 1010' Quadrangle: Shirley 7.5"  
District: McElroy County: Tyler  
Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.  
Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL \_\_\_\_\_ GAS XXXX

Company: Gastar Exploration USA Coal Operator \_\_\_\_\_  
229 West Main Street or owner \_\_\_\_\_

Agent: Mike McCown Coal Lessee \_\_\_\_\_  
With declaration **RECEIVED** Office of Oil & Gas

Permit Issued Date: 12/11/2013

AFFIDAVIT

MAR 13 2014

STATE OF WEST VIRGINIA,  
County of Tyler

ss:


WV Department of  
Environmental Protection

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 4<sup>th</sup> day of February, 2014 and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2000'	1860'	Rod 2002'	0
Cement	1076'	926'	2 3/8" 2010	0
Cement	508'	380'	5 1/2" 446'	5 1/2" 530'
Cement	250'	150'	7" 0	7" 1911'
Cement	150'	0		
Shot 5 1/2" @ 446 7" @ 203'; 102' not Free tried to back off; tagged @ 1855' 924' 150'				

Description of monument: 7 inch casing - 8 ft long with API# welded on it and that the work of plugging and filling said well was completed on the 12<sup>th</sup> day of February, 2014.  
And further deponents saith not.

Sworn and subscribe before me this 21<sup>st</sup> day of February, 2014  
My commission expires: March 3, 2020



Mildred L. Casto  
Notary Public  
[Signature] 2-21-14

03/14/2014