

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
SECTION OF OIL AND GAS

REVISED

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: PM Furbee Operator Well No.: No.8  
 LOCATION: Elevation: 1002' Quadrangle: Shirley 7.5'  
 District: McElroy County: Tyler  
 Latitude: Feet South of 00 Deg. 00 Min. 00 Sec.  
 Longitude: Feet West of 00 Deg. 00 Min. 00 Sec.

Well Type: OIL X GAS XXXX

Company: Gastar Exploration, Ltd. Coal Operator NA  
229 W. Main Street or owner  
Clarksburg, WV 26301

Agent: Mike McCown Coal Lessee NA  
 With declaration

Permit Issued Date: 12/09/2011

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Tyler ss:

Jacob Snider and Jackie Carpenter being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Joe Taylor Oil and Gas Inspector representing the Director, say that said work was commenced on the 09 day of January 2012 and that the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	1875'	1770'	Rods 2000'	0'
Cement	1235'	1085'	2 3/8" 1880'	200'
Cement	673'	580'	5 1/2" 397'	563'
Cement	450'	150'	7" 0'	1875'
Cement	113'	0'		
Cement				
Cement				
6% Gel between each plug				
Shot 2 3/8" @ 1880' 1 time; Free; Shot 5 1/2" @ 1183'; 1 time; 619'; 1 time 397'; 1 Time; Free; Shot 7" @ 386'; 1 time; 305' 1 time; 201'; 2 times; 114'; 2 times; Free; Tagged plug @ 1040'; 580'; 113'; reset plug 675' - 570' Tried to back off and could not back 7" off.				

Description of monument: 7 inch casing - 8 feet long with API # welded on it and that the work of plugging and filling said well was completed on the 1st day of February 2012

And further deponents saith not.

Sworn and subscribe before me this 5<sup>th</sup> day of October 2012.  
 My commission expires: June 3, 2020

James Meadows  
Middle of Cas to  
 Notary Public



10/19/2012