

Minimum Error of Closure 1" = 200'

Source of Elevation U.S.C. & G.S. B.M. ELEV. 628'

"I, the undersigned, hereby certify that this map was prepared by me or under my direct supervision and that I am a duly licensed professional engineer in the State of West Virginia. I have read and believe the information shown on this map to be true and correct and shows all the information required by the laws and regulations of the oil and gas section of the State of West Virginia."

- STIMULATION—
- New Location
- Drill Deeper
- Abandonment

11-21-89

X CNG TRANSMISSION

St Marys NC

1.895

0.98W

F.B. 1416 Pg. 15-17

FBI426 Pg. 3-8

MAP SHEET-62-N3W26

Company CONSOLIDATED GAS SUPPLY CORP.

Address CLARKSBURG, WEST VIRGINIA 179

Farm GEORGE T. GALE

Tract Acres 225 Lease No. 76329

Well (Farm) No. 12032 - \*15 Serial No. 12032

Elevation (Spirit Level) 641.74'

Quadrangle ST. MARYS 15/BENS RUN 7.5

County TYLER District UNION 6

Engineer

Engineer's Registration No.

File No. Drawing No.

Date 1-25-77 Scale 1" = 1000'

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION  
CHARLESTON

WELL LOCATION MAP

FILE NO. 47-095-1343-P

Denotes location of well on United States Topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.

— Denotes one inch spaces on border line of original tracing.

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENERGY  
DIVISION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVITE SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: CNG TRANSMISSION CORP. Operator Well No.: 12032

LOCATION: Elevation: 641.74 Quadrangle: BENS RUN  
District: UNION County: TYLER  
Latitude: 10050 Feet South of 39 Deg. 30 Min. 0 Sec.  
Longitude 5180 Feet West of 81 Deg. 5 Min. 0 Sec.

Well Type: OIL X GAS

Company: CNG TRANSMISSIONS

Coal Operator or Owner N/A

Agent: Glenn A. Knepper

Coal Operator or Owner N/A

Inspector: GLEN ROBERTSON  
Permit Issued: 11/21/89

AFFIDAVIT

RECEIVED  
JAN 10 1990

STATE OF WEST VIRGINIA,  
County of HARRISON

ss:

DIVISION OF OIL & GAS  
DEPARTMENT OF ENERGY


and CNG TRANSMISSIONS being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by CNG TRANSMISSIONS, well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6 day of DEC, 1989, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A CEMENT	1371	1271	1380 2"	
Gel 6%	1271	891		
CEMENT	891	791		
Gel 6%	791	490		
CEMENT	490	440	440-7"	463-7'
Gel 6%	440	290		
CEMENT	290	190		
Gel 6%	190	100		
CEMENT	100	0		80-10"

Description of monument: 7" 22ft Long

and that the work of plugging and filling said well was completed on the 7 day of Dec, 1989.

And further deponents saith not.



Subscribed before me this 9th day of January, 1990  
Susie J. Williams  
Notary Public JAN 16 1990