



---

west virginia department of environmental protection

---

Office of Oil and Gas  
601 57<sup>th</sup> Street, S.E.  
Charleston, WV 25304  
(304) 926-0450  
fax: (304) 926-0452

Harold D. Ward, Cabinet Secretary  
[www.dep.wv.gov](http://www.dep.wv.gov)

Tuesday, September 20, 2022  
WELL WORK PERMIT  
Horizontal 6A / New Drill

ANTERO RESOURCES CORPORATION  
1615 WYNKOOP STREET  
DENVER, CO 80202

Re: Permit approval for MAMBA UNIT 2H  
47-095-02821-00-00

This well work permit is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to any additional specific conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas Inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days of completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

Per 35 CSR 4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926- 0450.

A handwritten signature in blue ink, appearing to read 'J. A. Martin', is written over a printed name and title.

James A. Martin  
Chief

Operator's Well Number: MAMBA UNIT 2H  
Farm Name: DENNIS & CLISTA HEINTZM  
U.S. WELL NUMBER: 47-095-02821-00-00  
Horizontal 6A New Drill  
Date Issued: 9/20/2022

Promoting a healthy environment.

09/23/2022

# PERMIT CONDITIONS

West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

## CONDITIONS

---

1. This proposed activity may require permit coverage from the United States Army Corps of Engineers (USACE). Through this permit, you are hereby being advised to consult with USACE regarding this proposed activity.
2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than one hundred (100) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.
3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the moisture content of the fill material shall be within limits as determined by the Standard Proctor Density test of the actual soils used in specific engineered fill, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort, to achieve 95 % compaction of the optimum density. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.
4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.
5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations*, 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.
6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.
7. 24 hours prior to the initiation of the completion process the operator shall notify the Chief or his designee.
8. During the completion process the operator shall monitor annular pressures and report any anomaly noticed to the chief or his designee immediately.
9. If any explosion or other accident causing loss of life or serious personal injury occurs in or about a well or well work on a well, the well operator or its contractor shall give notice, stating the particulars of the explosion or accident, to the oil and gas inspector and the Chief, within 24 hours of said accident.
10. During the casing and cementing process, in the event cement does not return to the surface, the oil and gas inspector shall be notified within 24 hours.
11. The operator shall provide to the Office of Oil and Gas the dates of each of the following within 30 days of their occurrence: completion of construction of the well pad, commencement of drilling, cessation of drilling, completion of any other permitted well work, and completion of the well. Such notice shall be provided by sending an email to DEPOOGNotify@wv.gov.

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
WELL WORK PERMIT APPLICATION

1) Well Operator: Antero Resources Corporation 494507062 095 - Tyler Ellsworth Porter Falls 7.5'  
Operator ID County District Quadrangle

2) Operator's Well Number: Mamba Unit 2H Well Pad Name: Heintzman Pad

3) Farm Name/Surface Owner: Dennis & Clista Heintzman Public Road Access: Elk Fork Rd

4) Elevation, current ground: 1215' Elevation, proposed post-construction: ~1193'

5) Well Type (a) Gas  Oil  Underground Storage

Other \_\_\_\_\_

(b) If Gas Shallow  Deep

Horizontal

6) Existing Pad: Yes or No Yes

7) Proposed Target Formation(s), Depth(s), Anticipated Thickness and Expected Pressure(s):  
Marcellus Shale: 7100' TVD, Anticipated Thickness- 55 feet, Associated Pressure- 2850#

8) Proposed Total Vertical Depth: 7100' TVD

RECEIVED  
Office of Oil and Gas

9) Formation at Total Vertical Depth: Marcellus

AUG 29 2022

10) Proposed Total Measured Depth: 24200' MD

WV Department of  
Environmental Protection

11) Proposed Horizontal Leg Length: 15002.7'

12) Approximate Fresh Water Strata Depths: 420', 475'

13) Method to Determine Fresh Water Depths: 47-095-00269 Offset well records. Depths have been adjusted according to surface elevations.

14) Approximate Saltwater Depths: 1420'

15) Approximate Coal Seam Depths: 58'

16) Approximate Depth to Possible Void (coal mine, karst, other): None Anticipated

17) Does Proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes \_\_\_\_\_ No

(a) If Yes, provide Mine Info: Name: \_\_\_\_\_  
Depth: \_\_\_\_\_  
Seam: \_\_\_\_\_  
Owner: \_\_\_\_\_

*Steve May*  
*8/26/22*

WW-6B  
(04/15)

4709502821  
API NO. 47-095  
OPERATOR WELL NO. Mamba Unit 2H  
Well Pad Name: Heintzman Pad

18)

**CASING AND TUBING PROGRAM**

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill-up (Cu. Ft.)/CTS
Conductor	20"	New	H-40	94#	90	90	CTS, 86 Cu. Ft.
Fresh Water	13-3/8"	New	J-55	54.5#	525	525	CTS, 313 Cu. Ft.
Coal	9-5/8"	New	J-55	36#	2500	2500	CTS, 1018 Cu. Ft.
Intermediate							
Production	5-1/2"	New	P-110	23#	24200	24200	5181 Cu. Ft
Tubing	2-3/8"	New	N-80	4.7#			
Liners							

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20"	24"	0.438"	1530	50	Class A	~1.18
Fresh Water	13-3/8"	17-1/2"	0.38"	2730	1000	Class A	~1.18
Coal	9-5/8"	12-1/4"	0.352"	3520	1500	Class A	~1.18
Intermediate							
Production	5-1/2"	8-3/4" & 8-1/2"	0.415"	12,630	2500	Lead-H/POZ & Tail - H	H/POZ-1.44 & H-1.8
Tubing	2-3/8"	4.778"	0.19"	11,200			
Liners							

RECEIVED  
Office of Oil and Gas

AUG 29 2022

WV Department of  
Environmental Protection

**PACKERS**

Kind:	N/A			
Sizes:	N/A			
Depths Set:	N/A			

*Steve May*  
8/26/22

WW-6B  
(10/14)

4709502821  
API NO. 47-095 -  
OPERATOR WELL NO. Mamba Unit 2H  
Well Pad Name: Heintzman Pad

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Drill a new horizontal shallow well into the Marcellus Shale.

\*Antero will be air drilling the fresh water string which makes it difficult to determine when fresh water is encountered. Therefore, we have built in a buffer for the casing setting depth which helps to ensure that all fresh water zones are covered.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Antero plans to pump Slickwater into the Marcellus Shale formation in order to ready the well for production. The fluid will be comprised of approximately 99 percent water and sand, with less than 1 percent special-purpose additives as shown in the attached "List of Anticipated Additives Used for Fracturing or Stimulating Well."

Anticipated Max Pressure - 9300 lbs  
Anticipated Max Rate - 80 bpm

21) Total Area to be disturbed, including roads, stockpile area, pits, etc., (acres): 56.03 acres

22) Area to be disturbed for well pad only, less access road (acres): 7.82 acres

23) Describe centralizer placement for each casing string:

Conductor: no centralizers  
Surface Casing: one centralizer 10' above the float shoe, one on the insert float collar and one every 4th joint spaced up the hole to surface.  
Intermediate Casing: one centralizer above float joint, one centralizer 5' above float collar and one every 4th collar to surface.  
Production Casing: one centralizer at shoe joint and one every 3 joints to top of cement in intermediate casing.

RECEIVED  
Office of Oil and Gas

AUG 29 2022

24) Describe all cement additives associated with each cement type:

Conductor: no additives, Class A cement.  
Surface: Class A cement with 2-3% calcium chloride and 1/4 lb of flake  
Intermediate: Class A cement with 1/4 lb of flake, 5 gallons of clay treat  
Production: Lead cement- 50/50 Class H/Poz + 1.5% salt + 1% C-45 + 0.5% C-16a + 0.2% C-12 + 0.45% C-20 + 0.05% C-51  
Production: Tail cement- Class H + 45 PPS Calcium Carbonate + 1.0% FL-160 + 0.2% ACGB-47 + 0.05% ACSA-51 + 0.2% ACR-20

NY Department of  
Environmental Conservation

25) Proposed borehole conditioning procedures:

Conductor: blowhole clean with air, run casing, 10 bbls fresh water.  
Surface: blowhole clean with air, trip to conductor shoe, trip to bottom, blowhole clean with air, trip out, run casing, circulate pipe capacity + 40 bbls fresh water followed by 25 bbls bentonite mud, 10 bbls fresh water spacer.  
Intermediate: blowhole clean with air, trip to surface casing shoe, trip to bottom, blowhole clean with air, trip out, run casing, circulate 40 bbls brine water followed by 10 bbls fresh water and 25 bbls bentonite mud, pump 10 bbls fresh water.  
Production: circulate with 14 lb/gal NaCl mud, trip to middle of lateral, circulate, pump high viscosity sweep, trip to base of curve, pump high viscosity sweep, trip to top of curve, trip to bottom, circulate, pump high viscosity sweep, trip out, run casing, circulate 10 bbls fresh water, pump 48 bbls barite pill, pump 10 bbls fresh water followed by 48 bbls mud flush and 10 bbls water.

\*Note: Attach additional sheets as needed.

Page 3 of 3  
09/23/2022  
Steve May  
8/26/22

**LEGEND**

- Proposed gas well
- ☼ Existing Well, as noted
- ☼ Digitized Well, as noted



The orientation of this survey is Grid North, and its coordinate base is the West Virginia Coordinate System of 1927, North Zone

Wetzel County  
Tyler County

47-095  
-00685

500' Buffer

Mamba Unit 2H

RECEIVED  
Office of Oil and Gas

AUG 16 2022

WV Department of  
Environmental Protection




Bridgeport Office  
Phone: (304) 848-5035  
Fax: (304) 848-5037

172 Thompson Drive  
Bridgeport, WV 26330

PARTY CHIEF: C. Lynch	DRAWN BY: J. Smith
RESEARCH: J. Miller	PREPARED: July 29, 2022
SURVEYED: Dec. 2016	PROJECT NO: 99-54-E-19
FIELD CREW: C.L., K.M.	DRAWING NO: Mamba 2H Short AOR

Sheet 1 of 1



Scale: 1 inch = 2000 feet

09/23/2022

UWI (APINum)	Well Name	Well Number	Operator	Historical Operator	TD	Perforated Interval (shallowest, deepest)	Perforated Formation(s)	Producible Formation(s) not perf'd
47095006850000	KIMBLE BRADY	1	EQT PRODUCTION CO	CARTER-JONES LUMBER	2,695	2391 - 2581	Berea	Weir, Benson, Alexander

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

4709502821

WW-9  
(4/16)

API Number 47 - 095 - \_\_\_\_\_  
Operator's Well No. Mamba Unit 2H

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

RECEIVED  
Office of Oil and Gas

AUG 29 2022

FLUIDS/ CUTTINGS DISPOSAL & RECLAMATION PLAN

Operator Name Antero Resources Corporation OP Code 494507062 WV Department of  
Watershed (HUC 10) Outlet Middle Island Creek Quadrangle Porter Falls 7.5' Environmental Protection

Do you anticipate using more than 5,000 bbls of water to complete the proposed well work? Yes  No

Will a pit be used? Yes  No

If so, please describe anticipated pit waste: No pit will be used at this site (Drilling and Flowback Fluids will be stored in tanks. Cuttings will be lanked and hauled off site.)

Will a synthetic liner be used in the pit? Yes  No  If so, what ml.? N/A

Proposed Disposal Method For Treated Pit Wastes:

- Land Application
- Underground Injection ( UIC Permit Number                      \*UIC Permit # will be provided on Form WR-34 )
- Reuse (at API Number                      Future permitted well locations when applicable. API# will be provided on Form WR-34 )
- Off Site Disposal (Supply form WW-9 for disposal location) (Meadowfill Landfill Permit #SWF-1032-98)
- Other (Explain                      Northwestern Landfill Permit #SWF-1025/ WV0109410  
Wetzel Co Landfill Permit #SWF-1021)

Will closed loop system be used? If so, describe: Yes, fluids stored in tanks, cuttings removed offsite and taken to landfill.

Drilling medium anticipated for this well (vertical and horizontal)? Air, freshwater, oil based, etc. Surface - Air/Freshwater, Intermediate - Dust/Sluff Foam, Production - Water Based Mud

-If oil based, what type? Synthetic, petroleum, etc. Synthetic

Additives to be used in drilling medium? Please See Attachment

Drill cuttings disposal method? Leave in pit, landfill, removed offsite, etc. Drill cuttings stored in tanks, removed offsite and taken to landfill.

-If left in pit and plan to solidify what medium will be used? (cement, lime, sawdust) N/A

-Landfill or offsite name/permit number? Meadowfill Landfill (Permit #SWF-1032-98), Northwestern Landfill (Permit # SWF-1025/WV0109410)  
Wetzel Co Landfill (Permit #SWF-1021)

Permittee shall provide written notice to the Office of Oil and Gas of any load of drill cuttings or associated waste rejected at any West Virginia solid waste facility. The notice shall be provided within 24 hours of rejection and the permittee shall also disclose where it was properly disposed.

I certify that I understand and agree to the terms and conditions of the GENERAL WATER POLLUTION PERMIT issued on August 1, 2005, by the Office of Oil and Gas of the West Virginia Department of Environmental Protection. I understand that the provisions of the permit are enforceable by law. Violations of any term or condition of the general permit and/or other applicable law or regulation can lead to enforcement action.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments thereto and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment.

Company Official Signature Gretchen Kohler  
Company Official (Typed Name) Gretchen Kohler  
Company Official Title Director of Environmental & Regulatory Compliance

Subscribed and sworn before me this 12 day of Aug, 2022

Diane Blair

Notary Public  
DIANE BLAIR  
NOTARY PUBLIC  
STATE OF COLORADO  
NOTARY ID 19994011871  
MY COMMISSION EXPIRES 27-Apr-2024

My commission expires 27 Apr 2024

09/23/2022  
Steve M... 8/26/22



**Antero Resources Corporation**

Proposed Revegetation Treatment: Acres Disturbed 56.03 acres Prevegetation pH \_\_\_\_\_

Lime 2-4 Tons/acre or to correct to pH 6.5

Fertilizer type Hay or straw or Wood Fiber (will be used where needed)

Fertilizer amount 500 lbs/acre

Mulch 2-3 Tons/acre

Access Road "D" (16.60 acres) + Well Pad (7.82 acres) + Excess/Topsoil Material Stockpiles (31.61 acres) = 56.03 Acres

RECEIVED  
Office of Oil and Gas  
AUG 29 2022  
WV Department of  
Environmental Protection

Seed Mixtures

**Temporary**

**Permanent**

Seed Type	lbs/acre
Annual Ryegrass	40
Field Bromegrass	40

Seed Type	lbs/acre
Crownvetch	10-15
Tall Fescue	30

See attached Table IV-3 for additional seed type (Heintzman Pad Design)

See attached Table IV-4A for additional seed type (Heintzman Pad Design)

\*or type of grass seed requested by surface owner

\*or type of grass seed requested by surface owner

**Attach:**

Maps(s) of road, location, pit and proposed area for land application (unless engineered plans including this info have been provided). If water from the pit will be land applied, include dimensions (L x W x D) of the pit, and dimensions (L x W), and area in acreage, of the land application area.

Photocopied section of involved 7.5' topographic sheet.

Plan Approved by: Steve Mfloy

Comments: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Title: Oil & Gas Inspector Date: 8/26/22

Field Reviewed? ( ) Yes ( / ) No

Steve Mfloy  
8/26/22

09/23/2022

***Form WW-9 Additives Attachment*****SURFACE INTERVAL**

1. Fresh Water
2. Soap –Foamer AC
3. Air

**INTERMEDIATE INTERVAL*****STIFF FOAM RECIPE:***

- 1) 1 ppb Soda Ash / Sodium Carbonate-Alkalinity Control Agent
- 2) 1 ppb Conqor 404 ( 11.76 ppg) / Corrosion Inhibitor
- 3) 4 ppb KLA-Gard ( 9.17 ppg) / Amine Acid Complex-Shale Stabilizer
- 4) 1ppb Mil Pac R / Sodium Carboxymethylcellulose-Filtration Control Agent
- 5) 12 ppb KCL / Potassium Chloride-inorganic Salt
- 6) Fresh Water 80 bbls
- 7) Air

**PRODUCTION INTERVAL**

1. Alpha 1655  
Salt Inhibitor
2. Mil-Carb  
Calcium Carbonate
3. Cottonseed Hulls  
Cellulose-Cottonseed Pellets – LCM
4. Mil-Seal  
Vegetable, Cotton & Cellulose-Based Fiber Blend – LCM
5. Clay-Trol  
Amine Acid Complex – Shale Stabilizer
6. Xan-Plex  
Viscosifier For Water Based Muds
7. Mil-Pac (All Grades)  
Sodium Carboxymethylcellulose – Filtration Control Agent
8. New Drill  
Anionic Polyacrylamide Copolymer Emulsion – Shale Stabilizer
9. Caustic Soda  
Sodium Hydroxide – Alkalinity Control
10. Mil-Lime  
Calcium Hydroxide – Lime
11. LD-9  
Polyether Polyol – Drilling Fluid Defoamer
12. Mil Mica  
Hydro-Biotite Mica – LCM

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

4709502821

13. Escaid 110  
Drilling Fluid Solvent – Aliphatic Hydrocarbon
14. Ligco  
Highly Oxidized Leonardite – Filtration Control Agent
15. Super Sweep  
Polypropylene – Hole Cleaning Agent
16. Sulfatrol K  
Drilling Fluid Additive – Sulfonated Asphalt Residuum
17. Sodium Chloride, Anhydrous  
Inorganic Salt
18. D-D  
Drilling Detergent – Surfactant
19. Terra-Rate  
Organic Surfactant Blend
20. W.O. Defoam  
Alcohol-Based Defoamer
21. Perma-Lose HT  
Fluid Loss Reducer For Water-Based Muds
22. Xan-Plex D  
Polysaccharide Polymer – Drilling Fluid Viscosifier
23. Walnut Shells  
Ground Cellulosic Material – Ground Walnut Shells – LCM
24. Mil-Graphite  
Natural Graphite – LCM
25. Mil Bar  
Barite – Weighting Agent
26. X-Cide 102  
Biocide
27. Soda Ash  
Sodium Carbonate – Alkalinity Control Agent
28. Clay Trol  
Amine Acid complex – Shale Stabilizer
29. Sulfatrol  
Sulfonated Asphalt – Shale Control Additive
30. Xanvis  
Viscosifier For Water-Based Muds
31. Milstarch  
Starch – Fluid Loss Reducer For Water Based Muds
32. Mil-Lube  
Drilling Fluid Lubricant

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

09/23/2022



**911 Address**  
**2176 Elk Fork Road**  
**Middlebourne, WV 26149**

## Well Site Safety Plan

### Antero Resources

**Well Name: Heintzman Unit 5H, Leap Unit 1H-2H, Mamba Unit 1H-2H,  
 Nomad Unit 1H-2H**

**Pad Location: HEINTZMAN PAD**

Tyler County/Ellsworth District

RECEIVED  
 Office of Oil and Gas

AUG 29 2022

WV Department of  
 Environmental Protection

#### GPS Coordinates:

**Entrance** - Lat 39.539881' / Long -80.887809' (NAD83)

**Pad Center** - Lat 39.543135' / Long -80.855725 (NAD83)


#### Driving Directions:

From the U.S Post Office in Middlebourne, head east on Dodd St toward Fair St for 364 ft. Turn left onto WV-18 N/Main Street for 4.2 miles. Turn right onto WV-180 N for 0.5 miles, lease road will be on your right.

#### Alternate Route:

From the U.S Post Office in Sistersville, head southeast on Wells Street toward Elizabeth Street for 72 ft. Turn left at the 1st cross street onto Elizabeth Street. Elizabeth Street turns right & becomes WV-2 S/Chelsea Street for 1 mile. Continue straight onto WV-18S for 6.9 miles. Turn left onto WV-180 N for 0.5 miles, lease road will be on your right.

**EMERGENCY (24 HOUR) CONTACT 1-800-878-1373**



Access Road

Heintzman Pad

Elk Fork Road

E L L S

**Antero Resources Corporation**  
 Appalachian Basin  
 Heintzman Pad  
 Tyler County  
 Quadrangle: Porter Falls  
 Watershed: Outlet Middle Island Creek  
 District: Ellsworth  
 Date: 5-14-2019

Office of Oil and Gas  
 AUG 16 2022  
 WV Department of  
 Environmental Protection




**Antero Resources  
Well No. Mamba 2H**

Antero Resources Corporation



I, the undersigned, hereby certify that this plat is correct to the best of my knowledge and belief and shows all the information required by law and the rules issued and prescribed by the Department of Environmental Protection.



*Bradley D. Miller*  
Bradley D. Miller, P.S. 2167



**TOP HOLE LATITUDE 39 - 35 - 00**  
**BTM HOLE LATITUDE 39 - 37 - 30**

**Notes**  
West Virginia Coordinate System of 1927, North Zone  
based upon Differential GPS Measurements  
Well No. Mamba Unit 2H Top Hole coordinates are  
N: 382,729.52' Latitude: 39°32'34.42"  
E: 1,617,666.98' Longitude: 80°51'20.81"  
Bottom Hole coordinates are  
N: 398,516.47' Latitude: 39°35'09.79"  
E: 1,613,292.51' Longitude: 80°52'19.72"  
UTM Zone 17, NAD 1983  
Top Hole Coordinates Bottom Hole Coordinates  
N: 4,377,043.715m N: 4,381,831.037m  
E: 512,407.241m E: 510,994.389m  
Plat orientation and corner and well references are based upon the grid north meridian.  
Well location references are based upon the magnetic meridian.

**Notes:**  
Well No. Mamba Unit 2H  
UTM Zone 17, NAD 1927  
Top Hole Coordinates  
N: 14,359,636.35'  
E: 1,681,074.83'  
Point of Entry Coordinates  
N: 14,361,173.18'  
E: 1,681,353.34'  
Bottom Hole Coordinates  
N: 14,375,342.73'  
E: 1,676,439.00'



Note: 0 water wells or springs were found within 2000' of proposed well. No occupied dwellings or buildings 2,500 square feet or larger used to house or shelter dairy cattle or poultry husbandry are located within 625' of the center of the well pad.

**Legend**

- Proposed gas well
- Monument, as noted
- Existing Well, as noted
- Digitized Well, as noted
- Creek or Drain
- Road
- Surface boundary (approx.)
- Interior surface tracts (approx.)
- County Line

	Bearing	Dist.
L1	S 35°21' E	2,409.5'
L2	S 05°23' W	2,292.7'
L3	S 27°29' W	881.6'
L4	N 02°46' W	406.5'
L5	N 11°14' E	1,562.4'

FILE NO: 99-54-E-19  
DRAWING NO: Mamba Unit 2H Well Plat  
SCALE: 1" = 2000'  
MINIMUM DEGREE OF ACCURACY: Submeter  
PROVEN SOURCE OF ELEVATION: WVDOT, Harrisville, WV

**STATE OF WEST VIRGINIA**  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
**OIL AND GAS DIVISION**

DATE: August 12 2022  
OPERATOR'S WELL NO. Mamba Unit 2H  
API WELL NO  
47 - 095 - 02521  
STATE COUNTY PERMIT


WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
(IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW

LOCATION: ELEVATION: Existing 1215' Proposed 1193' WATERSHED: Outlet Middle Island Creek TH:Porter Falls 164.28125; BH:Paden City 20.67; 33.25; 20.67; 33.25; 3.36; 15; 98.5; 3.36; 15; 98.5;  
DISTRICT: Ellsworth Jeffrey Seckman; Beverly Kay Campbell; James D. VanCamp, et ux; William G. Baker; Antero Minerals, LLC; COUNTY: Tyler 09/23/2022  
SURFACE OWNER: Dennis & Clista Heintzman Gary A. Midcap, et ux (3); Lee Morgan; James D. VanCamp; ACREAGE: 417.6 30.9625; 40; 48.796; 10.02; 33.48125;  
ROYALTY OWNER: BRC Appalachian Minerals I, LLC (2); TMP Properties, LLC; Judy P. Meyers; LEASE NO: ACREAGE: 42.46875; 99.4438  
PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY) \_\_\_\_\_ 7,100' TVD  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus Shale ESTIMATED DEPTH: 24,200' MD

WELL OPERATOR: Antero Resources Corporation DESIGNATED AGENT: Dianna Stamper - CT Corporation System  
ADDRESS: 1615 Wynkoop Street ADDRESS: 5400 D Big Tyler Road  
Denver, CO 80202 Charleston, WV 25313

**Antero Resources  
Well No. Mamba 2H**

Antero Resources Corporation



ID	TM/Par	Owner	Bk/Pg	Acres
1	6-36	Dennis & Clista Heintzman	297/640	417.60
2	10-4	Stefan L. & Alberta B. Smolski	356/467	56.08
3	6-49	Dennis & Clista A. Heintzman	297/637	45.00
4	6-30.1	Larry M. & Amy B. Adams	369/344	150.33
5	6-30	Larry G. Rice	333/682	64.61
6	6-27	Ronnie L. VanCamp, et al	568/32	69.88
7	6-27.3	Laura A. Richeson	365/34	5.14
8	6-27.4	Joseph M. & Tammy A. Rice	634/778	3.79
9	6-21.2	Richard E. Leek	OR147/27	3.15
10	6-27.1	Larry G. Rice	333/682	0.81
11	6-27.5	David W. VanCamp	555/14	2.56
12	6-21.3	Richard E. Leek	OR147/27	0.28
13	6-21.1	Richard E. Leek	391/533	2.74
14	6-29	Richard Leek	402/216	1.00
15	6-28	David Wayne & Virginia VanCamp	395/557	2.00
16	6-47.1	Donna Faulk	408/113	1.00
17	6-27.2	David Wayne & Virginia VanCamp	395/557	1.0
18	6-47	Jeffrey Seckman	545/70	18.99
19	6-11	Jeffrey A. & Joann E. Seckman	343/153-A	68.72
20	6-20.2	Hiram Groves	98/195	7.50
21	6-20.1	Jeffrey Seckman	545/70	2.52
22	6-19	Linda J. & Jack E. Mason	OR101/678	10.00
23	6-20	Jeffrey Seckman	545/70	36.15
24	6-8	Matthew T. Ebert	361/219	98.50
25	6-7	Gary A. & Penny K. Midcap	301/265	30.90
26	3-26.1	Gary A. & Penny K. Midcap	301/265	40.00
27	3-34	Charlotte Terry, et al	WB76/367	57.19
28	3-27	Herbert & Phyllis Glendenning	349/827	33.25
29	3-25.1	Gary A. & Penny K. Midcap	304/230	33.48
30	3-25	Gary A. & Penny K. Midcap	301/265	42.47
31	3-28	Rhoda & Lawrence Morgan Est	317/413	61.33
32	3-19	Gary A. & Penny K. Midcap	301/265	20.94
33	3-9	Steven D. & Brenda M. Higgins	313/623	163.34
34	3-10	Steven D. & Brenda M. Higgins	313/623	79.75
35	3-10.1	Steven D. & Brenda M. Higgins	313/623	10.16
36	1-11	Daniel A. Witschey	541/326	122.81
37	16-64	Richard Todd Kay	420/650	29.00
38	1-16	Daniel A. & Amy J. Witschey	602/421	20.00

Leases	
A	BRC Appalachian Minerals I, LLC
B	Rose Enterprises, LLC
C	Dennis R. & Clista A. Heintzman
D	TMP Properties, LLC
E	Judy P. Meyers
F	Laura A. Richeson
G	Bobby J. Dennis
H	David W. VanCamp, et ux
I	BRC Appalachian Minerals I, LLC
J	Antero Mineral, LLC
K	Martha Elizabeth Matthews
L	David Wayne VanCamp, et ux
M	Jeffrey Seckman
N	Jon Keith Irvin
O	James D. VanCamp
P	Linda J. & Jack E. Mason
Q	David E. Bowyer
R	Christina L. Ebert
S	Gary A. Midcap, et ux
T	Gary A. Midcap, et ux
U	Lee Morgan
V	BRC Appalachian Minerals I, LLC
W	James D. VanCamp, et ux
X	MAP2012-OK
Y	William G. Baker
Z	Gary A. Midcap, et ux
AA	Mary F. Mutscheiknaus
AB	Steven D. Higgins, et ux
AC	Beverly Kay Campbell
AD	Cider Run Mineral Holdings, LLC
AE	Don A. Stertzbach, et ux
AF	Michael Stillwagner

FILE NO: 99-54-E-19  
DRAWING NO: Mamba Unit 2H Well Plat  
SCALE: 1" = 2000'  
MINIMUM DEGREE OF ACCURACY: Submeter  
PROVEN SOURCE OF ELEVATION: WVDOT, Harrisville, WV


**STATE OF WEST VIRGINIA**  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
**OIL AND GAS DIVISION**



DATE: August 12 2022  
OPERATOR'S WELL NO. Mamba Unit 2H  
API WELL NO  
47 - 095 - 02221  
STATE COUNTY PERMIT

WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
(IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW  
LOCATION: ELEVATION: Existing 1215' Proposed 1193' WATERSHED: Middle Island Creek Outlet  
DISTRICT: Ellsworth TH:Porter Falls  
SURFACE OWNER: Dennis & Clista Heintzman COUNTY: Tyler 09/23/2022  
ROYALTY OWNER: BRC Appalachian Minerals I, LLC (2); TMP Properties, LLC; Judy P. Meyers; LEASE NO: ACREAGE: 417.6 30.9625; 40; 48.796; 10.02; 33.48125; 42.46875;99.4438  
PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY) 7.100' TVD  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus Shale ESTIMATED DEPTH: 24,200' MD

WELL OPERATOR: Antero Resources Corporation DESIGNATED AGENT: Dianna Stamper - CT Corporation System  
ADDRESS: 1615 Wynkoop Street ADDRESS: 5400 D Big Tyler Road  
Denver, CO 80202 Charleston, WV 25313



**Antero Resources**  
**Well No. Mamba 2H**  
 Antero Resources Corporation



I, the undersigned, hereby certify that this plat is correct to the best of my knowledge and belief and shows all the information required by law and the rules issued and prescribed by the Department of Environmental Protection.



*Bradley D. Miller*  
 Bradley D. Miller, P.S. 2167




**TOP HOLE LATITUDE 39 - 35 - 00**  
**BTM HOLE LATITUDE 39 - 37 - 30**

**Notes**  
 West Virginia Coordinate System of 1927, North Zone based upon Differential GPS Measurements.  
 Well No. Mamba Unit 2H Top Hole coordinates are  
 N: 382,729.52' Latitude: 39°32'34.42"  
 E: 1,617,666.98' Longitude: 80°51'20.81"  
 Bottom Hole coordinates are  
 N: 398,516.47' Latitude: 39°35'09.79"  
 E: 1,613,292.51' Longitude: 80°52'19.72"  
 UTM Zone 17, NAD 1983  
 Top Hole Coordinates Bottom Hole Coordinates  
 N: 4,377,043.715m N: 4,381,831.037m  
 E: 512,407.241m E: 510,994.389m  
 Plat orientation and corner and well references are based upon the grid north meridian.  
 Well location references are based upon the magnetic meridian.

**Notes:**  
 Well No. Mamba Unit 2H UTM Zone 17, NAD 1927  
 Top Hole Coordinates  
 N: 14,359,636.35'  
 E: 1,681,074.83'  
 Point of Entry Coordinates  
 N: 14,361,173.18'  
 E: 1,681,353.34'  
 Bottom Hole Coordinates  
 N: 14,375,342.73'  
 E: 1,676,439.00'



Note: 0 water wells or springs were found within 2000' of proposed well. No occupied dwellings or buildings 2,500 square feet or larger used to house or shelter dairy cattle or poultry husbandry are located within 625' of the center of the well pad.



- Legend**
- Proposed gas well
  - ⊗ Monument, as noted
  - ☼ Existing Well, as noted
  - ☼ Digitized Well, as noted
  - Creek or Drain
  - Road
  - Surface boundary (approx.)
  - Interior surface tracts (approx.)
  - County Line

	Bearing	Dist.
L1	S 35°21' E	2,409.5'
L2	S 05°23' W	2,292.7'
L3	S 27°29' W	881.6'
L4	N 02°46' W	406.5'
L5	N 11°14' E	1,562.4'

FILE NO: 99-54-E-19  
 DRAWING NO: Mamba Unit 2H Well Plat  
 SCALE: 1" = 2000'  
 MINIMUM DEGREE OF ACCURACY: Submeter  
 PROVEN SOURCE OF ELEVATION: WVDOT, Harrisville, WV

**STATE OF WEST VIRGINIA**  
 DEPARTMENT OF ENVIRONMENTAL PROTECTION  
**OIL AND GAS DIVISION**

DATE: August 12 2022  
 OPERATOR'S WELL NO. Mamba Unit 2H  
 API WELL NO  
 47 - 095 - 02821  
 STATE COUNTY PERMIT

WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
 (IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW


LOCATION: ELEVATION: Proposed 1193' Existing 1215' WATERSHED: Outlet Middle Island Creek TH:Porter Falls BH:Paden City 164,281.25; 28,873,233.55; 3,3615,98.5;  
 DISTRICT: Ellsworth Jeffrey Seckman; Beverly Kay Campbell; James D. VanCamp, et ux; William G. Baker; Antero Minerals, LLC; COUNTY: Tyler 09/23/2022  
 SURFACE OWNER: Dennis & Clista Heintzman Gary A. Midcap, et ux (3); Lee Morgan; James D. VanCamp; ACREAGE: 417.6 30,9625; 40; 48,796;  
 ROYALTY OWNER: BRC Appalachian Minerals I, LLC (2); TMP Properties, LLC; Judy P. Meyers; LEASE NO: ACREAGE: 42,46875;99.4438  
 PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY) \_\_\_\_\_ 7,100' TVD  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus Shale ESTIMATED DEPTH: 24,200' MD

WELL OPERATOR: Antero Resources Corporation DESIGNATED AGENT: Dianna Stamper - CT Corporation System  
 ADDRESS: 1615 Wynkoop Street ADDRESS: 5400 D Big Tyler Road  
 Denver, CO 80202 Charleston, WV 25313



**Antero Resources  
Well No. Mamba 2H**

Antero Resources Corporation



ID	TM/Par	Owner	Bk/Pg	Acres
1	6-36	Dennis & Clista Heintzman	297/640	417.60
2	10-4	Stefan L. & Alberta B. Smolski	356/467	56.08
3	6-49	Dennis & Clista A. Heintzman	297/637	45.00
4	6-30.1	Larry M. & Amy B. Adams	369/344	150.33
5	6-30	Larry G. Rice	333/682	64.61
6	6-27	Ronnie L. VanCamp, et al	568/32	69.88
7	6-27.3	Laura A. Richeson	365/34	5.14
8	6-27.4	Joseph M. & Tammy A. Rice	634/778	3.79
9	6-21.2	Richard E. Leek	OR147/27	3.15
10	6-27.1	Larry G. Rice	333/682	0.81
11	6-27.5	David W. VanCamp	555/14	2.56
12	6-21.3	Richard E. Leek	OR147/27	0.28
13	6-21.1	Richard E. Leek	391/533	2.74
14	6-29	Richard Leek	402/216	1.00
15	6-28	David Wayne & Virginia VanCamp	395/557	2.00
16	6-47.1	Donna Faulk	408/113	1.00
17	6-27.2	David Wayne & Virginia VanCamp	395/557	1.0
18	6-47	Jeffrey Seckman	545/70	18.99
19	6-11	Jeffrey A. & Joann E. Seckman	343/153-A	68.72
20	6-20.2	Hiram Groves	98/195	7.50
21	6-20.1	Jeffrey Seckman	545/70	2.52
22	6-19	Linda J. & Jack E. Mason	OR101/678	10.00
23	6-20	Jeffrey Seckman	545/70	36.15
24	6-8	Matthew T. Ebert	361/219	98.50
25	6-7	Gary A. & Penny K. Midcap	301/265	30.90
26	3-26.1	Gary A. & Penny K. Midcap	301/265	40.00
27	3-34	Charlotte Terry, et al	WB76/367	57.19
28	3-27	Herbert & Phyllis Glendenning	349/827	33.25
29	3-25.1	Gary A. & Penny K. Midcap	304/230	33.48
30	3-25	Gary A. & Penny K. Midcap	301/265	42.47
31	3-28	Rhoda & Lawrence Morgan Est	317/413	61.33
32	3-19	Gary A. & Penny K. Midcap	301/265	20.94
33	3-9	Steven D. & Brenda M. Higgins	313/623	163.34
34	3-10	Steven D. & Brenda M. Higgins	313/623	79.75
35	3-10.1	Steven D. & Brenda M. Higgins	313/623	10.16
36	1-11	Daniel A. Witschey	541/326	122.81
37	16-64	Richard Todd Kay	420/650	29.00
38	1-16	Daniel A. & Amy J. Witschey	602/421	20.00

Leases	
A	BRC Appalachian Minerals I, LLC
B	Rose Enterprises, LLC
C	Dennis R. & Clista A. Heintzman
D	TMP Properties, LLC
E	Judy P. Meyers
F	Laura A. Richeson
G	Bobby J. Dennis
H	David W. VanCamp, et ux
I	BRC Appalachian Minerals I, LLC
J	Antero Mineral, LLC
K	Martha Elizabeth Matthews
L	David Wayne VanCamp, et ux
M	Jeffrey Seckman
N	Jon Keith Irvin
O	James D. VanCamp
P	Linda J. & Jack E. Mason
Q	David E. Bowyer
R	Christina L. Ebert
S	Gary A. Midcap, et ux
T	Gary A. Midcap, et ux
U	Lee Morgan
V	BRC Appalachian Minerals I, LLC
W	James D. VanCamp, et ux
X	MAP2012-OK
Y	William G. Baker
Z	Gary A. Midcap, et ux
AA	Mary F. Mutschelknaus
AB	Steven D. Higgins, et ux
AC	Beverly Kay Campbell
AD	Cider Run Mineral Holdings, LLC
AE	Don A. Stertzbach, et ux
AF	Michael Stillwagner

FILE NO: 99-54-E-19  
DRAWING NO: Mamba Unit 2H Well Plat  
SCALE: 1" = 2000'  
MINIMUM DEGREE OF ACCURACY:  
Submeter  
PROVEN SOURCE OF ELEVATION:  
WVDOT, Harrisville, WV

**STATE OF WEST VIRGINIA**  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
**OIL AND GAS DIVISION**

DATE: August 12 20 22  
OPERATOR'S WELL NO. Mamba Unit 2H  
API WELL NO  
47 - 095 - 02521  
STATE COUNTY PERMIT

WELL TYPE:  OIL  GAS  LIQUID INJECTION  WASTE DISPOSAL  
(IF GAS) PRODUCTION:  STORAGE  DEEP  SHALLOW  
LOCATION: ELEVATION: Existing 1215' Proposed 1193' WATERSHED: Middle Island Creek Outlet: Middle Island Creek QUADRANGLE: BH: Paden City TH: Porter Falls  
DISTRICT: Ellsworth COUNTY: Tyler  
SURFACE OWNER: Dennis & Clista Heintzman  
ROYALTY OWNER: BRC Appalachian Minerals I, LLC (2); TMP Properties, LLC; Judy P. Meyers; LEASE NO: ACREAGE: 417.6  
PROPOSED WORK:  DRILL  CONVERT  DRILL DEEPER  FRACTURE OR STIMULATE  PLUG OFF OLD FORMATION  
 PERFORATE NEW FORMATION  OTHER PHYSICAL CHANGE IN WELL (SPECIFY) ESTIMATED DEPTH: 24,200' MD  
 PLUG AND ABANDON  CLEAN OUT AND REPLUG TARGET FORMATION: Marcellus Shale

WELL OPERATOR: Antero Resources Corporation DESIGNATED AGENT: Dianna Stamper - CT Corporation System  
ADDRESS: 1615 Wynkoop Street ADDRESS: 5400 D Big Tyler Road  
Denver, CO 80202 Charleston, WV 25313

09/23/2022

WW-6A1

Operator's Well Number Mamba Unit 2H

INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE  
Chapter 22, Article 6A, Section 5(a)(5)  
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that –

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Grantor, lessor, etc.	Grantee, lessee, etc.	Royalty	Book/Page
<b><u>A: BRC Appalachian Minerals I LLC Lease</u></b>			
BRC Appalachian Minerals I LLC	BRC Working Interest Company LLC	1/8	0369/0300
BRC Working Interest Company LLC	Chesapeake Appalachia LLC	Assignment	0369/0784
Chesapeake Appalachia LLC	Statoil USA Onshore Properties Inc	Assignment	0378/0764
Statoil USA Onshore Properties Inc	SWN Exchange Titleholder LLC	Assignment	0470/0668
SWN Exchange Titleholder LLC	EQT Production Company	Assignment	0539/0239
EQT Production Company	Antero Resources Corporation	Assignment	0663/0001
<b><u>D: TMP Properties, LLC Lease</u></b>			
TMP Properties, LLC	Antero Resources Corporation	1/8+	0070/0197
<b><u>E: Judy P. Meyers Lease</u></b>			
Judy P. Meyers	Antero Resources Corporation	1/8+	0002/0044
<b><u>M: Jeffrey Seckman Lease</u></b>			
Jeffrey Seckman	Antero Resources Corporation	1/8+	0191/0097
<b><u>L: David Wayne VanCamp, et ux Lease</u></b>			
David Wayne VanCamp, et ux	Antero Resources Corporation	1/8+	0415/0756
<b><u>O: James D. VanCamp Lease</u></b>			
James D. VanCamp	Antero Resources Corporation	1/8+	0553/0693
<b><u>Q: David E. Bowyer Lease</u></b>			
David E. Bowyer	Antero Resources Corporation	1/8+	0191/0095
<b><u>R: Christina L. Ebert Lease</u></b>			
Christina L. Ebert	Antero Resources Corporation	1/8+	0108/0694
<b><u>S: Gary A. Midcap, et ux Lease</u></b>			
Gary A. Midcap, et ux	Antero Resources Corporation	1/8+	0070/0182
<b><u>T: Gary A. Midcap, et ux Lease</u></b>			
Gary A. Midcap, et ux	Antero Resources Corporation	1/8+	0070/0182
<b><u>U: Lee Morgan Lease</u></b>			
Lee Morgan	Antero Resources Corporation	1/8+	0106/0557
<b><u>V: BRC Appalachian Minerals I LLC Lease</u></b>			
BRC Appalachian Minerals I LLC	BRC Working Interest Company LLC	1/8	0369/0300
BRC Working Interest Company LLC	Chesapeake Appalachia LLC	Assignment	0369/0784
Chesapeake Appalachia LLC	Statoil USA Onshore Properties Inc	Assignment	0378/0764

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

09/23/2022

Operator's Well Number Mamba Unit 2H

INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE  
Chapter 22, Article 6A, Section 5(a)(5)  
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that –

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Grantor, lessor, etc.	Grantee, lessee, etc.	Royalty	Book/Page
Statoil USA Onshore Properties Inc	SWN Exchange Titleholder LLC	Assignment	0470/0668
SWN Exchange Titleholder LLC	EQT Production Company	Assignment	0539/0239
EQT Production Company	Antero Resources Corporation	Assignment	0663/0001
<b><u>W: James D. VanCamp, et ux Lease</u></b> James D. VanCamp, et ux	Antero Resources Corporation	1/8+	0664/0478
<b><u>Y: William G. Baker Lease</u></b> William G. Baker	Antero Resources Corporation	1/8+	0016/0488
<b><u>Z: Gary A. Midcap, et ux Lease</u></b> Gary A. Midcap, et ux	Antero Resources Corporation	1/8+	0070/0182

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

\*Partial Assignments to Antero Resources Corporation include 100% rights to extract, produce and market the oil and gas from the Marcellus and any other formations completed with this well.

**INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE  
Chapter 22, Article 6A, Section 5(a)(5)  
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)**

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that –

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
<u>AC: Beverly Kay Campbell Lease</u>	Beverly Kay Campbell	Antero Resources Corporation	1/8+	0012/0572

\*Partial Assignments to Antero Resources Corporation include 100% rights to extract, produce and market the oil and gas from the Marcellus and any other formations completed with this well.

**Acknowledgement of Possible Permitting/Approval  
In Addition to the Office of Oil and Gas**

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

Well Operator: Antero Resources Corporation  
 By: Tim Rady  
 Its: Senior VP of Land

RECEIVED  
Office of Oil and Gas  
AUG 16 2022

WV Department of  
Environmental Protection

4709502821



Antero Resources  
1615 Wynkoop Street  
Denver, CO 80202  
Office 303.357.7310  
Fax 303.357.7315

August 11, 2022

West Virginia Department of Environmental Protection  
Chief, Office of Oil and Gas  
Attn: Mr. James Martin  
601 57<sup>th</sup> Street SE  
Charleston, WV 25304

RE: Mamba Unit 1H & 2H  
Quadrangle: Porter Falls 7.5'  
Tyler County/Ellsworth District, West Virginia

Mr. Martin:

Antero Resources Corporation (Antero) is submitting the following application for a new well work permit for the Mamba Unit 1H & 2H horizontal shallow well. As an authorized representative, I certify that Antero has the right to extract, produce or market the oil or gas for all leases through which the Mamba Unit 1H & 2H horizontal lateral will drill through including any and all roads crossed under as identified on the attached survey plats.

Sincerely,

A handwritten signature in blue ink, appearing to read "Max Green", with a long horizontal flourish extending to the right.

Max Green  
VP Land

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

09/23/2022

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
NOTICE CERTIFICATION

Date of Notice Certification: 08/11/2022

API No. 47- 095 - \_\_\_\_\_

Operator's Well No. Mamba Unit 2H

Well Pad Name: Heintzman Pad

**Notice has been given:**

Pursuant to the provisions in West Virginia Code § 22-6A, the Operator has provided the required parties with the Notice Forms listed below for the tract of land as follows:

State:	<u>West Virginia</u>	UTM NAD 83	Easting:	<u>512407.24m</u>
County:	<u>Tyler</u>		Northing:	<u>4377043.72m</u>
District:	<u>Ellsworth</u>	Public Road Access:	<u>Elk Fork Rd</u>	
Quadrangle:	<u>Porter Falls 7.5'</u>	Generally used farm name:	<u>Dennis &amp; Clista Heintzman</u>	
Watershed:	<u>Outlet Middle Island Creek</u>			

Pursuant to West Virginia Code § 22-6A-7(b), every permit application filed under this section shall be on a form as may be prescribed by the secretary, shall be verified and shall contain the following information: (14) A certification from the operator that (i) it has provided the owners of the surface described in subdivisions (1), (2) and (4), subsection (b), section ten of this article, the information required by subsections (b) and (c), section sixteen of this article; (ii) that the requirement was deemed satisfied as a result of giving the surface owner notice of entry to survey pursuant to subsection (a), section ten of this article six-a; or (iii) the notice requirements of subsection (b), section sixteen of this article were waived in writing by the surface owner; and Pursuant to West Virginia Code § 22-6A-11(b), the applicant shall tender proof of and certify to the secretary that the notice requirements of section ten of this article have been completed by the applicant.

Pursuant to West Virginia Code § 22-6A, the Operator has attached proof to this Notice Certification that the Operator has properly served the required parties with the following:

\*PLEASE CHECK ALL THAT APPLY

- 1. NOTICE OF SEISMIC ACTIVITY or  NOTICE NOT REQUIRED BECAUSE NO SEISMIC ACTIVITY WAS CONDUCTED
- 2. NOTICE OF ENTRY FOR PLAT SURVEY or  NO PLAT SURVEY WAS CONDUCTED
- 3. NOTICE OF INTENT TO DRILL or  NOTICE NOT REQUIRED BECAUSE NOTICE OF ENTRY FOR PLAT SURVEY WAS CONDUCTED or  WRITTEN WAIVER BY SURFACE OWNER (PLEASE ATTACH)
- 4. NOTICE OF PLANNED OPERATION
- 5. PUBLIC NOTICE
- 6. NOTICE OF APPLICATION

**OOG OFFICE USE ONLY**

- RECEIVED/ NOT REQUIRED
- RECEIVED
- RECEIVED/ NOT REQUIRED
- RECEIVED
- RECEIVED
- RECEIVED

Office of Oil and Gas  
AUG 16 2022  
WV Department of Environmental Protection


**Required Attachments:**

The Operator shall attach to this Notice Certification Form all Notice Forms and Certifications of Notice that have been provided to the required parties and/or any associated written waivers. For the Public Notice, the operator shall attach a copy of the Class II Legal Advertisement with publication date verification or the associated Affidavit of Publication. The attached Notice Forms and Certifications of Notice shall serve as proof that the required parties have been noticed as required under West Virginia Code § 22-6A. Pursuant to West Virginia Code § 22-6A-11(b), the Certification of Notice to the person may be made by affidavit of personal service, the return receipt card or other postal receipt for certified mailing.

**Certification of Notice is hereby given:**

THEREFORE, I Robert Odenthal, have read and understand the notice requirements within West Virginia Code § 22-6A. I certify that as required under West Virginia Code § 22-6A, I have served the attached copies of the Notice Forms, identified above, to the required parties through personal service, by registered mail or by any method of delivery that requires a receipt or signature confirmation. I certify under penalty of law that I have personally examined and am familiar with the information submitted in this Notice Certification and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Well Operator:	<u>Antero Resources Corporation</u>	Address:	<u>1615 Wynkoop Street</u>
By:	<u>Robert Odenthal <i>Robert S. Odenthal</i></u>		<u>Denver, CO 80202</u>
Its:	<u>VP of Drilling</u>	Facsimile:	<u>303-357-7315</u>
Telephone:	<u>303-357-7310</u>	Email:	<u>mstanton@anteroresources.com</u>



Subscribed and sworn before me this 12 day of Aug 2022.

*Diane Blair* Notary Public

My Commission Expires 27 Apr 2024

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [deprivacyofficer@wv.gov](mailto:deprivacyofficer@wv.gov).

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

WW-6A  
(9-13)

API NO. 47-095-4709502821  
OPERATOR WELL NO. Mamba Unit 2H  
Well Pad Name: Heintzman Pad

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
NOTICE OF APPLICATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: 06/23/2022 Date Permit Application Filed: 08/12/2022

Notice of:

- [X] PERMIT FOR ANY WELL WORK [ ] CERTIFICATE OF APPROVAL FOR THE CONSTRUCTION OF AN IMPOUNDMENT OR PIT

Delivery method pursuant to West Virginia Code § 22-6A-10(b)

- [ ] PERSONAL SERVICE [ ] REGISTERED MAIL [X] METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to W. Va. Code § 22-6A-10(b) no later than the filing date of the application, the applicant for a permit for any well work or for a certificate of approval for the construction of an impoundment or pit as required by this article shall deliver, by personal service or by registered mail or by any method of delivery that requires a receipt or signature confirmation, copies of the application, the erosion and sediment control plan required by section seven of this article, and the well plat to each of the following persons: (1) The owners of record of the surface of the tract on which the well is or is proposed to be located; (2) The owners of record of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for roads or other land disturbance as described in the erosion and sediment control plan submitted pursuant to subsection (c), section seven of this article; (3) The coal owner, operator or lessee, in the event the tract of land on which the well proposed to be drilled is located [sic] is known to be underlain by one or more coal seams; (4) The owners of record of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for the placement, construction, enlargement, alteration, repair, removal or abandonment of any impoundment or pit as described in section nine of this article; (5) Any surface owner or water purveyor who is known to the applicant to have a water well, spring or water supply source located within one thousand five hundred feet of the center of the well pad which is used to provide water for consumption by humans or domestic animals; and (6) The operator of any natural gas storage field within which the proposed well work activity is to take place. (c)(1) If more than three tenants in common or other co-owners of interests described in subsection (b) of this section hold interests in the lands, the applicant may serve the documents required upon the person described in the records of the sheriff required to be maintained pursuant to section eight, article one, chapter eleven-a of this code. (2) Notwithstanding any provision of this article to the contrary, notice to a lien holder is not notice to a landowner, unless the lien holder is the landowner. W. Va. Code R. § 35-8-5.7.a requires, in part, that the operator shall also provide the Well Site Safety Plan ("WSSP") to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

[X] Application Notice [X] WSSP Notice [X] E&S Plan Notice [X] Well Plat Notice is hereby provided to:

[X] SURFACE OWNER(s)  
Name: Dennis R. & Clista A. heintzman  
Address: 980 Sand Gap Road  
Pennsboro WV 26415-3051  
Name: Stefan L. & Alberta B. Smolski  
Address: 510 Pittsburgh Avenue  
Fairmont WV 26554-4162

[ ] COAL OWNER OR LESSEE  
Name: NO DECLARATIONS ON RECORD WITH COUNTY  
Address: \_\_\_\_\_  
[ ] COAL OPERATOR  
Name: NO DECLARATIONS ON RECORD WITH COUNTY  
Address: \_\_\_\_\_

[ ] SURFACE OWNER(s) (Road and/or Other Disturbance)  
Name: \_\_\_\_\_  
Address: \_\_\_\_\_  
Name: \_\_\_\_\_  
Address: \_\_\_\_\_

[ ] SURFACE OWNER OF WATER WELL AND/OR WATER PURVEYOR(s)  
Name: NO WATER WELLS WITHIN 2000'  
Address: \_\_\_\_\_

[ ] SURFACE OWNER(s) (Impoundments or Pits)  
Name: \_\_\_\_\_  
Address: \_\_\_\_\_

[ ] OPERATOR OF ANY NATURAL GAS STORAGE FIELD  
Name: \_\_\_\_\_  
Address: \_\_\_\_\_

\*Please attach additional forms if necessary

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

09/23/2022



**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-10(b), notice is hereby given that the undersigned well operator has applied for a permit for well work or for a certificate of approval for the construction of an impoundment or pit.

**This Notice Shall Include:**

Pursuant to W. Va. Code § 22-6A-10(b), this notice shall include: (1) copies of the application; (2) the erosion and sediment control plan required by section seven of this article; and (3) the well plat.

Pursuant to W. Va. Code § 22-6A-10(f), this notice shall include: (1) a statement of the time limits for filing written comments; (2) who may file written comments; (3) the name and address of the secretary for the purpose of filing the comments and obtaining additional information; and (4) a statement that the persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

Pursuant to W. Va. Code R. § 35-8-5.7.a, the operator shall provide the Well Site Safety Plan to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

Pursuant to W. Va. Code R. § 35-8-15.2.c, this notice shall: (1) contain a statement of the surface owner's and water purveyor's right to request sampling and analysis; (2) advise the surface owner and water purveyor of the rebuttable presumption for contamination or deprivation of a fresh water source or supply; advise the surface owner and water purveyor that refusal to allow the operator to conduct a pre-drilling water well test constitutes a method to rebut the presumption of liability; (3) advise the surface owner and water purveyor of his or her independent right to sample and analyze any water supply at his or her own expense; advise the surface owner and water purveyor whether or not the operator will utilize an independent laboratory to analyze any sample; and (4) advise the surface owner and or water purveyor that he or she can obtain from the Chief a list of water testing laboratories in the subject area capable of and qualified to test water supplies in accordance with standard acceptable methods.

Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/and-gas/pages/default.aspx](http://www.dep.wv.gov/and-gas/pages/default.aspx).

RECEIVED  
Office of Oil and Gas  
AUG 16 2022

**Well Location Restrictions**

Pursuant to W. Va. Code § 22-6A-12, Wells may not be drilled within two hundred fifty feet measured horizontally from any existing water well or developed spring used for human or domestic animal consumption. The center of well pads may not be located within six hundred twenty-five feet of an occupied dwelling structure, or a building two thousand five hundred square feet or larger used to house or shelter dairy cattle or poultry husbandry. This limitation is applicable to those wells, developed springs, dwellings or agricultural buildings that existed on the date a notice to the surface owner of planned entry for surveying or staking as provided in section ten of this article or a notice of intent to drill a horizontal well as provided in subsection (b), section sixteen of this article was provided, whichever occurs first, and to any dwelling under construction prior to that date. This limitation may be waived by written consent of the surface owner transmitted to the department and recorded in the real property records maintained by the clerk of the county commission for the county in which such property is located. Furthermore, the well operator may be granted a variance by the secretary from these distance restrictions upon submission of a plan which identifies the sufficient measures, facilities or practices to be employed during well site construction, drilling and operations. The variance, if granted, shall include terms and conditions the department requires to ensure the safety and protection of affected persons and property. The terms and conditions may include insurance, bonding and indemnification, as well as technical requirements. (b) No well pad may be prepared or well drilled within one hundred feet measured horizontally from any perennial stream, natural or artificial lake, pond or reservoir, or a wetland, or within three hundred feet of a naturally reproducing trout stream. No well pad may be located within one thousand feet of a surface or ground water intake of a public water supply. The distance from the public water supply as identified by the department shall be measured as follows: (1) For a surface water intake on a lake or reservoir, the distance shall be measured from the boundary of the lake or reservoir. (2) For a surface water intake on a flowing stream, the distance shall be measured from a semicircular radius extending upstream of the surface water intake. (3) For a groundwater source, the distance shall be measured from the wellhead or spring. The department may, in its discretion, waive these distance restrictions upon submission of a plan identifying sufficient measures, facilities or practices to be employed during well site construction, drilling and operations to protect the waters of the state. A waiver, if granted, shall impose any permit conditions as the secretary considers necessary. (c) Notwithstanding the foregoing provisions of this section, nothing contained in this section prevents an operator from conducting the activities permitted or authorized by a Clean Water Act Section 404 permit or other approval from the United States Army Corps of Engineers within any waters of the state or within the restricted areas referenced in this section. (d) The well location restrictions set forth in this section shall not apply to any well on a multiple well pad if at least one of the wells was permitted prior to the effective date of this article. (e) The secretary shall, by December 31, 2012, report to the Legislature on the noise, light, dust and volatile organic compounds generated by the drilling of horizontal wells as they relate to the well location restrictions regarding occupied dwelling structures pursuant to this section. Upon a finding, if any, by the secretary that the well location restrictions regarding occupied dwelling structures are inadequate or otherwise require alteration to address the items

WV Department of Environmental Protection

WW-6A  
(8-13)

API NO. 47-095 **4709502821**  
OPERATOR WELL NO. Mamba Unit 2H  
Well Pad Name: Heintzman Pad

examined in the study required by this subsection, the secretary shall have the authority to propose for promulgation legislative rules establishing guidelines and procedures regarding reasonable levels of noise, light, dust and volatile organic compounds relating to drilling horizontal wells, including reasonable means of mitigating such factors, if necessary.

**Water Well Testing:**

Pursuant to West Virginia Code § 22-6A-10(d), notification shall be made, with respect to surface landowners identified in subsection (b) or water purveyors identified in subdivision (5), subsection (b) of this section, of the opportunity for testing their water well. The operator shall provide an analysis to such surface landowner or water purveyor at their request.

**Water Testing Laboratories:**

Pursuant to West Virginia Code § 22-6A-10(i), persons entitled to notice pursuant to subsection (b) of this section may contact the department to ascertain the names and locations of water testing laboratories in the subject area capable and qualified to test water supplies in accordance with standard accepted methods. In compiling that list of names the department shall consult with the state Bureau for Public Health and local health departments. A surface owner and water purveyor has an independent right to sample and analyze any water supply at his or her own expense. The laboratory utilized by the operator shall be approved by the agency as being certified and capable of performing sample analyses in accordance with this section.

**Rebuttable Presumption for Contamination or Deprivation of a Fresh Water Source or Supply:**

W. Va. Code § 22-6A-18 requires that (b) unless rebutted by one of the defenses established in subsection (c) of this section, in any action for contamination or deprivation of a fresh water source or supply within one thousand five hundred feet of the center of the well pad for horizontal well, there is a rebuttable presumption that the drilling and the oil or gas well or either was the proximate cause of the contamination or deprivation of the fresh water source or supply. (c) In order to rebut the presumption of liability established in subsection (b) of this section, the operator must prove by a preponderance of the evidence one of the following defenses: (1) The pollution existed prior to the drilling or alteration activity as determined by a predrilling or prealteration water well test. (2) The landowner or water purveyor refused to allow the operator access to the property to conduct a predrilling or prealteration water well test. (3) The water supply is not within one thousand five hundred feet of the well. (4) The pollution occurred more than six months after completion of drilling or alteration activities. (5) The pollution occurred as the result of some cause other than the drilling or alteration activity. (d) Any operator electing to preserve its defenses under subdivision (1), subsection (c) of this section shall retain the services of an independent certified laboratory to conduct the predrilling or prealteration water well test. A copy of the results of the test shall be submitted to the department and the surface owner or water purveyor in a manner prescribed by the secretary. (e) Any operator shall replace the water supply of an owner of interest in real property who obtains all or part of that owner's supply of water for domestic, agricultural, industrial or other legitimate use from an underground or surface source with a comparable water supply where the secretary determines that the water supply has been affected by contamination, diminution or interruption proximately caused by the oil or gas operation, unless waived in writing by that owner. (f) The secretary may order the operator conducting the oil or gas operation to: (1) Provide an emergency drinking water supply within twenty-four hours; (2) Provide temporary water supply within seventy-two hours; (3) Within thirty days begin activities to establish a permanent water supply or submit a proposal to the secretary outlining the measures and timetables to be used in establishing a permanent supply. The total time in providing a permanent water supply may not exceed two years. If the operator demonstrates that providing a permanent replacement water supply cannot be completed within two years, the secretary may extend the time frame on case-by-case basis; and (4) Pay all reasonable costs incurred by the real property owner in securing a water supply. (g) A person as described in subsection (b) of this section aggrieved under the provisions of subsections (b), (e) or (f) of this section may seek relief in court... (i) Notwithstanding the denial of the operator of responsibility for the damage to the real property owner's water supply or the status of any appeal on determination of liability for the damage to the real property owner's water supply, the operator may not discontinue providing the required water until authorized to do so by the secretary or a court of competent jurisdiction.

RECEIVED  
Office of Oil and Gas

**Written Comment:**

Pursuant to West Virginia Code § 22-6A-11(a), all persons described in subsection (b), section ten of this article may file written comments with the secretary as to the location or construction of the applicant's proposed well work within thirty days after the application is filed with the secretary. All persons described in West Virginia Code § 22-6A-10(b) may file written comments as to the location or construction of the applicant's proposed well work to the Secretary at:

AUG 16 2022  
WV DEPARTMENT OF ENVIRONMENTAL PROTECTION

Chief, Office of Oil and Gas  
Department of Environmental Protection  
601 57<sup>th</sup> St. SE  
Charleston, WV 25304  
(304) 926-0450

Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water. **NOTE: YOU ARE NOT REQUIRED TO FILE ANY COMMENT.**

09/23/2022

**Time Limits and Methods for Filing Comments.**

The law requires these materials to be served on or before the date the operator files its Application. You have **THIRTY (30) DAYS** after the filing date to file your comments. Comments must be filed in person or received in the mail by the Chief's office by the time stated above. You may call the Chief's office to be sure of the date. Check with your postmaster to ensure adequate delivery time or to arrange special expedited handling. If you have been contacted by the well operator and you have signed a "voluntary statement of no objection" to the planned work described in these materials, then the permit may be issued at any time.

Pursuant to West Virginia Code § 22-6A-11(c)(2), Any objections of the affected coal operators and coal seam owners and lessees shall be addressed through the processes and procedures that exist under sections fifteen, seventeen and forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article. The written comments filed by the parties entitled to notice under subdivisions (1), (2), (4), (5) and (6), subsection (b), section ten of this article shall be considered by the secretary in the permit issuance process, but the parties are not entitled to participate in the processes and proceedings that exist under sections fifteen, seventeen or forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article.

**Comment Requirements**

Your comments must be in writing and include your name, address and telephone number, the well operator's name and well number and the approximate location of the proposed well site including district and county from the application. You may add other documents, such as sketches, maps or photographs to support your comments.

Disclaimer: All comments received will be placed on our web site <http://www.dep.wv.gov/oil-and-gas/Horizontal-Permits/Pages/default.aspx> and the applicant will automatically be forwarded an email notice that such comments have been submitted. The applicant will be expected to provide a response to comments submitted by any surface owner, water purveyor or natural gas storage operator noticed within the application.

**Permit Denial or Condition**

The Chief has the power to deny or condition a well work permit. Pursuant to West Virginia Code § 22-6A-8(d), the permit may not be issued or be conditioned, including conditions with respect to the location of the well and access roads prior to issuance if the director determines that:

- (1) The proposed well work will constitute a hazard to the safety of persons;
- (2) The plan for soil erosion and sediment control is not adequate or effective;
- (3) Damage would occur to publicly owned lands or resources; or
- (4) The proposed well work fails to protect fresh water sources or supplies.

RECEIVED  
Office of Oil and Gas

A permit may also be denied under West Virginia Code § 22-6A-7(k), the secretary shall deny the issuance of a permit if the secretary determines that the applicant has committed a substantial violation of a previously issued permit for a horizontal well, including the applicable erosion and sediment control plan associated with the previously issued permit, or a substantial violation of one or more of the rules promulgated under this article, and in each instance has failed to abate or seek review of the violation within the time prescribed by the secretary pursuant to the provisions of subdivisions (1) and (2), subsection (a), section five of this article and the rules promulgated hereunder, which time may not be unreasonable.

AUG 16 2022  
WV DEPARTMENT OF ENVIRONMENTAL PROTECTION

Pursuant to West Virginia Code § 22-6A-10(g), any person entitled to submit written comments to the secretary pursuant to subsection (a), section eleven of this article, shall also be entitled to receive from the secretary a copy of the permit as issued or a copy of the order modifying or denying the permit if the person requests receipt of them as a part of the written comments submitted concerning the permit application. Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

WW-6A  
(8-13)

4709502821  
API NO. 47-095  
OPERATOR WELL NO. Mamba Unit 2H  
Well Pad Name: Heintzman Pad


**Notice is hereby given by:**

Well Operator: Antero Resources Corporation  
Telephone: (303) 357-7310 Robert S. Odenthal  
Email: mstanton@anteroresources.com

Address: 1615 Wynkoop Street  
Denver, CO 80202  
Facsimile: 303-357-7315

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).



Subscribed and sworn before me this 12 day of Aug 2022.

Diane Blair Notary Public

My Commission Expires 27 Apr 2024


RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

09/23/2022

### Heintzman Drill Pad Water Well & Spring Map



Scale 1" = 600'



RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

Note: No water wells were found within 2000' from center of proposed pad.

**STATE OF WEST VIRGINIA**  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS**  
**NOTICE OF INTENT TO DRILL**

Pursuant to W. Va. Code § 22-6A-16(b), the Notice of Intent to Drill is only required if the notice requirements of W. Va. Code § 22-6A-10(a) have NOT been met or if the Notice of Intent to Drill requirement has NOT been waived in writing by the surface owner.

**Notice Time Requirement:** Notice shall be provided at least **TEN (10)** days prior to filing a permit application.

**Date of Notice:** 06/23/2022      **Date Permit Application Filed:** 08/12/2022

**Delivery method pursuant to West Virginia Code § 22-6A-16(b)**

HAND DELIVERY       CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Pursuant to W. Va. Code § 22-6A-16(b), at least ten days prior to filing a permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner notice of its intent to enter upon the surface owner's land for the purpose of drilling a horizontal well: *Provided*, That notice given pursuant to subsection (a), section ten of this article satisfies the requirements of this subsection as of the date the notice was provided to the surface owner: *Provided, however*, That the notice requirements of this subsection may be waived in writing by the surface owner. The notice, if required, shall include the name, address, telephone number, and if available, facsimile number and electronic mail address of the operator and the operator's authorized representative.

**Notice is hereby provided to the SURFACE OWNER(s):**

Name: Dennis R. & Clista A. Heintzman  
Address: 980 Sand Gap Road  
Pennsboro, WV 26415-3051

Name: Stefan L. & Alberta B. Smolski  
Address: 510 Pittsburgh Avenue  
Fairmont, WV 26554-4162

RECEIVED  
Office of Oil and Gas

AUG 16 2022

WV Department of  
Environmental Protection

**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-16(b), notice is hereby given that the undersigned well operator has an intent to enter upon the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State: <u>West Virginia</u>	UTM NAD 83	Easting: <u>512407.24m</u>
County: <u>Tyler</u>		Northing: <u>4377043.72m</u>
District: <u>Ellsworth</u>	Public Road Access: <u>Elk Fork Rd</u>	
Quadrangle: <u>Porter Falls 7.5'</u>	Generally used farm name: <u>Dennis Heintzman et al</u>	
Watershed: <u>Outlet Middle Island Creek</u>		

**This Notice Shall Include:**

Pursuant to West Virginia Code § 22-6A-16(b), this notice shall include the name, address, telephone number, and if available, facsimile number and electronic mail address of the operator and the operator's authorized representative. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/oil-and-gas/pages/default.aspx](http://www.dep.wv.gov/oil-and-gas/pages/default.aspx).

**Notice is hereby given by:**

Well Operator: Antero Resources Corporation  
Address: 1615 Wynkoop St.  
Denver, CO 80202  
Telephone: 303-357-7310  
Email: mstanton@anteroresources.com  
Facsimile: 303-357-7315

Authorized Representative: Mallory Stanton  
Address: 1615 Wynkoop St.  
Denver, CO 80202  
Telephone: 303-357-7310  
Email: mstanton@anteroresources.com  
Facsimile: 303-357-7315

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS  
NOTICE OF PLANNED OPERATION

**Notice Time Requirement:** notice shall be provided no later than the **filing date of permit application.**

**Date of Notice:** 08/12/2022 **Date Permit Application Filed:** 08/12/2022

**Delivery method pursuant to West Virginia Code § 22-6A-16(c)**

- CERTIFIED MAIL RETURN RECEIPT REQUESTED
- HAND DELIVERY

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

**Notice is hereby provided to the SURFACE OWNER(s)**  
(at the address listed in the records of the sheriff at the time of notice):

Name: Dennis R. & Clista A. Heintzman  
Address: 980 Sand Gap Road  
Pennsboro WV 26415-3051

Name: Stefan L. & Alberta B. Smolksi  
Address: 510 Pittsburgh Avenue  
Fairmont, WV 26554-4162

**Notice is hereby given:**

Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State:	West Virginia	UTM NAD 83 Easting:	512407.24m
County:	Tyler	UTM NAD 83 Northing:	4377043.72m
District:	Ellsworth	Public Road Access:	Elk Fork Rd
Quadrangle:	Porter Falls 7.5'	Generally used farm name:	Dennis & Clista Heintzman
Watershed:	Outlet Middle Island Creek		

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

**This Notice Shall Include:**

Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1) A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57<sup>th</sup> Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting [www.dep.wv.gov/oil-and-gas/pages/default.aspx](http://www.dep.wv.gov/oil-and-gas/pages/default.aspx).

Well Operator: Antero Resources Corporation  
Telephone: (303) 357-7310  
Email: mstanton@anteroresources.com

Address: 1615 Wynkoop Street  
Denver, CO 80202  
Facsimile: 303-357-7315

**Oil and Gas Privacy Notice:**

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at [depprivacyofficer@wv.gov](mailto:depprivacyofficer@wv.gov).

4709502821



WEST VIRGINIA DEPARTMENT OF TRANSPORTATION  
**Division of Highways**

1900 Kanawha Boulevard East • Building Five • Room 110  
Charleston, West Virginia 25305-0430 • (304) 558-3505

D. Alan Reed, P.E.  
State Highway Engineer

Jimmy Wriston, P. E.  
Secretary of Transportation  
Commissioner of Highways

July 18, 2022

James A. Martin, Chief  
Office of Oil and Gas  
Department of Environmental Protection  
601 57<sup>th</sup> Street, SE  
Charleston, WV 25304

Subject: DOH Permit for the Heintzman Pad, Tyler County  
Mamba Unit 2H Well Site

Dear Mr. Martin,

This well site will be accessed from a DOH permit #06-2017-0767 which has been issued to Antero Resources for access to the State Road for a well site located off Tyler County Route 11/6 SLS MP 0.33.

This operator is in compliance with §22-6A-20 of the WV Code. Operator has signed a STATEWIDE OIL AND GAS ROAD MAINTENANCE BONDING AGREEMENT and provided the required Bond. This operator is currently in compliance with the DOH OIL AND GAS POLICY dated October 1, 2018. This letter is valid for permitting purposes for one year from the date of this letter.

Very Truly Yours,

A handwritten signature in blue ink that reads "Gary K. Clayton".

Gary K. Clayton, P.E.  
Regional Maintenance Engineer  
Central Office O&G Coordinator

Cc: Diane Blair  
Antero Resources  
CH, OM, D-6  
File

RECEIVED  
Office of Oil and Gas  
AUG 16 2022

WV Department of  
Environmental Protection



Subdivision 3.3.e A listing of the anticipated additives that may be used in the water used for fracturing or stimulating the well. (A listing of the additives that were actually used in the fracturing or stimulating of the well shall be submitted as part of the completion report required by W. Va. Code 22-6-22.)

**FRACTURING/STIMULATING INTERVAL**

<b>Additive</b>	<b>Chemical Abstract Service Number (CAS #)</b>
1. Fresh Water	7732-18-5
2. 2 Phosphobutane 1,2,4 tricarboxylic acid	37971-36-1
3. Ammonium Persulfate	7727-54-0
4. Anionic copolymer	Proprietary
5. Anionic polymer	Proprietary
6. BTEX Free Hydrotreated Heavy Naphtha	64742-48-9
7. Cellulase enzyme	(Proprietary)
8. Demulsifier Base	(Proprietary)
9. Ethoxylated alcohol blend	Mixture
10. Ethoxylated Nonylphenol	68412-54-4
11. Ethoxylated oleylamine	26635-93-8
12. Ethylene Glycol	107-21-1
13. Glycol Ethers	111-76-2
14. Guar gum	9000-30-0
15. Hydrogen Chloride	7647-01-0
16. Hydrotreated light distillates, non-aromatic, BTEX free	64742-47-8
17. Isopropyl alcohol	67-63-0
18. Liquid, 2,2-dibromo-3- nitrilopropionamide	10222-01-2
19. Microparticle	Proprietary
20. Petroleum Distillates (BTEX Below Detect)	64742-47-8
21. Polyacrylamide	57-55-6
22. Propargyl Alcohol	107-19-7
23. Propylene Glycol	57-55-6
24. Quartz	14808-60-7
25. Sillica crystalline quartz	7631-86-9
26. Sodium Chloride	7647-14-5
27. Sodium Hydroxide	1310-73-2
28. Sugar	57-50-1
29. Surfactant	68439-51-0
30. Suspending agent (solid)	14808-60-7
31. Tar bases, quinolone derivs, benzyl chloride-quarternized	72480-70-7
32. Solvent Naptha, petroleum, heavy alliph	64742-96-7
33. Soybean Oil, Me ester	67784-80-9
34. Copolymer of Maleic and Acrylic Acid	52255-49-9
35. DETA Phosponate	15827-60-8
36. Hexamethylene Triamine Penta	34690-00-1
37. Phosphino Carboxylic acid polymer	71050-62-9
38. Hexamethylene diamine penta	23605-74-5
39. 2-Propenoic acid, polymer with 2 propenamides	9003-06-9
40. Hexamethylene diamine penta (methylene phosphonic acid)	23605-74-5
41. Diethylene Glycol	111-46-6
42. Methenamine	100-97-0
43. Polyethylene polyamine	68603-67-8
44. Coco amine	61791-14-8
45. 2-Propyn-1-olcompound with methyloxirane	38172-91-7

RECEIVED  
Office of Oil and Gas  
AUG 16 2022  
WV Department of  
Environmental Protection

**LOCATION COORDINATES:**  
 HEINTZMAN (PANEL) ACCESS ROAD "A" ENTRANCE  
 LATITUDE: 38.53884 LONGITUDE: -80.887509 (NAD 83)  
 LATITUDE: 38.538804 LONGITUDE: -80.887682 (NAD 27)  
 N 4376696.59 E 508840.55 (UTM ZONE 17 METERS)  
 CENTROID OF PAD  
 LATITUDE: 38.543105 LONGITUDE: -80.885716 (NAD 83)  
 LATITUDE: 38.543057 LONGITUDE: -80.885890 (NAD 27)  
 N 4377058.34 E 512387.71 (UTM ZONE 17 METERS)

**GENERAL DESCRIPTION:**  
 THE ACCESS ROAD(S) AND WELL PAD ARE BEING CONSTRUCTED TO AID IN THE DEVELOPMENT OF MARCELLUS SHALE GAS WELLS.

**FLOODPLAIN NOTES:**  
 THE PROPOSED SITE IS LOCATED WITHIN FEMA FLOOD ZONE "X" PER FEMA FLOOD MAP NUMBER 4540950045C.

**MISS UTILITY STATEMENT:**  
 ANTERO RESOURCES CORPORATION WILL NOTIFY MISS UTILITY OF WEST VIRGINIA FOR THE LOCATING OF UTILITIES PRIOR TO THIS PROJECT DESIGN. TICKET 1907295086. IN ADDITION, MISS UTILITY WILL BE CONTACTED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT.

**ENTRANCE PERMIT:**  
 ANTERO RESOURCES CORPORATION WILL OBTAIN AN ENCROACHMENT PERMIT (FORM MM-109) FROM THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

**ENVIRONMENTAL NOTES:**  
 STREAM AND WETLAND DELINEATIONS WERE PERFORMED IN 2018 & 2019, BY ALLSTAR ECOLOGY TO REVIEW THE SITE FOR WATERS AND WETLANDS THAT ARE MOST LIKELY WITHIN THE REGULATORY PURVIEW OF THE U.S. ARMY CORPS OF ENGINEERS (USACE) AND/OR THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP). THE FEBRUARY 7, 2019 STREAM AND WETLAND DELINEATION INDEX MAP WAS PREPARED BY ALLSTAR ECOLOGY AND SUMMARIZES THE RESULTS OF THE FIELD DELINEATION. THIS MAP DOES NOT IN ANY WAY REPRESENT A JURISDICTIONAL DETERMINATION OF THE LANDWARD LIMITS OF WATERS AND WETLANDS WHICH MAY BE REGULATED BY THE USE OR THE WVDEP. IT IS STRONGLY RECOMMENDED THAT THE APPLICANT/OWNER BE CONSULTED IN AN EFFORT TO OBTAIN WRITTEN CONFIRMATION OF THE DELINEATION SHOWN ON THIS EXHIBIT PRIOR TO ENGAGING CONSTRUCTION ON THE PROPERTY DESCRIBED HEREIN. THE DEVELOPER SHALL OBTAIN THE APPROPRIATE PERMITS FROM THE FEDERAL AND/OR STATE REGULATORY AGENCIES PRIOR TO ANY PROPOSED IMPACTS TO WATERS OF THE U.S., INCLUDING WETLAND FILLS AND STREAM CROSSINGS.

**GEOTECHNICAL NOTES:**  
 A SUBSURFACE INVESTIGATION OF THE PROPOSED SITE WAS PERFORMED BY PENNSYLVANIA SOIL & ROCK, INC. ON MARCH 19 - MAY 22, 2019, AND REVISED FEBRUARY 19, 2020. THE REPORT PREPARED BY PENNSYLVANIA SOIL & ROCK, INC. DATED MAY 24, 2019, AND REVISED MAY 27, 2020, REFLECTS THE RESULTS OF THE SUBSURFACE INVESTIGATION. THE INFORMATION AND RECOMMENDATIONS CONTAINED IN THIS REPORT WERE USED IN THE PREPARATION OF THESE PLANS. PLEASE REFER TO THE SUBSURFACE INVESTIGATION REPORT BY PENNSYLVANIA SOIL & ROCK, INC. FOR ADDITIONAL INFORMATION, AS NEEDED.

**PROJECT CONTACTS:**

CHARLES E. COMPTON, III - UTILITY COORDINATOR  
 (304) 719-6449

MARK HUTTON - LAND AGENT  
 CELL: (304) 589-8935

**ENGINEER/SURVEYOR:**  
 NAVITUS ENGINEERING, INC.  
 CYRUS S. KUMAR, PE - PROJECT MANAGER/ENGINEER  
 OFFICE: (800) 882-4185 CELL: (540) 686-6747

**ENVIRONMENTAL:**  
 ALLSTAR ECOLOGY, LLC  
 RYAN L. WARD - ENVIRONMENTAL SCIENTIST  
 (618) 213-2888 CELL: (304) 882-7477

**GEOTECHNICAL:**  
 PENNSYLVANIA SOIL & ROCK, INC.  
 CHRISTOPHER W. SAMOIS - PROJECT ENGINEER  
 (412) 372-1000 CELL: (412) 589-0882

**RESTRICTIONS NOTES:**

1. THERE ARE NO PERENNIAL STREAMS, LAKES, POND'S OR RESERVOIRS WITHIN 100 FEET OF THE WELL PAD AND LOT. THERE ARE WETLANDS ADJACENT TO STOCKPILES WHICH WILL REMAIN UNDISTURBED.
2. THERE ARE NO NATURALLY PRODUCING TROUT STREAMS WITHIN 300 FEET OF THE WELL PAD AND LOT.
3. THERE ARE NO GROUNDWATER INTAKE OR PUBLIC WATER SUPPLY FACILITIES WITHIN 1000 FEET OF THE WELL PAD AND LOT.
4. THERE ARE NO APPARENT EXISTING WATER WELLS OR DEVELOPED SPRINGS WITHIN 200 FEET OF THE WELL(S) BEING DRILLED.
5. THERE ARE NO OCCUPIED DWELLING STRUCTURES WITHIN 625 FEET OF THE CENTER OF THE WELL PAD.
6. THERE ARE NO AGRICULTURAL BUILDINGS LARGER THAN 2,500 SQUARE FEET WITHIN 625 FEET OF THE CENTER OF THE WELL PAD.

**REPRODUCTION NOTE**

THESE PLANS WERE CREATED TO BE PLOTTED ON 24"X36" (ANSI D) PAPER. HALF SCALE DRAWINGS ARE ON 11"X17" (ANSI B) PAPER.

THESE PLANS WERE CREATED FOR COLOR PRINTING AND ANY REPRODUCTIONS IN GRAY SCALE OR COLOR MAY RESULT IN A LOSS OF INFORMATION AND SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES.

# HEINTZMAN WELL PAD

## SITE DESIGN & CONSTRUCTION PLAN, EROSION & SEDIMENT CONTROL PLANS

ELLSWORTH DISTRICT, TYLER COUNTY, WEST VIRGINIA  
 POINT PLEASANT CREEK & ELK FORK WATERSHEDS  
 USGS 7.5 PADEN CITY & PORTER FALLS QUAD MAPS



WEST VIRGINIA COUNTY MAP



(NOT TO SCALE)

WVDOH COUNTY ROAD MAP



WEST VIRGINIA STATE PLANE COORDINATE SYSTEM  
 NORTH ZONE, NAD83 NAVIS  
 ESTABLISHED BY SURVEY, GRADE CRIS & OPUS  
 POST-PROCESSING

**SHEET INDEX:**

1	COVER SHEET
2	NOTES
3	LEGEND
4	MATERIAL QUANTITIES
5	STORM DRAINAGE & E&S COMPUTATIONS
6	EXISTING CONDITIONS
7	EXISTING STRUCTURES & FEATURES
8	OVERALL PLAN SHEET INDEX & VOLUMES
10-11	ACCESS ROAD PLAN
12	ACCESS ROAD & WATER CONTAINMENT PAD PLAN
13	ACCESS ROAD & WELL PAD PLAN
14-16	ACCESS ROAD PLAN
17	WELL PAD PLAN
18-19	STOCKPILE PLAN
20	WELL PAD GRADING PLAN
21-25	ACCESS ROAD PROFILES
26	WELL PAD SECTIONS
27	STOCKPILE SECTIONS
28-36	CONSTRUCTION DETAILS
37-38	ACCESS ROAD RECLAMATION PLAN
39	ACCESS ROAD & WATER CONTAINMENT PAD RECLAMATION PLAN
40	ACCESS ROAD & WELL PAD RECLAMATION PLAN
41-43	ACCESS ROAD RECLAMATION PLAN
44	WELL PAD RECLAMATION PLAN
45-46	STOCKPILE RECLAMATION PLAN
6500-6505	GEOTECHNICAL DETAILS

**APPROVED**  
**WVDEP OOG**  
 Updated  
 9/7/2022

**HEINTZMAN LIMITS OF DISTURBANCE AREA (AC)**

Total Site	
Access Road "D" (3,932')	18.80
Well Pad	7.82
Excess/Topsoil Material Stockpiles	31.81
<b>Total Affected Area</b>	<b>58.03</b>
Total Wooded Acres Disturbed	45.55
<b>Impacts to Patricia Ann Heintzman TM 10-2</b>	
Access Road "D"	0.95
Well Pad	0.95
<b>Total Affected Area</b>	<b>0.96</b>
Total Wooded Acres Disturbed	0.95
<b>Impacts to Dennis R. &amp; Clete A. Heintzman TM 6-36</b>	
Access Road "D" (2,963')	11.62
Well Pad	5.53
Excess/Topsoil Material Stockpiles	29.51
<b>Total Affected Area</b>	<b>46.78</b>
Total Wooded Acres Disturbed	37.53
<b>Impacts to Dennis R. &amp; Clete A. Heintzman TM 6-48</b>	
Access Road "D" (969.00')	4.03
Well Pad	1.13
Excess/Topsoil Material Stockpiles	3.10
<b>Total Affected Area</b>	<b>8.26</b>
Total Wooded Acres Disturbed	7.02
<b>Impacts to Stefan L. &amp; Alberta B. Smoiled TM 10-4</b>	
Well Pad	1.06
Total Affected Area	1.06
Total Wooded Acres Disturbed	1.05

Well Name	WI North NAD 27	NAD 27 Lat & Long	UTM (METERS) ZONE 17	NAD 83 Lat & Long
Parents Location				
Leap	N 382789.41	LAT 38-32-34 8136	E 612409.88	LAT 38-32-32 5963
Unit 1H	E 191786.16	LONG 80-51-27 0739	E 612409.88	LONG 80-51-20 4538
Leap	N 382787.11	LAT 38-32-34 8847	E 612409.88	LAT 38-32-34 8857
Unit 2H	E 191783.05	LONG 80-51-20 9887	E 612409.88	LONG 80-51-20 3828
Mambo	N 382742.82	LAT 38-32-34 8343	E 612409.88	LAT 38-32-34 8343
Unit 1H	E 191786.03	LONG 80-51-20 8875	E 612409.88	LONG 80-51-20 2714
Mambo	N 382728.52	LAT 38-32-34 4258	E 612409.88	LAT 38-32-34 7948
Unit 2H	E 191786.08	LONG 80-51-20 4204	E 612409.88	LONG 80-51-20 1823
Normed	N 382716.22	LAT 38-32-34 2758	E 612409.88	LAT 38-32-34 5746
Unit 1H	E 191787.53	LONG 80-51-20 7152	E 612409.88	LONG 80-51-20 0891
Normed	N 382702.80	LAT 38-32-34 1933	E 612409.88	LAT 38-32-34 4442
Unit 2H	E 191786.08	LONG 80-51-20 6840	E 612409.88	LONG 80-51-20 8979
Heintzman Unit 3H (Permitted)	N 382713.42	LAT 38-32-34 8529	E 612409.88	LAT 38-32-34 1338
APW 47-884-22512	E 191785.85	LONG 80-51-21 2117	E 612409.88	LONG 80-51-20 5880
Proposed Well Pad Elevation	1,190.0			

MISS Utility of West Virginia  
 1-800-245-4848  
 West Virginia State Law  
 (Section XIV: Chapter 24-C)  
 Requires that you call two  
 business days before you dig in  
 the state of West Virginia.  
 IT'S THE LAW!!



**REVISION**

DATE	REVISION
05/01/2019	REVISED PER WVDEP COMMENTS
11/21/2019	REVISED PER WELL PAD & STOCKPILE
03/10/2020	REVISED PER PARTIAL CONSTRUCTION
06/04/2021	REVISED PER WELL PAD
06/15/2021	REVISED PER D&S
09/27/2022	REVISED PER WELL PAD




THIS DOCUMENT WAS PREPARED FOR ANTERO RESOURCES CORPORATION

COVER SHEET  
**HEINTZMAN**  
**WELL PAD**  
 ELLSWORTH DISTRICT  
 TYLER COUNTY, WEST VIRGINIA



DATE: 03/18/2019  
 SCALE: AS SHOWN  
 SHEET 1 OF 46

# WELL PAD GRADING PLAN



**APPROVED**  
**WVDEP OOG**  
 Updated  
 9/7/2022

**NAVATUS**  
 ENERGY ENGINEERING  
 Telephone: (888) 652-1151 www.NavatusEng.com

DATE	REVISION
05/10/2019	REVISED PER WHP COMMENTS
11/27/2019	REVISED PER WELL PAD & STOCKPILE
03/10/2020	REVISED FOR PARTIAL CONSTRUCTION
09/24/2020	REVISED PER WELL PAD
06/16/2021	REVISED PER RAS
09/17/2021	REVISED PER WELLS



WELL PAD GRADING PLAN  
**HEINTZMAN**  
**WELL PAD**  
 ELLSWORTH DISTRICT  
 TYLER COUNTY, WEST VIRGINIA



DATE: 03/18/2019  
 SCALE: 1" = 30'  
 SHEET 20 OF 46



**LOCATION COORDINATES:**

HEINTZMAN (REEL) ACCESS ROAD "A" ENTRANCE  
 LATITUDE: 39.539981 LONGITUDE: -80.987809 (NAD 83)  
 LATITUDE: 39.539984 LONGITUDE: -80.987809 (NAD 83)  
 N 4376698.56 E 509840.55 (UTM ZONE 17 METERS)  
 CENTER OF PAD  
 LATITUDE: 39.541055 LONGITUDE: -80.985716 (NAD 83)  
 LATITUDE: 39.543027 LONGITUDE: -80.985690 (NAD 83)  
 N 4377058.34 E 518397.71 (UTM ZONE 17 METERS)

**GENERAL DESCRIPTION:**

THE ACCESS ROAD(S), AND WELL PAD ARE BEING CONSTRUCTED TO AID IN THE DEVELOPMENT OF MARCELLUS SHALE GAS WELLS.

**FLOODPLAIN NOTES:**

THE PROPOSED SITE IS LOCATED WITHIN FEMA FLOOD ZONE "X" PER FEMA FLOOD MAP NUMBER #54095C0045C.

**MISS UTILITY STATEMENT:**

ANTERO RESOURCES CORPORATION WILL NOTIFY MISS UTILITY OF WEST VIRGINIA FOR THE LOCATING OF UTILITIES PRIOR TO THIS PROJECT DESIGN TICKET #07209088. IN ADDITION, MISS UTILITY WILL BE CONTACTED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT.

**ENTRANCE PERMIT:**

THE ANTERO RESOURCES CORPORATION WILL OBTAIN AN ENCROACHMENT PERMIT (FORM MM-109) FROM THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

**ENVIRONMENTAL NOTES:**

A SUBSURFACE INVESTIGATION OF THE PROPOSED SITE WAS PERFORMED BY ALLSTAR ECOLOGY TO REVIEW STREAM AND WETLAND DELINEATIONS WERE PERFORMED IN 2018 & 2019. BY ALLSTAR ECOLOGY TO REVIEW THE SITE FOR WATERS AND WETLANDS THAT ARE MOST LIKELY WITHIN THE REGULATORY PURVIEW OF THE U.S. ARMY CORPS OF ENGINEERS (USACE) AND/OR THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP). THE FEBRUARY 1, 2019 STREAM AND WETLAND DELINEATION INDEX MAP WAS PREPARED BY ALLSTAR ECOLOGY AND SUMMARIZES THE RESULTS OF THE FIELD DELINEATION. THE MAP DOES NOT IN ANY WAY REPRESENT A JURISDICTIONAL DETERMINATION OF THE LANDWARD LIMITS OF WATERS AND WETLANDS WHICH MAY BE REGULATED BY THE USACE OR THE WVDEP. IT IS STRONGLY RECOMMENDED THAT THE AFORESAID AGENCIES BE CONSULTED IN AN EFFORT TO GAIN WRITTEN CONFIRMATION OF THE DELINEATION SHOWN ON THIS EXHIBIT PRIOR TO ENGAGING CONSTRUCTION ON THE PROPERTY DESCRIBED HEREIN. THE DEVELOPER SHALL OBTAIN THE APPROPRIATE PERMITS FROM THE FEDERAL AND/OR STATE REGULATORY AGENCIES PRIOR TO ANY PROPOSED IMPACTS TO WATERS OF THE U.S., INCLUDING WETLAND FILLS AND STREAM CROSSINGS.

**GEOTECHNICAL NOTES:**

A SUBSURFACE INVESTIGATION OF THE PROPOSED SITE WAS PERFORMED BY PENNSYLVANIA SOIL & ROCK, INC. ON MARCH 19 - MAY 22, 2019, AND REVISED FEBRUARY 19, 2020. THE REPORT PREPARED BY PENNSYLVANIA SOIL & ROCK, INC. DATED MAY 24, 2019, AND REVISED MAY 27, 2020, REFLECTS THE RESULTS OF THE SUBSURFACE INVESTIGATION. THIS INFORMATION AND RECOMMENDATIONS CONTAINED IN THIS REPORT WERE USED IN THE PREPARATION OF THESE PLANS. PLEASE REFER TO THE SUBSURFACE INVESTIGATION REPORT BY PENNSYLVANIA SOIL & ROCK, INC. FOR ADDITIONAL INFORMATION, AS NEEDED.

**PROJECT CONTACTS:**

**ANTERO:**  
 ANTERO RESOURCES CORPORATION  
 535 WHITE OAK BLVD.  
 BRIDGEPORT, WV 26036  
 PHONE: (864) 842-4100  
 FAX: (204) 842-4102

**ELI WAGNER - ENVIRONMENTAL ENGINEER & REGULATORY MANAGER**  
 OFFICE: (304) 842-4058 CELL: (204) 478-9770

**DIANA HOFF - SVF OPERATIONS**  
 OFFICE: (304) 367-6804

**AARON KUNZLER - CONSTRUCTION MANAGER**  
 CELL: (304) 842-4181

**ROBERT WIKES - DESIGN MANAGER**  
 OFFICE: (304) 842-4108 CELL: (304) 827-7405

**CHARLES E. COMPTON, III - UTILITY COORDINATOR**  
 (304) 739-8449

**MARK HUTSON - LAND AGENT**  
 CELL: (304) 889-8315

**ENGINEER/SURVEYOR:**  
 NAVITUS ENGINEERING, INC.

**CYRUS S. KUMF, PE - PROJECT MANAGER/ENGINEER**  
 OFFICE: (888) 864-4188 CELL: (240) 895-6747

**ENVIRONMENTAL:**  
 ALLSTAR ECOLOGY, LLC

**RYAN L. WARD - ENVIRONMENTAL SCIENTIST**  
 (868) 213-2686 CELL: (304) 692-7477

**GEOTECHNICAL:**  
 PENNSYLVANIA SOIL & ROCK, INC.

**CHRISTOPHER W. SANDS - PROJECT ENGINEER**  
 (412) 376-4000 CELL: (412) 589-0562

**RESTRICTIONS NOTES:**

1. THERE ARE NO PERENNIAL STREAMS, LAKES, PONDS, OR RESERVOIRS WITHIN 100 FEET OF THE WELL PAD AND LOD. THERE ARE WETLANDS ADJACENT TO STOCKPILES WHICH WILL REMAIN UNDEVELOPED.
2. THERE ARE NO NATURALLY PRODUCING TROUT STREAMS WITHIN 200 FEET OF THE WELL PAD AND LOD.
3. THERE ARE NO GROUNDWATER INTAKE OR PUBLIC WATER SUPPLY FACILITIES WITHIN 1000 FEET OF THE WELL PAD AND LOD.
4. THERE ARE NO APPARENT EXISTING WATER WELLS OR DEVELOPED SPRINGS WITHIN 250 FEET OF THE WELLS) BEING DRILLED.
5. THERE ARE NO OCCUPIED DWELLING STRUCTURES WITHIN 625 FEET OF THE CENTER OF THE WELL PAD.
6. THERE ARE NO AGRICULTURAL BUILDINGS LARGER THAN 2,600 SQUARE FEET WITHIN 625 FEET OF THE CENTER OF THE WELL PAD.

**REPRODUCTION NOTE**

THESE PLANS WERE CREATED TO BE PLOTTED ON 24"X36" (ANSI D) PAPER. HALF SCALE DRAWINGS ARE ON 11"X17" (ANSI B) PAPER. THESE PLANS WERE CREATED FOR COLOR PLOTTING AND ANY REPRODUCTION IN GRAY SCALE OR COLOR MAY RESULT IN A LOSS OF INFORMATION AND SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES.


# HEINTZMAN WELL PAD

## SITE DESIGN & CONSTRUCTION PLAN, EROSION & SEDIMENT CONTROL PLANS

ELLSWORTH DISTRICT, TYLER COUNTY, WEST VIRGINIA  
 POINT PLEASANT CREEK & ELK FORK WATERSHEDS  
 USGS 7.5 PADEN CITY & PORTER FALLS QUAD MAPS



WEST VIRGINIA STATE PLANE COORDINATE SYSTEM  
 NORTH ZONE  
 ELEVATION BASED ON ANTERO  
 POST-PROCESSING



(NOT TO SCALE)

**DESIGN CERTIFICATION:**

THE DRAWINGS, CONSTRUCTION NOTES, AND REFERENCE DIAGRAMS ATTACHED HERETO HAVE BEEN PREPARED IN ACCORDANCE WITH THE WEST VIRGINIA CODE OF STATE RULES, DIVISION OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS CR 35-B.

MISS Utility of West Virginia  
 1-800-245-4848  
 West Virginia State Law  
 (Section XIV: Chapter 24-C)  
 Requires that you call two business days before you dig in the state of West Virginia.  
**IT'S THE LAW!!**

**SHEET INDEX:**

- 1 - COVER SHEET
- 2 - NOTES
- 3 - LEGEND
- 4 - MATERIAL QUANTITIES
- 5 - STORM DRAINAGE & P&S COMPUTATIONS
- 6 - EXISTING CONDITIONS
- 9 - EXISTING STRUCTURES & FEATURES
- 9 - OVERALL PLAN SHEET INDEX & VOLUMES
- 10-11 - ACCESS ROAD PLAN
- 12 - ACCESS ROAD & WATER CONTAINMENT PAD PLAN
- 13 - ACCESS ROAD & WELL PAD PLAN
- 14-19 - ACCESS ROAD PLAN
- 17 - WELL PAD PLAN
- 18-19 - STOCKPILE PLAN
- 20 - WELL PAD GRADING PLAN
- 21-25 - ACCESS ROAD PROFILES
- 26 - WELL PAD SECTION
- 27 - STOCKPILE SECTIONS
- 28-38 - CONSTRUCTION DETAILS
- 37-38 - ACCESS ROAD RECLAMATION PLAN
- 39 - ACCESS ROAD & WATER CONTAINMENT PAD RECLAMATION PLAN
- 40 - ACCESS ROAD & WELL PAD RECLAMATION PLAN
- 41-43 - ACCESS ROAD RECLAMATION PLAN
- 44 - WELL PAD RECLAMATION PLAN
- 45-49 - STOCKPILE RECLAMATION PLAN
- GE500-02505 - GEOTECHNICAL DETAILS

HEINTZMAN LOTS OF IMPURANCE AREA (AC)	
<b>Total Site</b>	
Access Road "A" (3,932')	16.60
Well Pad	7.52
Excess/Topsoil Material Stockpiles	31.81
<b>Total Affected Area</b>	<b>56.03</b>
Total Wooded Acres Disturbed	46.55
<b>Impacts to Parkers Acre Heintzman TR 10-3</b>	
Total Affected Area	0.95
Total Wooded Acres Disturbed	0.95
<b>Impacts to Daniels R. &amp; Clats A. Heintzman TR 8-36</b>	
Access Road "D" (2,965')	11.62
Well Pad	5.63
Excess/Topsoil Material Stockpiles	28.51
<b>Total Affected Area</b>	<b>46.76</b>
Total Wooded Acres Disturbed	37.53
<b>Impacts to Daniels R. &amp; Clats A. Heintzman TR 8-48</b>	
Access Road "D" (389.00')	4.03
Well Pad	1.13
Excess/Topsoil Material Stockpiles	3.10
<b>Total Affected Area</b>	<b>8.26</b>
Total Wooded Acres Disturbed	7.02
<b>Impacts to Stefan L. &amp; Alberta B. Smolkin TR 10-4</b>	
Well Pad	1.06
<b>Total Affected Area</b>	<b>1.06</b>
Total Wooded Acres Disturbed	1.06

WELL NAME	WV Well ID (ARC 27)	MD 27.83 R. 1000'	LOT/ELEV (ELEV) - 2245.17'	ARC 83.18 R. 1,000'
Dwelling/Erosion				
Leap Unit TH	N 38789.47	LAT 39-32-34.8150	N 437705.79	LAT 78-51-35.0982
Leap Unit TH	E 101946.15	LONG -80-51-21.0706	E 512400.89	LONG -80-52-26.4578
Leap Unit 24	N 38788.11	LAT 39-32-34.9417	N 437701.75	LAT 78-52-34.9857
Leap Unit TH	E 101783.09	LONG -80-51-20.8867	E 512402.87	LONG -80-51-30.3626
Member Unit TH	N 38742.82	LAT 39-32-34.2643	N 437704.73	LAT 78-52-34.8353
Member Unit TH	E 101760.23	LONG -80-51-20.8218	E 512406.26	LONG -80-51-20.2714
Member Unit TH	N 38729.55	LAT 39-32-34.4298	N 437703.72	LAT 78-52-34.4649
Member Unit 24	E 101768.38	LONG -80-51-20.8294	E 512407.24	LONG -80-51-20.1822
Normal Unit 14	N 38719.22	LAT 39-32-34.2006	N 437708.70	LAT 78-52-34.8761
Normal Unit 14	E 101787.82	LONG -80-51-20.7152	E 512409.42	LONG -80-51-20.0901
Normal Unit 24	N 38702.93	LAT 39-32-34.1832	N 437705.09	LAT 78-52-34.4442
Normal Unit 24	E 101767.98	LONG -80-51-20.8248	E 512411.81	LONG -80-51-19.9878
Heintzman Unit 14 (Heintzman) AP# 17-225-23512	N 38773.49	LAT 39-32-34.4625	N 437706.90	LAT 78-52-34.7339
Heintzman Unit 14 (Heintzman) AP# 17-225-23512	E 101785.88	LONG -80-51-21.2111	E 512407.54	LONG -80-51-20.0466
Proposed Well Pad Elevation		1,890.0		



DATE	REVISION	REVISION PER WYDEP COMMENTS	REVISION PER WELL PAD & STOCKPILE	REVISION FOR PARTIAL CONSTRUCTION	REVISION PER WELL PAD	REVISION PER P&S	REVISION PER EAS	REVISION PER WELLS
05/01/2019								
11/01/2018								
05/01/2020								
06/15/2021								
06/15/2020								
04/07/2020								

COVER SHEET  
**HEINTZMAN WELL PAD**  
 ELLSWORTH DISTRICT  
 TYLER COUNTY, WEST VIRGINIA



DATE: 03/16/2019  
 SCALE: AS SHOWN  
 SHEET 1 OF 48

Stephen May @1/6/22