

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

To The Department of Mines
Charleston, W. Va.

Joe. Harlow Jr.

Union Bank Building
Pittsburgh, Penna.

Address

COAL OPERATOR OR COAL OWNER

Address

Waneco Corporation

OWNER OF MINERAL RIGHTS

Wheeling, West Va.

Address

Government

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas having fee title thereto, (or as the case may be) under grant or lease dated October 21, 1910 made by Waneco Corporation to Pittsburgh & West Va Gas Company, and recorded on the 27 day

of December 1910 in the office of the County Clerk for said County in Book 30-A page 309

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Mineral District and County above named, determined by survey and courses and distances from two permanent points or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Code, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by or filed with the Department of Mines within ten days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must be set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)
Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above named coal operators or coal owners at their above shown respective addresses _____ day before _____ or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston West Virginia.

Very truly yours,
PITTSBURGH & WEST VA GAS COMPANY

WELL OPERATOR
408 Union M. W. Bank Bldg.
Street
City or Town
West Va.

Section 3 of the Code of West Virginia provides that in each objection be filed or be found by the department of mines, within said period of ten days from the receipt of said notice and that by the department of mines to said proposed location, the operator shall forthwith issue to the well operator a ruling permit reciting the title of such plat, that no objections have been made by the coal operators to the location of the well, and that the same is approved and the well operator authorized to proceed to drill at said location.

10/06/2023

A-10

PITTSBURGH AND WEST VIRGINIA GAS COMPANY

455 SIXTH AVENUE

PITTSBURGH, PENNSYLVANIA

Clarksburg, West Va.,
September 28, 1942.

West Virginia Department of Mines
Oil and Gas Division.
Charleston, West Va.,

Dear Mrs. Griffith:

We enclose you herewith Form OG-1,
Notice of proposed location of oil and gas well, and
well location map showing proposed location of Well
No. 5427, Nampeco Corporation farm, Grant District,
Wetzel County, West Va.,

Very truly yours,
PITTSBURGH & WEST VA GAS COMPANY.

F. E. Bridgen
F. E. Bridgen

FEB/M



10/06/2023

11/10

PITTSBURGH AND WEST VIRGINIA GAS COMPANY

ASSOCIATED STATES
PITTSBURGH AND WEST VIRGINIA GAS COMPANY


Charleston, West Va.,
September 28, 1912.

West Virginia Department of Mines
Oil and Gas Division
Charleston, West Va.,

Dear Mr. Griffith:

We enclose you herewith Form OG-1,
Notice of proposed location of oil and gas well, and
well location map showing proposed location of well
No. 2427, Hampshire Corporation farm, Grand District,
Wetzel County, West Va.

Very truly yours,
PITTSBURGH AND WEST VIRGINIA GAS COMPANY.



FEB 11

A-11

October 9, 1942

Pittsburgh & W. Va. Gas Company
Clarksburg, West Virginia

Gentlemen:

Permit WET-287 to drill Well No. 5427 on the
Nampeco Corporation Farm, Grant District, Wetzel County,
is enclosed.

Very truly yours,

Secretary
OIL AND GAS DIVISION

MG/jh
enc-2

CC: Inspector D. G. Courtney

10/06/2023

A-12

PITTSBURGH AND WEST VIRGINIA GAS COMPANY

~~36 SIXTH AVENUE~~

~~PITTSBURGH PENNSYLVANIA~~

Clarksburg, West Va.,
January 25, 1943.

*File Wet-287
JC
1*

West Virginia Department of Mines
Oil and Gas Division.
Charleston, West Va.,

Dear Mrs. Griffith:

We enclose you herewith Form OG-10,
Well Record on Well No.5427, Nampeco Corporation farm,
Grant District, Wetzel County, West Va.,

Very truly yours,
PITTSBURGH WEST VA GAS COMPANY.

F. E. Bricker
F. E. Bricker

FEB/M



PITTSBURGH AND WEST VIRGINIA GAS COMPANY

XXXXXXXXXXXXXXXXXXXX
XXXXXXXXXXXXXXXXXXXX
Clarksburg, West Va.,
January 25, 1943.

West Virginia Department of Mines
Oil and Gas Division,
Charleston, West Va.,

Dear Mrs. Griffith:

We enclose you herewith Form 00-10,
Well Record on Well No. 5427, Hancock Corporation farm,
Grant District, Wayne County, West Va.

Very truly yours,
PITTSBURGH AND WEST VIRGINIA GAS COMPANY.

[Handwritten signature]
F. B. [unclear]



B-2

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock	Red	Soft	1189	1200			
Slate-Shells	Dark	"	1200	1313			
Lime	White	Hard	1313	1331			
Slate&Shells	Gray	Soft	1331	1362			
Lime	White	Hard	1362	1382			
Slate-Shells	Dark	Soft	1382	1395			
Big Dunkard	White	Hard	1395	1424			
Slate-Shells	Dark	Soft	1424	1508			
Lime	White	Hard	1508	1536			
Slate-Shells	"	Soft	1536	1550			
Lime	"	Hard	1550	1610			
Gas Sand	"	Medium	1610	1673			
Slate&Shells	Dark	Soft	1673	1728			
1st. Salt Sd.	White	Hard	1728	1772			
Slate	Black	Soft	1772	1790	Water	1751'	3 Bailers Hr. S.L. 1740'
2nd. Salt Sand	White	Hard	1790	1810			
Slate&Shells	Dark	Soft	1810	1880			
3rd. Salt Sand	White	"	1880	1964	Water	1924'	5 Bailers Hr.
Slate-Shells	"	"	1964	1990			
4th. Salt Sand	"	"	1990	2007			
Slate-Shells	Dark	"	2007	2068			
Red Rock	Red	"	2068	2072			
Lime	White	Hard	2072	2103			
Red Rock	Red	Soft	2103	2105			
Slate Shells	White	Medium	2105	2151			
Little Lime	"	Hard	2151	2167			
Slate	"	Soft	2167	2178			
Big Lime	"	Hard	2178	2230			S.L. 2188'
Big Injun	"	Hard	2230	2453	Gas	2333-2335'	4/10 Water 1"
Slate&Shells	Dark	Medium	2453	2932	"	2344-2348'	6/10 Water 1"
30 Ft. Sand	White	Hard	2932	2949	Sh. Oil	2344-2348'	
Slate-Shells	"	Soft	2949	3007			
Gordon Stray	"	Hard	3007	3050			S.L. 3040'
Slate-Shells	Dark	Hard&Soft	3050	3090			
Gordon Sand	White	Hard	3090	3103	Gas	3092-3095'	6 1/10 Water in 1-1/2" F.M.
Slate&Shells	"	Soft	3103	3372			
Total Depth				3372'			

10/06/2023

Date January 25, 1943, 194

APPROVED PITTSBURGH & WEST VA GAS COMPANY, Owner

By F. E. Hagedorn (Title)

B-1 Littleton S.E.

STATE OF WEST VIRGINIA DEPARTMENT OF MINES OIL AND GAS DIVISION

WELL RECORD

Permit No. WET-287


Oil or Gas Well GAS (KIND)

Company Pittsburgh & West Va Gas Company. Address Clarksburg, West Va., Farm Nampeco Corporation Acres 114 Location (waters) Littleton S/E. 3-2 Well No. 5427 Elev. 1250' VA District Grant County Wetzel The surface of tract is owned in fee by W. Fairfield Peterson Address Wheeling, W. Va., Mineral rights are owned by Nampeco Corporation Address Wheeling, W. Va., Drilling commenced November 16, 1942 Drilling completed January 16, 1943 Date Shot From To With Open Flow 30 /10ths Water in 1-1/2" Inch /10ths Merc. in Inch Volume 114,000 Cu. Ft. Rock Pressure 444 lbs 48 hrs. Oil bbls., 1st 24 hrs. Fresh water feet feet Salt water feet feet

Table with columns: Casing and Tubing, Used in Drilling, Left in Well, Packers. Rows include sizes 16, 18, 10, 8 1/4, 6, 5 3/16, 3, 2 and packer details like Kind of Packer, Size of, Depth set, Perf. top/bottom.

CASING CEMENTED SIZE No. Ft. Date COAL WAS ENCOUNTERED AT 625 FEET 24 INCHES 868 FEET 24 INCHES 970 FEET 60 INCHES

Main stratigraphic log table with columns: Formation, Color, Hard or Soft, Top, Bottom, Oil, Gas or Water, Depth Found, Remarks. Lists various geological layers from Clay to Slate&Shell with depths and remarks like '1 Bailer Hr.' and 'S.L. 975'.



10/06/2023 S.L. 975'

