

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Ensminger, George Operator Well No.: Geo. W. Ensminger #3

LOCATION: Elevation: 981.48' Quadrangle: Big Run 7.5'
District: Grant County: Wetzel
Latitude: 39.52483 Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: -80.52246 Feet West of _____ Deg. _____ Min. _____ Sec.

RECEIVED
Office Of Oil and Gas

NOV 25 2025

WV Department of
Environmental Protection

Well Type: OIL _____ GAS x

Company Diversified Production, LLC Coal Operator American Consolidated Natural Resources, Inc.
414 Summers Street or Owner 46226 National Rd.
Charleston, WV 25301 St. Clairsville, OH 43950
Agent Chris Veazey Coal Operator West Virginia Land Resources, Inc.
Permit Issued Date 10/10/25 or Owner 46226 National Road West
St. Clairsville, OH

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Michael Proctor and Timothy Hicks being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22nd day of October, 2025, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
75 sks Expanding Cement	2164'	1600'	2145' of rods	0'
16 sks Expanding Cement	1775'	1600'	2155' of 2 3/8"	0'
84 sks Expanding Cement	1428'	988'	1444' of 5 1/2"	639'
59 sks Thixotropic	988'	582'	0' of 7"	Unknown
20 sks Thixotropic	720'	582'		
105 sks Expanding Cement	582'	0'		

Description of monument: Steel Casing W/API # welded on at least 36" above ground and that the work of plugging and filling said well was completed on the 6th day of November, 2025.

And further deponents saith not. [Signature]

Sworn and subscribe before me this 19 day of November, 2025

My commission expires: 7/21/29



Notary Public

Stephen Mccoy

Digitally signed by Stephen Mccoy
Date: 2025.11.24 08:51:57 -05'00'

Affidavit reviewed by the Office of Oil and Gas:

Title: _____

11/28/2025