

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Fairfield Peterson Operator Well No.: 7198

LOCATION: Elevation: 1256.02' Quadrangle: Folsom W.VA

District: Grant County: Wetzel

Latitude: _____ Feet South of 39 Deg. 29 Min. 45.58 Sec.

Longitude: _____ Feet West of -80 Deg. 30 Min. 48.19 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 08/16/2021

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:


Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of September, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/Green Dye and Gas Blocker	1322'	894'		
Expandable Cement	894'	0'		
8 5/8" Casing	76'	Unknown	17'	Unknown
10 3/4" Casing	Surface	83'	0'	83'
16" Conductor	Surface	60'	0'	60'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 11th day of November, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright



Sworn and subscribe before me this 30th day of NOV, 2021

My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/08/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CNX LAND LLC
Lease or Property Owner
1000 CONSOL ENERGY DRIVE CANONSBURG, PA 15317
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

FOLSOM, W.VA
Well Location

GRANT
District

WETZEL
County

7198
Well No.

FAIRFIELD PETERSON
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of September, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 14 3/4" hole from surface to 59'. Tagged top of the existing 8 5/8" casing at 59'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 59' to 1321'. Removed 17' of 8 5/8" casing from 59' to 76'. Attempted to remove remaining 8 5/8" casing by pulling 150% of string weight. All attempts to remove remaining 8 5/8" casing were unsuccessful. Left unknown amount of 8 5/8" casing from 76' to unknown depth. Cut remaining 8 5/8" casing at 1298', 1251', 1201', 1151', 1111', 1106', 1101', 1098.5', 1096.5', 1094', 1089', 1084', 1045', and 995'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1093.9' - 1100.3'). Left 83' of 10 3/4" casing in the hole from the surface to 83'. Left 60' of 16" conductor pipe in the hole from the surface to 60'. Cemented the hole from 1321' to the surface as follows: From 1321' to 882' with 130 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. From 894' to surface with 260 sacks of Expandable Cement. Cement did circulate at the surface. A total of 390 sacks of cement were used to fill the hole from 1322' to the surface.	8 5/8" Casing	17'	Unknown	
		10 3/4" Casing	0'	83'
		16" Conductor	0'	60'
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	1093.9' - 1100.3'			
	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 11th day of November, 2021

And further deponents saith not.



Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 30th day of NOV, 2021

[Signature] 04/08/2022
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-01073
Well No. 7198
Latitude: 39° 29' 45.58"N
Longitude: -80° 30' 48.19"W