

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COLUMBIA GAS TRANSMISSION CORP.
Lease or Property Owner
P.O. Box 498 Washington, PA 15301
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED, W.VA
Well Location
CHURCH
District
WETZEL
County
8125
Well No.
MOSES BARTRUG
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCoy

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

MATTHEW A. YEARSLEY and **JOHN CAMPBELL** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of October, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Removed 1614' of 5 1/2" casing from surface to 1614'. Left 1691' of 5 1/2" casing from 1614' to 3305'. A diligent effort was made to remove remaining 5 1/2" casing by pulling 150% of the string weight. All attempts were unsuccessful. Perforated remaining 5 1/2" casing at 3206', 3110', 3009', 2905', 2085', 2705', 2605', 2505', 2405', 2303', 2200', 2106', 2005', 1905', 1800', and 1710'. Removed 1600' of 7" casing from surface to 1600'. A diligent effort was made to remove 7" casing starting at 1600' by pulling 150% of the string weight. All attempts were unsuccessful. Removed 1487' of 8 5/8" casing from surface to 1487'. A diligent effort was made to remove 8 5/8" casing starting at 1487' by pulling 150% of the string weight. All attempts were unsuccessful. Cleaned 9 7/8" hole from surface to 1276'. Cleaned 9 7/8" hole through Pittsburgh Coal Seam (1276' – 1282.5'). Cleaned a 9 7/8" hole from 1282.5' to 1487'. A diligent effort was made to remove 10 5/8" casing from surface to 194' by pulling 150% of the string weight. All attempts were unsuccessful. Left 20' of 16" conductor casing in the hole from 20' to surface.	5 1/2" Casing	1614'	1691'	
	7" Casing	1600'	Unknown	
	8 5/8" Casing	1487'	Unknown	
	10 3/4" Casing	0'	194'	
	16" Conductor Casing	0'	20'	
CONTINUED ON PAGE 2				
Coal Seams		Description of Monument		
Pittsburgh	1276' – 1282.5'	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 3rd day of November, 2023

And further deponents saith no:



Matthew A. Yearsley

Matthew A. Yearsley

John Campbell

John Campbell

Sworn to and subscribed before me this 5th day of December 2023

Notary Public

My commission expires: August 17, 2025

Permit No. 47-103-01271
Well No. 8125
Latitude: 39° 39' 40.43"N
Longitude: -80° 24' 3.99"W

RECEIVED
Office of Oil and Gas

SEP 08 2025

WV Department of
Environmental Protection
09/12/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
COLUMBIA GAS TRANSMISSION CORP.
Lease or Property Owner
P.O. Box 498 Washington, PA 15301
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED, W.VA
Well Location
CHURCH
District
WETZEL
County
8125
Well No.
MOSES BARTRUG
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Wetzel ss:

MATTHEW A. YEARSLEY and **JOHN CAMPBELL**, being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of October, 2023 and that the well was plugged in the following manner:

Sand or Zona Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cemented Hole from 3331' to surface as follows:				
Cemented bottom hole from 3331' to 1600' with 235 sacks of Expandable Cement with Gas Blocker additive. Cemented intermediate plug from 1600' to 1076' with 275 sacks of Thixotropic Cement with Green Dye. Cemented from 1076' to surface with 440 sacks of Expandable Cement. Cement did circulate at the surface. A total of 950 sacks of cement were used to fill the hole from 3331' to surface.		5 1/2" Casing	1614'	1691'
		7" Casing	1600'	Unknown
		8 5/8" Casing	1487'	Unknown
		10 3/4" Casing	0'	194'
		16" Conductor Casing	0'	20'
Coal Seams		Description of Monument		
Pittsburgh	1276' - 1282.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 3rd day of November, 2023

And further deponents saith not



Matthew A. Yearsley
Matthew A. Yearsley

John Campbell
John Campbell

Sworn to and subscribed before me this 5th day of December, 2023

Notary Public

My commission expires: August 17, 2025

Permit No. 47-103-01271
Well No. 8125
Latitude: 39° 39' 40.43"N
Longitude: -80° 24' 3.99"W

09/12/2025