

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Stevens, S.C. Operator Well No.: 7512
LOCATION: Elevation: 944.22 Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.5166004 Feet South of 39 Deg. 30 Min. 59.76 Sec.
Longitude: -80.5074739 Feet West of 80 Deg. 30 Min. 26.9064 Sec.

Well Type: OIL ☐ GAS ☒

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator
Permit Issued Date 01/03/2025 or Owner

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29th day of April, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ gas block	990'	571'	3/4" Cable - 1850'	0'
Expanding Cement	571'	Surface	2 3/8" Tubing - 3306'	0'
			5 1/2" Casing - 990'	Unknown
			7" Casing - 0'	Unknown
			16" Conductor Casing - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of May, 2025.

And further deponents saith not. Matthew A. Yearsley

Thomas Thrasher


Sworn and subscribe before me this 20th day of June, 2025

My commission expires: August 13, 2029

Kerri McCormick
Notary Public
Digitally signed by Stephen Mccoy
Mccoy
Date: 2025.06.23 08:56:54 -04'00'

Affidavit reviewed by the Office of Oil and Gas: Stephen Mccoy

Title:



RECEIVED
Office of Oil and Gas

JUN 23 2025

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
DOUGLAS SMITH
Lease or Property Owner
4464 MANNINGTON RD SMITHFIELD, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN WV
Well Location
GRANT
District
WETZEL
County
7512
Well No.
STEVENS, S.C.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT


STATE OF WEST VIRGINIA,

County of WETZEL ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29th day of April, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
<p>Pulled 3306' of 2 3/8" tubing and 1850' of 3/4" cable. Placed cut in 5 1/2" casing at 990'. Pulled 990' of 5 1/2" casing leaving an unknown amount of 5 1/2" casing in the hole. Made cuts in 7" casing at 977' and 787'. Made a diligent effort to remove 7" casing from surface to 787' by pulling 150% of string weight. All attempts to remove 7" casing were unsuccessful. Made cuts in 7" casing at 927', 877', 827', 782', 777', 775', 773', 771', 766', 761', 721', and 671'. Perforated the 7" casing at 787', 782', 777', 775', 773', 771', 766', and 761' using 6 shots at each location. Pittsburgh Coal Seam (771.0' – 777.0'). Left 20' of 16" conductor casing in hole from 20' to surface.</p> <p>Cemented hole from 990' to surface as follows: Cemented hole from 990' to 571' using 85 sacks of Thixotropic Cement with Green Dye and Gas Block Additive. Cemented hole from 571' to surface using 90 sacks of Expandable Cement. A total of 175 sacks of cement were used to fill the hole from 990' to surface. Cement did circulate at surface.</p>	3/4" Cable	1850'	0'	
	2 3/8" Tubing	3306'	0'	
	5 1/2" Casing	990'	Unknown	
	7" Casing	0'	Unknown	
	16" Conductor Casing	0'	20'	
Coal Seams		Description of Monument		
Pittsburgh	771.00' – 777.00'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of May, 2025



Sworn to and subscribed before me this

20th day of June 2025

Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-01435
Well No. 7512
Latitude: 39° 30' 59.76"W
Longitude: -80° 30' 26.9064"W

RECEIVED
Office of Oil and Gas

JUN 23 2025

WV Department of
Environmental Protection

Stephen McCoy

Digitally Signed by Stephen McCoy
Date: 2025.06.23 08:57:31 -04'00'