

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7290

LOCATION: Elevation: 954' Quadrangle: Big Run, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 34.39 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 56.53 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 01/30/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of March, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	993'	550'	8 5/8" Casing - 0' (Multiple Perforations)	Unknown
Expandable Cement	550'	Surface		


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 7th day of April, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribe before me this 15th day of May, 2023

My commission expires: June 8, 2027

Christopher Willis  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MAGNOLIA LAND PARTNERS  
Lease or Property Owner  
100 S. JUNIPER ST. (FLOOR 3) PHILADELPHIA, PA 19107  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7290  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16<sup>th</sup> day of March, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to top of existing 8 5/8" casing at 344'. Cleaned a 7 7/8" hole from 344' to 993'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (750.6' – 756.6'). Cut the existing 8 5/8" casing at 956.6'. A diligent effort was made to remove the existing 8 5/8" casing from 344' to 956.6' by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from the 344' to an unknown depth. Perforated the remaining 8 5/8" casing at the following depths: 906.6', 856.6', 806.6', 766.6', 761.6', 756.6', 754.6', 752.6', 750.6', 745.6', 740.6', 700.6' and 650.6'. Left 20' of 16" conductor pipe in the hole from the surface to 20'.		8 5/8" Casing	0'	Unknown
		16" Conductor	0'	20'
<b>Cemented the hole from 993' to the surface as follows:</b> From 993' to 550' with 130 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 550'. Cemented the hole from 550' to the surface with 345 sacks of Expandable Cement. Cement did circulate at the surface. A total of 475 sacks of cement were used to fill the hole from 993' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>750.6' – 756.6'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7<sup>th</sup> day of April, 2023

And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*


Kevin S. Wright

Sworn to and subscribed before me this 15<sup>th</sup> day of May, 2023

*[Signature]*  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-01569

Well No. 7290

Latitude: 39° 30' 34.39"N

Longitude: -80° 31' 56.53"W