

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7236

LOCATION: Elevation: 1078.96' Quadrangle: Big Run, WV  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 12.83 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 16.86 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 08/26/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1112'	847'		
Thixotropic Cement	847'	766'		
Expandable Cement	766'	Surface		
5 1/2" Casing			Milled 23'	0'
7" Casing	181'	856'	28'	675'
8 5/8" Casing	Surface	188'	0'	188'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 23rd day of September, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 11th day of Oct, 2022  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MAGNOLIA LAND PARTNERS LLC  
Lease or Property Owner  
104 S 20<sup>th</sup> ST STE A PHILADELPHIA, PA 19103  
Address

WEST VIRGINIA LAND RESOURCES, INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN, WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7236  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector 10/12/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, LLC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28<sup>th</sup> day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned out 7" casing with a 6 1/4 bit from the surface to the top of the 5 1/2" casing at 18'. Reduced the hole to 4 3/4" at 18'. Cleaned the hole with a 4 3/4" bit from 18' to 55'. A caliper log was ran to a depth of 55' and the caliper log indicated the 5 1/2" casing stopped at 41'. Due to cement bonding the existing 5 1/2" casing was pilot milled from 18' to 41'. Removed the existing 7" casing from the surface to 28. Cleaned the hole with a 12 1/4" bit from the surface to the top of the existing 7" casing at 181'. Several attempts were made to get inside the 7" casing at 181' but all attempts were unsuccessful. Ran 188' of 8 5/8" casing in the hole with an 11" shoe on the bottom to use as a guide to get inside the 7" casing. Cleaned out the existing 7" casing from 181' to 1112'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (866.3' - 872.7'). Attempted to remove remaining 7" casing from 181' by pulling 150% of the string weight but all attempts were unsuccessful. Left 675' of 7" casing in the hole from 181' to 856'. The remaining 7" casing was ripped at 855', 819', 804', 762', 719', and 658'. Left 20' of 16" casing in the hole from the surface to 20'.	5 1/2" Casing 7" Casing 8 5/8" Casing	Milled 23' 28' 0'	0' 675' 188'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	866.3' - 872.7'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 23<sup>rd</sup> day of September, 2021

And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley


*Kevin S. Wright*

Kevin S. Wright

Sworn to and subscribed before me this 11<sup>th</sup> day of Oct, 2021

*[Signature]* 09/20/2024  
Notary Public

My commission expires: 09/15/22



Permit No. 47-103-01572  
Well No. 7236  
Latitude: 39° 30' 12.83"N  
Longitude: -80° 32' 16.86"W