

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7287

LOCATION: Elevation: 1128' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 21.06 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 09.60 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 07/18/2023 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 23rd day of August, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1167'	747'	7" Casing - 0'	Unknown - Multiple cuts placed in remaining casing
Expandable Cement	747'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 14th day of September, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 25th day of September, 2023

My commission expires: June 8, 2027

Christopher Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
JAYME BAKER  
Lease or Property Owner  
840 BALDWIN AVE. ELYRIA, OH 44035  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7287  
Well No.  
I.D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KARLIE D. SMALLWOOD being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23<sup>rd</sup> day of August, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 287'. Cleaned a 9 7/8" hole from 287' to top of existing 7" casing at 434'. Cleaned a 6 1/4" hole from 434' to 1167'. Cut 7" casing at 1154' and 847'. A diligent effort was made to remove existing 7" casing by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 7" casing in the hole from 434' to an unknown depth. Cut remaining 7" casing at 1104', 1054', 1004', 964', 959', 954', 952.2', 950.5', 948.7', 947', 942', 937' and 897'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (947' - 954'). Left 20' of 16" casing in the hole from the surface to 20'.		7" Casing  16" Conductor	0'  0'	Unknown  20'
<b>Cemented the hole from 1167' to the surface as follows:</b> From 1167' to 747' with 90 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 747'. Cemented the hole from 747' to the surface with 320 sacks of Expandable Cement. Cement did circulate at the surface. A total of 410 sacks of cement were used to fill the hole from 1167' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>947' - 954'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 14<sup>th</sup> day of September, 2023

And further deponents saith not.


Matthew A. Yearsley  
Matthew A. Yearsley

Karlie D. Smallwood  
Karlie D. Smallwood

Sworn to and subscribed before me this 18<sup>th</sup> day of October, 2023

[Signature]  
Notary Public

My commission expires:  
June 8, 2027



Permit No. 47-103-01576  
Well No. 7287  
Latitude: 39° 30' 21.06"N  
Longitude: -80° 31' 09.60"W