

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Spencer Walters Operator Well No.: 7301

LOCATION: Elevation: 1105.37' Quadrangle: Big Run, W.VA
District: Grant County: Wetzel
Latitude: 39.512288 Feet South of 39 Deg. 30 Min. 44.236 Sec.
Longitude: -80.523231 Feet West of 80 Deg. 31 Min. 23.955 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 4/25/2023 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

Mathew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of October, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w Green Dye/Gas Becker	1112'	702'		
Expandable Cement	702'	0'		
8 5/8" Casing			0'	Unknown
10 3/4" Casing			0'	518'
16" Conductor			0'	20'

Description of monument: 77' of 7" casing with company name, well #, and date cemented and that the work of plugging and filling said well was completed on the 15th day of November, 2023.

And further deponents saith not. Matthew A. Yearsley
Thomas Thrasher



Sworn and subscribe before me this 12th day of December, 2023

My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
YVONNE R. MCFADDEN
Lease or Property Owner
249 Buck Run RD. Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run, WV
Well Location
GRANT
District
WETZEL
County
7301
Well No.
SPENCER WALTERS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of October, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from surface to top of existing 10 3/4" casing at 100'. Reduced to a 9 7/8" hole. Cleaned 9 7/8" hole from 618' to 902.5'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (902.5' - 909'). Cleaned a 9 7/8" from 909' to the top of existing 8 5/8" casing at 911'. Reduced to a 7 7/8" hole. Cleaned 7 7/8" hole from 911' to 1112'. Cut 8 5/8" casing at 1109'. A diligent effort was made to remove 8 5/8" casing from 911' to 1109' by pulling 150% of the string weight. All attempts were unsuccessful. Left an unknown amount of 8 5/8" casing from 911' to an unknown depth. Cut remaining 8 5/8" casing at 914', 919', 959', 1009' and, 1059'. Left 20' of 16" conductor pipe in the hole from 20' to surface.		8 5/8"	0'	Unknown
		10 3/4"	0'	518'
		16" Conductor	0'	20'
<u>Cemented Hole from 1112' to the surface as follows:</u> Cemented from 1112' to 702' with 175 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Cemented from 702' to the surface with 315 sacks of Expandable Cement. Cement did circulate at the surface. A total of 490 sacks of cement were used to fill the hole from 1112' to surface.				
Coal Seams		Description of Monument		
Pittsburgh	902.5' - 909'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 15th day of November, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 12th day of December, 2023

Christopher Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-01690
Well No. 7301
Latitude: 39° 30' 44.25"N
Longitude: -80° 31' 23.96"W