

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Mary R. Kocher Operator Well No.: 6352

LOCATION: Elevation: 1075.60 Quadrangle: Wallace, WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 30.58 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 29 Min. 12.30 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 11/02/2020

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 29th day of January, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	1197'	Surface		
7" Casing	504'	515'	0'	11'
16" Conductor Pipe	Surface	15'	0'	15'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 17th day of February, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 15<sup>th</sup> day of mar, 2021  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M Haught Title: Oil & Gas Inspector

06/04/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MARY R. KOCHER  
Lease or Property Owner  
185 MCDUGAL HOLLOW RD. SMITHFIELD, WV 26437  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

WALLACE, WV 7.5'  
Well Location

GRANT  
District

WETZEL  
County

6352  
Well No.

MARY R. KOCHER  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 29<sup>th</sup> day of January, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 319'. Reduced the hole to 9 7/8" at 319'. Cleaned the hole with a 9 7/8" bit from 319' to the top of the existing 7" casing at 504'. Reduced the hole to 6 1/4" at 504'. Cleaned the hole with a 6 1/4" bit from 504' to 1197'. Tagged a plug at 1197'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (971.5' - 978.1'). Left 11' of 7" casing in the hole from 504' to 515'. Left 15' of 16" conductor pipe in the hole from the surface to 15'.		16" Conductor	0'	15'
		7" Casing	0'	11'
<b>Cemented the hole from 1197' to surface as follows:</b> From 1197' to surface' with 580 sacks of Expandable Cement with a gas blocker additive. Cement did circulate at surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	971.5' - 978.1'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 17<sup>th</sup> day of February, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 18<sup>th</sup> day of Mar, 2021

[Signature]  
Notary Public

06/04/2021

My commission expires: 09/15/22

Permit No. 47-103-01848  
Well No. 6352  
Latitude: 39° 29' 30.58"N  
Longitude: -80° 29' 12.30"W