

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Consolidation Coal Co.
Coal Operator or Owner
PO Box 100, Osage, WV 26543
Address
Coal Operator or Owner
Address
Eva Mae Liggett
Lease or Property Owner
RD. 1, Smithfield WV 26437
Address

Consolidation Coal Co.
Name of Well Operator
PO Box 100, Osage, WV 26543
Complete Address
Wallace
Well Location
Grant
District
Wetzel
County
6366
Well No.
Liggett, Eva Mae
Farm

STATE INSPECTOR SUPERVISING PLUGGING:

Steven A. Morrison

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Kevin Wright and Byron L. Musselman being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of August, 2002 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 14" hole from surface to 273'. Reduced hole to 9 7/8", cleaned 9 7/8" hole from 273' to 513', top of 8 5/8" csg. Reduced hole to 7 7/8", cleaned 7 7/8" hole from 513' to 1692. Pulled 8 5/8" csg from 513' to 1386'. Cleaned 9 7/8" hole from 513' to 1384'. Cleaned 9 7/8" hole thru Pittsburgh Coal-1257' to 1264'. Cement hole solid from 1692' back to surface. Cement hole as follows: from, 1692' to 1464' and from 1157' back to surface with 393 sks. high yield lite, and from 1464' to 1157' with 120 sks. thix with dye.			8 5/8" – 873'	306'
Coal Seams	Pittsburgh Coal 1257' – 1264'	Description of Monument		
(Name)		7" well marker 77" long with Consol Coal Co.,		
(Name)		well number, permit number, date and solid plug		
(Name)		stated on 7" well marker. Well marker will be		
(Name)		attached to solid cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 11th day of September, 2002


And further deponents saith not.

Byron L. Musselman
Kevin S. Wright

Sworn to and subscribed before me this 18th day of September 2002

Kathleen M. Blake
Notary Public

My commission expires:



Permit No. 47-103-01895P

09/05/2025