

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

JAN 18 2022 3

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Watson, Ernest Jack & Nancy Operator Well No.: 516119 Ernest Watson Unit 1V

LOCATION: Elevation: 1,391' Quadrangle: 438 - Littleton 7.5'
District: 3 - Clay County: WETZEL
Latitude: 2,700 Feet South of 39 Deg. 42 Min. 30.0 Sec.
Longitude: 13,740 Feet West of 80 Deg. 32 Min. 30.0 Sec.

Well Type: OIL _____ GAS X

Company EQT Production Company Coal Operator _____
400 Woodcliff Drive or Owner Western Pocahotas Properties Limited Partnership
Canonsburg PA 15317 5260 Irwin Road
Coal Operator Huntington WV 25727-3247
Agent Joseph C. Mallow or Owner CBC Holdings LLC
Permit Issued Date March 30th, 2021 12088 Middle Island Road, Alma WV 26320-7211

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

JUSTIN C. FARRAR and JOE ARBOGAST being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of October, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
34 SKS CMT (class A)	7390'	6890'	3690' 4 1/2" casing	4,033' 4 1/2 casing
GEL Spacer	6890'	5305'		
75 SKS CMT (Class A)	5305'	5005'		
16# MUD	5005'	4500'		
135 SKS Class A CMT	4500'	3170'		# Perfs 5310', 4500', 3710' in 4 1/2"
Gel Spacer	3170'	2915'		# CIBP 7496' and 7390' in 4 1/2"
#CONT'D PAGE 2				# CIBP 2540' in 6 5/8"


Description of monument: 2'x2' plate on 6" casing, 6' above ground
said well was completed on the 5th day of January, 2022.

And further deponents saith not.

[Handwritten signatures of Justin C. Farrar and Joe Arbogast]

Sworn and subscribe before me this 30th day of January, 2022

My commission expires: 09-07-2022



Notary Public
Digitally signed by Stephen Mccoy
Date: 2023.01.11 20:58:56 -0500

Affidavit reviewed by the Office of Oil and Gas:

Stephen Mccoy

Title: WV Oil and Gas Inspector

03/10/2023

TYPE	FROM	TO	PIPE REMOVED	LEFT
120 SKS Class A CMT	2915'	2590'		
GEL Spacer	2590'	1415'		2715' 8 5/8 casing
60 SKS Class A CMT	1415	1215'		600' 11 3/4 casing
Gel Spacer	1215'	950'		40' of 16" casing
120 SKS Class A CMT	950'	500'		# 8 5/8 casing jet cut at 200'
Gel Spacer	500'	350'		
120' SKS Class A CMT	350'	0		

Surface Owner:

Ernest Jack Watson & Nancy Lee Watson

145 Watson Lane

Littleton, WV 26581-7745